


OHIO HISTORIC INVENTORY

Ohio Historic Preservation Office
Ohio Historical Center
Columbus, Ohio 43211

1. No.		4. Present Name(s) Residence, J. Penniston		1. No.	
2. County Summit		5. Other Name(s)			2. County Summit
3. Location of Negatives HHA 5-32,33,34					
6. Specific Location 166 Hudson Street		16. Thematic Category D		28. No. of Stories 2	
7. City or Town If Rural, Township & Vicinity Hudson		17. Date(s) or Period c. 1931		29. Basement? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	
8. Site Plan with North Arrow 		18. Style or Design Colonial Revival		30. Foundation Material concrete block	
9. Coordinates Lat. _____ Long. _____ U.T.M. Reference 17 463 823 4566030		19. Architect or Engineer		31. Wall Construction wood frame	
10. Zone Easting Northing Site <input type="checkbox"/> Structure <input type="checkbox"/> Building <input checked="" type="checkbox"/> Object <input type="checkbox"/>		20. Contractor or Builder		32. Roof Type & Material gable - asph shingle	
11. National Register? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		21. Original Use, if apparent residence		33. No. of Bays Front 3 Side 3	
12. Is it Eligible? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		22. Present Use residence		34. Wall Treatment beveled siding	
13. Part of Estab. Yes <input checked="" type="checkbox"/> Hist. Dist.? No <input type="checkbox"/>		23. Ownership Public <input type="checkbox"/> Private <input checked="" type="checkbox"/>		35. Plan Shape rect	
14. District Potent'l? Yes <input type="checkbox"/> No <input type="checkbox"/>		24. Owner's Name & Address, if known J. Penniston 166 Hudson Street Hudson 44236		36. Changes (Explain in #42) Addition <input checked="" type="checkbox"/> Altered <input type="checkbox"/> Moved <input type="checkbox"/>	
15. Name of Established District Hudson Local Historic District		25. Open to Public? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		37. Condition Interior _____ Exterior <u>good</u>	
15. Name of Established District Hudson Local Historic District		26. Local Contact Person or Organization Hudson Heritage Association		38. Preservation Underway? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	
42. Further Description of Important Features Enclosed entrance, four pilasters on enclosure; dropped shed roof screened porch at rear southwest; shed dormer at rear with triple casement windows; 20-pane fixed window, flanked by 10 pane casement windows, on front facade; triple 8-pane casement windows at each side of entry enclosure; 10/10 windows, second story, front facade; two additions to east; lunette in side gable; attached garage.		27. Other Surveys in Which Included		39. Endangered? Yes <input type="checkbox"/> By What? <u>No <input checked="" type="checkbox"/></u>	
43. History and Significance				40. Visible from Public Road? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	
44. Description of Environment and Outbuildings Quiet residential street, little traffic.				41. Distance from and Frontage on Road 40' 95'	
Sources of Information Summit County Tax Assessment records Personal inspection		46. Prepared by L Newkirk F Barlow		5. Other Name(s) Photo	
		47. Organization HHA			
		48. Date			
		49. Revision Date(s)			

SITE PLAN SURVEY


OF
166 HUDSON STREET
HUDSON, OHIO
 KNOWN AS
PN 3201342

SITUATED IN PART OF ORIGINAL HUDSON TOWNSHIP LOT 56, COUNTY OF SUMMIT, STATE OF OHIO.

TBM ELEVATION: 1116.28- Top Nut of Hydrant 100' East of Subject
 FINISHED FIRST FLOOR ELEVATION: 1116.17 FINISHED BASEMENT FLOOR ELEVATION: 1107.17
 TOP OF FOOTER ELEVATION: 1107.84 FINISHED GARAGE FLOOR ELEVATION: 1114.17
 TOP OF FOOTER ELEVATION (CRAWL SPACE): 1110.39
 SANITARY CONNECTION ELEVATION: REUSE STORM CONNECTION ELEVATION: N/A




CONTRACTOR TO VERIFY BEFORE STARTING CONSTRUCTION:
 1. FIN. FLOOR ELEVATION & HOUSE SIZES
 2. LOCATION & ELEVATIONS OF EXISTING UTILITY CONNECTIONS
 SILT FENCE TO BE UTILIZED AT THE DIRECTION OF HUDSON, WASHOUT AND STOCKPILE AREA
 ALL PROPOSED STORM LINES TO BE PVC SDR 35.
 BACKFLOW PREVENTION REQUIRED FOR SUMP PUMP OUTLET LINE.
 OUPS DESIGN TICKET NO. A7120438 DSGN - SOME, NON RESPONSIVE AT TIME OF SURVEY
 NO SOILS SHALL BE DEPOSITED ONTO ADJACENT PROPERTIES OR ROADWAY.



● - 5/8" BY 30" IRON PIN SET AND CAPPED "CASEY PROFESSIONAL SERVICES PS829"	(R) RECORD	MH	MANHOLE
(M) - MONUMENT BOX FOUND	(C) CALCULATED	N	NORTH
○ - IRON PIN/PIPE FOUND	CL CENTERLINE	PG.	PAGE
(MH) - COMBINATION MANHOLE	CO CLEAN OUT	PERM.	PERMEABLE
● - PROPOSED YARD DRAIN	CONC. CONC.	PROP.	PROPOSED
○ - HYDRANT	CONN. CONNECTION	REC	RECORD
(W) - WATER VALVE	E EAST	R/W	RIGHT-OF-WAY
● - SPOT ELEVATION	FF FINISHED FLOOR ELEVATION	S	SOUTH
● - PROPOSED CLEANOUT	FF FLUSHING MANHOLE	SAN	SANITARY
● - PROPOSED TEST TEE	HP HIGH POINT	S.F.	SQUARE FEET
⊙ - GAS VALVE	L IRON	STM	STORM
--- CHAIN LINK FENCE	INV INVERT	TBM	TEMPORARY
--- DRAINAGE FLOW	LF LINEAR FEET	BENCHM.	BENCHMARK
	MIN. MINIMUM	T/C	TOP OF CURB
		TT	TEST TEE
		VOL.	VOLUME
		W	WEST


"THE UNDERGROUND UTILITIES SHOWN HAVE BEEN LOCATED FROM FIELD SURVEY INFORMATION AND EXISTING DRAWINGS. THE SURVEYOR MAKES NO GUARANTEE THAT THE UNDERGROUND UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN SERVICE OR ABANDONED. THE SURVEYOR FURTHER DOES NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED ALTHOUGH HE DOES CERTIFY THAT THEY ARE LOCATED AS ACCURATELY AS POSSIBLE FROM THE INFORMATION AVAILABLE. THIS SURVEYOR HAS NOT PHYSICALLY LOCATED THE UNDERGROUND UTILITIES." I HEREBY CERTIFY THAT THE BOUNDARIES AND EXISTING CONDITIONS SHOWN HEREON ARE THE RESULT OF A SURVEY DONE BY MYSELF ON MAY 3RD, 2017. THIS BOUNDARY RETRACEMENT SURVEY IS IN ACCORDANCE WITH THE OHIO ADMINISTRATIVE CODE CHAPTER 4733-37.



 1159 Holmden Avenue, Cleveland, OH 44109 216-781-4644 office & fax 216-299-9555 mobile www.caseyps.com	JOB NO.	17007
	PREPARED FOR:	James Hasson
	SCALE: 1"=20'	2
	DRAWN BY: SJC	2
	FIELD WORK DATE:	5/3/2017

TBM: 1116.28
 Top Nut of Hydrant

HUDSON STREET 60'
 (A PUBLIC RIGHT-OF-WAY)



Lot Coverage

- Patios, walkways and driveway = 2,685 SF
 - Decks = 200 SF
 - House = 3,950 SF
- Total = 6,835 SF**

Total Lot Area = 21,000 SF
Lot Coverage = 32%

Yard Drain #	Rim±	Invert±
YD 1	1113.8	1113.0
YD 2	1113.8	1112.6
YD 3	1113.8	1112.3
YD 4	1113.8	1112.1
YD 5	1112.7	1111.5
YD 6	1111.7	1111.1
YD 7	1111.7	1110.7
YD 8	1112.8	1111.7
YD 9	1111.4	1110.4

Existing Impervious Area:	4,148 SF
Existing Pervious Area:	14,669 SF
Proposed Impervious Area:	5,333 SF
Proposed Pervious Area:	13,484 SF





SELECT® RAILING

SHARE:  Save 



TREX SELECT® RAILING IN CLASSIC WHITE WITH ROUND ALUMINUM BALUSTERS IN CHARCOAL BLACK WITH A PEBBLE GREY COCKTAIL RAIL

Curb appeal, defined.





Trex Select® HIGH-PERFORMANCE COMPOSITE RAILING

railing: Select in Classic White

Rails:

- Top Rail
- Bottom Rail

Baluster: Square

Post: Trex Composite Post Sleeve

 This section features a white composite railing system installed on a deck. To the right of the railing image are three columns of product details. The first column, labeled 'Rails', shows two cross-sections: a 'Top Rail' and a 'Bottom Rail'. The second column, labeled 'Baluster', shows a 'Square' baluster. The third column, labeled 'Post', shows a 'Trex Composite Post Sleeve'.





