		City	y of Hudson, Ohio							
	0	DOT LPA Administration Support for the	SUM State Route 91	Nort	h Tur	n Lane F	Project,	PID 9382	22	
Phase by Week	Months	Description	Category	Weeks	Hours	Total Hours	Rate	Sub Totals		Totals
WOOK		PRECONSTRUCTION SERVICES		<u> </u>	<u> </u>					
		Pre-Construction Phase - 2020	Inspector 1	0	0	0	\$ 72.00	\$ -		
			Inspector 2	0	0	0	\$ 63.00	\$ -		
			CE 1/Doc Clerk/Communications	0	0	0	\$ 63.00	\$ -		
			EEO/DBE/Prevailing Wage	0	0	0	\$ 50.00	\$ -		
			PM/CPE	0	0	0	\$ 100.00	\$ -		
			Project Executive	0	0	0	\$ -	\$ -	\$	-
		PHASE 1 INSTALL DRAINAGE AND WIDENING WEST SIDE SR-91	la sa s stor d			•	Ф 70 00	Φ.		
		2020 Construction Phase - August 2020 to December 2020	Inspector 1	0	0	0	\$ 72.00 \$ 104.00	\$ - \$ -	ł	
			Inspector 1 OT Inspector 2	4	0 0	0 0	\$ 63.00	\$ -	ł	
			Inspector 2 OT	4	0	0	\$ 91.00	\$ -	ł	
			CE 1/Doc Clerk/Communications	2	0	0	\$ 63.00	\$ -		
			Soils & Aggregate Inspector	0	0	0	\$ 72.00	\$ -	1	
			Soils & Aggregate Inspector OT	0	0	0	\$ 104.00	\$ -	1	
			EEO/DBE/Prevailing Wage	0	0	0	\$ 50.00	\$ -	1	
			PM/CPE	0	0	0	\$ 100.00	\$ -	1	
			Project Executive	0	0	0	\$ -	\$ -	\$	-
			•			20:	20 TOTA	L BILLED	\$	45,785.24
								ase Order		
				2020					Ф	107,548.00
		PHASE 2 AND 3 2021		2020	PURC	HASE OR	DEK KE	MAINING	\$	(61,762.76)
21	5	2021 Construction March to August, 2021	Inspector 1	21	8	168	72.00	\$ 12,096.00		
		(Hudson to Supply All Inspection except Saturdays and Holidays)	Inspector 1 OT	21	2	42	104.00	\$ 4,368.00	1	
		(Inspector 1		8	8	72.00	\$ 576.00	1	
			Inspector 1 OT		2	4	104.00	\$ 416.00	1	
			Inspector 2	4	0	0	63.00	\$ -	1	
			Inspector 2 OT	4	0	0	91.00	\$ -	1	
			CE 1/Doc Clerk/Communications	21	30	630	63.00	\$ 39,690.00	1	
			Soils & Aggregate Inspector	21	20	420	72.00	\$ 30,240.00	1	
			Soils & Aggregate Inspector OT	21	0	0	104.00	\$ -		
			T&E Inspector TEC	21	4	84	103.83	\$ 8,721.72		
			EEO/DBE/Prevailing Wage	21	0	0	50.00	\$ -	ļ	
			PM/CPE	21	10	210	100.00	\$ 21,000.00		
			Project Executive	21	0.5	11	0.00	\$ -		
		POST CONSTRCTION PHASE PROJECT CLOSEOUT							\$	117,107.72
4	1	Post - Construction Phase - (30 cal days)	Inspector 1	4	0	0	72.00	\$ -		
•	•	. set sensition i mass (so our days)	CE 1/Doc Clerk/Communications	4	20	80	63.00	\$ 5,040.00	1	
			EEO/DBE/Prevailing Wage	4	0	0	50.00	\$ -	1	
			PM/CPE	4	10	40	100.00	\$ 4,000.00	1	
			Project Executive	4	4	16	0.00	\$ -	1	
			·						\$	9,040.00
		Reimbursable, Supplies, Marking Paint, Paper, Expenses	2021 Reimbursable						\$	3,000.00
		PSI Vehicles and Testing Consumables	Testing Laboratory Services						\$	8,720.00
	2021 TOTAL ESTIMATE									137,867.72
2020 PURCHASE ORDER REMAININ									\$	(61,762.76)
2021 TOTAL PURCHASE ORDER NEEDED										76,104.96
Z021 TOTAL FORCHASE ORDER NEEDED									Ψ	70,104.30