

OHIO
HUDSON

PUBLIC WORKS • 1769 Georgetown Road • Hudson, Ohio 44236 • (330) 342-1750

Cardinal Asphalt Company
Subject: 303 Emergency St. Repairs

ITEM/DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	EXTENSION
REMOVE AND REPLACE DAMAGED SECTION OF 303 AND REPLACE IT WITH 10" MS CONCRETE – INCLUDED WINTER PROTECTION	473	SY	153	72,369
MOBILIZATION AND MOT	1	LS	1000	1000
PAVEMENT MARKINGS	1	LS	2500	2500
BASE BID TOTAL				
CONTINGENCY ITEMS				
TRAFFIC LOOPS	2	EA	2200	4400
4" UNDERDRAIN	1	LF	25	25
6" UNDERDRAIN	1	LF	30	30
UNDERCUTTING / REMOVING AND REPLACING UNSUITABLE SUBBASE WITH 304 LIMESTONE	1	CY	110	110

Notes

- Work will be performed in two phases. The two inside lanes will be poured first followed by the two outside lanes.
-
- the city will set up the detour for Lennox.
- Remove and replace marked section of roadway includes the following items.
 - Saw cutting.
 - Pavement removal.
 - Subgrade compaction.
 - Adjust valve boxes and remove one.
 - Install dowel bar baskets and hook bolts.
 - Pour 10" of QCMS concrete.
 - Concrete cylinders.
 - Winter protection includes hot water, visqueen, and concrete blankets.
 - Replace dashed, channel, and double yellow lines removed during this work with water-based paint. Please note that we cannot guarantee how well the water base paint will adhere to the new concrete in cold temperatures.