


OHIO HISTORIC INVENTORY

Ohio Historic Preservation Office
Ohio Historical Center
Columbus, Ohio 43211

1. No.		4. Present Name(s) Residence, Thomas Kohl		1. NO.	
2. County Summit		5. Other Name(s)			2. COUNTY Summit
3. Location of Negatives HHA 34-5					
6. Specific Location 27 College Street		16. Thematic Category C		4. COUNTY Summit	
7. City or Town If Rural, Township & Vicinity Hudson		17. Date(s) or Period c. 1873			5. PRESENT NAME(S) Residence, Thomas Kohl
8. Site Plan with North Arrow 		18. Style or Design Gothic Revival		6. COUNTY Summit	
		19. Architect or Engineer			7. PRESENT NAME(S) Residence, Thomas Kohl
		20. Contractor or Builder		8. COUNTY Summit	
		21. Original Use, if apparent residence			9. PRESENT NAME(S) Residence, Thomas Kohl
		22. Present Use residence		10. COUNTY Summit	
9. Coordinates Lat. _____ Long. _____ U.T.M. Reference 7 463360 4525393		23. Ownership Public ☐ Private ☒			11. COUNTY Summit
		24. Owner's Name & Address, if known Thomas Kohl 27 College Street Hudson 44236		12. COUNTY Summit	
10. one Easting _____ Northing _____ 2. Site ☐ Building ☒ Structure ☐ Object ☐		25. Open to Public? Yes ☐ No ☒			13. COUNTY Summit
11. 1. Original Register? Yes ☒ No ☐ 12. Is it Eligible? Yes ☐ No ☐		26. Local Contact Person or Organization Hudson Heritage Association		14. COUNTY Summit	
13. Part of Estab. Hist. Dist.? Yes ☒ No ☐ 14. District Potent'l? Yes ☐ No ☐		27. Other Surveys in Which Included			15. COUNTY Summit
15. Name of Established District Hudson Historic District				16. COUNTY Summit	
16. Further Description of Important Features Barge board; front section older; gabled wing facing Church Street; foundation replaced with cement block. Hipped roof full length front porch with slender, turned supports and spindlework balustrade; roof steeply pitched; single pane double-hung windows.					17. COUNTY Summit
17. History and Significance 1929 occupant Frank C. Bailey Thought to be one of a group of houses built at the south end of College Street by or for workers at Seymour Straights cheese enterprises in the late 1800's.				18. COUNTY Summit	
18. Description of Environment and Outbuildings Residential street					19. COUNTY Summit
19. Sources of Information Summit County Tax Assessment records Personal inspection		46. Prepared by L Newkirk, F Barlow		20. COUNTY Summit	
		47. Organization HHA			21. COUNTY Summit
		48. Date _____ 49. Revision Date(s) _____		22. COUNTY Summit	
					23. COUNTY Summit
				24. COUNTY Summit	
					25. COUNTY Summit
				26. COUNTY Summit	
					27. COUNTY Summit
				28. COUNTY Summit	
					29. COUNTY Summit
				30. COUNTY Summit	
					31. COUNTY Summit
				32. COUNTY Summit	
					33. COUNTY Summit
				34. COUNTY Summit	
					35. COUNTY Summit
				36. COUNTY Summit	
					37. COUNTY Summit
				38. COUNTY Summit	
					39. COUNTY Summit
				40. COUNTY Summit	
					41. COUNTY Summit
				42. COUNTY Summit	
					43. COUNTY Summit
				44. COUNTY Summit	
					45. COUNTY Summit
				46. COUNTY Summit	
					47. COUNTY Summit
				48. COUNTY Summit	
					49. COUNTY Summit
				50. COUNTY Summit	
					51. COUNTY Summit
				52. COUNTY Summit	
					53. COUNTY Summit
				54. COUNTY Summit	
					55. COUNTY Summit
				56. COUNTY Summit	
					57. COUNTY Summit
				58. COUNTY Summit	
					59. COUNTY Summit
				60. COUNTY Summit	
					61. COUNTY Summit
				62. COUNTY Summit	
					63. COUNTY Summit
				64. COUNTY Summit	
					65. COUNTY Summit
				66. COUNTY Summit	
					67. COUNTY Summit
				68. COUNTY Summit	
					69. COUNTY Summit
				70. COUNTY Summit	
					71. COUNTY Summit
				72. COUNTY Summit	
					73. COUNTY Summit
				74. COUNTY Summit	
					75. COUNTY Summit
				76. COUNTY Summit	
					77. COUNTY Summit
				78. COUNTY Summit	
					79. COUNTY Summit
				80. COUNTY Summit	
					81. COUNTY Summit
				82. COUNTY Summit	
					83. COUNTY Summit
				84. COUNTY Summit	
					85. COUNTY Summit
				86. COUNTY Summit	
					87. COUNTY Summit
				88. COUNTY Summit	
					89. COUNTY Summit
				90. COUNTY Summit	
					91. COUNTY Summit
				92. COUNTY Summit	
					93. COUNTY Summit
				94. COUNTY Summit	
					95. COUNTY Summit
				96. COUNTY Summit	
					97. COUNTY Summit
				98. COUNTY Summit	
					99. COUNTY Summit
				100. COUNTY Summit	








Window Design to be altered
(see elevations)







PROJECT #: 2302		
ISSUE	ID	DATE
FOR PERMIT	A	12/09/2024



1 SOUTH ELEVATION (SIDE OF HOUSE)
SCALE: 1/4" = 1'-0"




2 WEST ELEVATION (FRONT OF HOUSE)
SCALE: 1/4" = 1'-0"




WINDOW SCHEDULE			
ID	QTY	W x H	REMARKS
W01	3	2'-2"x4'-0"	
W02	4	3'-0"x3'-0"	
W03	2	2'-8"x5'-0"	
W05	2	3'-0"x5'-0"	
W06	1	3'-5"x1'-0"	
W07	1	3'-0"x1'-6"	
W08	2	2'-0"x5'-6"	
W09	4	3'-0"x5'-6"	
W10	2	3'-0"x4'-8"	
W11	1	2'-5"x3'-10 1/2"	



6 EXISTING ELEVATION
SCALE: 1/4" = 1'-0"



5 EXISTING ELEVATIONS
SCALE: 1/4" = 1'-0"





WENCLEWICZ RESIDENCE

PROJECT INFORMATION

CITY	HUDSON
COUNTY	SUMMIT COUNTY
PARCEL NO	3200958
ZONING	DISTRICT 4 HISTORIC RESIDENTIAL NEIGHBORHOOD

PROJECT	A NEW ADDITION OFF THE REAR OF THE HOUSE. THE ADDITION WILL HOUSE A NEW LIVING ROOM, MUD ROOM, AND OWNER'S SUITE ON THE SECOND FLOOR. THE EXTERIOR MATERIALS OF THE ADDITION ARE SPECIFIED TO MATCH THE EXISTING RESIDENCE WITH CEDAR SHAKE SIDING (PAINTED), DOUBLE HUNG WOOD WINDOWS, AND ASPHALT SHINGLE ROOF.
---------	---

AREA	RESIDENCE	1,408 SF
	ADDITION	1,148 SF
	TOTAL	2,556 SF

PROJECT TEAM

ARCHITECT:

HARA ARCHITECTS
HUDSON, OHIO
P: 419.410.6241

CONTACT: NATE BAILEY

DRAWING INDEX

G100	COVER SHEET	03/11/2025	1
C101	EXISTING CONDITIONS & DEMO PLAN	12/09/2024	
C102	SITE PLAN	12/09/2024	
C103	IMPERVIOUS AREA MAP		
D100	DEMOLITION PLANS	12/09/2024	1
A100	FOUNDATION PLAN	03/11/2025	
A101	FLOOR PLANS	03/11/2025	
A103	ROOF PLAN	12/09/2024	
A300	EXTERIOR ELEVATIONS	12/09/2024	
A301	EXTERIOR ELEVATIONS	12/09/2024	
A400	BUILDING SECTIONS & SECTION DETAILS	03/11/2025	1



PROJECT GENERAL NOTES

THE CONTRACTOR WILL FURNISH ALL LABOR, MATERIAL, EQUIPMENT, PERMITS, TAXES, AND INSURANCE NECESSARY TO COMPLETE THE WORK INDICATED AND/OR IMPLIED IN THE CONSTRUCTION DOCUMENTS UNLESS NOTED OTHERWISE AND WILL COORDINATE THE WORK RESPONSIBILITIES OF ALL SUBCONTRACTORS: ALL LABOR AND MATERIALS TO CARRY OUT FULLY THE INTENTIONS OF THE PLANS AND SPECIFICATIONS ARE PART OF THE CONTRACT, WHETHER OR NOT SPECIFICALLY DOCUMENTED.

ALL WORK WILL CONFORM TO THE CURRENT OHIO BUILDING, MECHANICAL & PLUMBING CODES, AS WELL AS THE CURRENT NATIONAL BOARD OF FIRE UNDERWRITERS AND ALL OTHER APPLICABLE CITY CODES, LOCAL LAWS, AND AUTHORITIES HAVING JURISDICTION. CODE STANDARDS AND PUBLICATIONS OF PRIVATE AND PUBLIC BODIES MENTIONED WITHIN THE SPECIFICATIONS OR ON THE DRAWINGS, WILL BE CONSIDERED TO BE THOSE IN FORCE AT THE TIME OF THE CONTRACT AWARD.

THE CONTRACTOR WILL BE RESPONSIBLE FOR ALL CONTROLLED INSPECTIONS AND ANY TECHNICAL TESTING REQUIRED FOR CONTROLLED INSPECTIONS AS STIPULATED BY ALL APPLICABLE CODES.

ALL MANUFACTURED ARTICLES, MATERIALS, AND EQUIPMENT WILL BE NEW AND FREE OF DEFECTS AND WILL BE SUPPLIED, INSTALLED, CONNECTED, ERECTED, USED, CLEANED, AND CONDITIONED AS DIRECTED BY THE RESPECTIVE MANUFACTURERS, UNLESS SPECIFIED OTHERWISE.

THE CONTRACTOR WILL NOTIFY THE ARCHITECT OF ANY ERRORS, OMISSIONS, CONFLICTS, OR AMBIGUITIES IN AND BETWEEN THE DRAWINGS AND THE SPECIFICATIONS PRIOR TO PROCEEDING WITH THE WORK. IF SUCH NOTICE IS NOT FURNISHED TO THE ARCHITECT, THE CONTRACTOR WILL BE DEEMED TO HAVE INSPECTED THE DRAWINGS AND SPECIFICATIONS AND TO HAVE FOUND THEM IN PROPER FORM FOR EXECUTION.

THE CONTRACTOR REPRESENTS THAT HE HAS HAD ADEQUATE ACCESS TO THE JOB SITE AND BUILDING AREA IN WHICH THE WORK IS TO BE PERFORMED, THAT HE HAS SATISFIED HIMSELF AT TO THE NATURE AND LOCATION OF WORK, INCLUDING ANY OBSTRUCTIONS, SCOPE OF WORK, ACTUAL LEVELS, THE EQUIPMENT AND FACILITIES NEEDED PRELIMINARY TO AND DURING THE EXECUTION OF THE WORK AND ALL OTHER MATTERS, WHICH CAN IN ANY WAY AFFECT THE WORK OR THE COST THEREOF UNDER THIS CONTRACT, AND THAT HE HAS STUDIED THE CONTRACT DOCUMENTS AND ALL OTHER DOCUMENTS PERTAINING TO THE INSTALLATION OF OTHER TRADES WHICH MAY INFLUENCE HIS WORK.

THE CONTRACTOR WILL ASSUME FULL RESPONSIBILITY, INCLUDING RESPONSIBILITY FOR ALL RELATED COSTS FOR ANY AND ALL WORK DONE WITHOUT THE APPROVAL OF THE ARCHITECT IF SUCH WORK IS IN CONFLICT WITH THE CONTRACT, DRAWINGS, OR SPECIFICATIONS.

THE OWNER WILL ESTABLISH THE LIMITS OF THE CONSTRUCTION SITE IN ADDITION TO ANY CONTRACT LIMIT LINES SHOWN IN THE DRAWINGS. THE CONTRACTOR WILL CONTINUE HIS OPERATIONS WITHIN THESE LIMITS, UNLESS UPON WRITTEN REQUEST AND REPLY, A VARIANCE IS AGREED TO BY THE OWNER. THE CONTRACTOR WILL BE RESPONSIBLE FOR TRESPASS ON AND/ OR DAMAGE TO OTHER PROPERTY BY ANY OF HIS EMPLOYEES OR HIS SUBCONTRACTORS' EMPLOYEES.

THE CONTRACTOR WILL BE RESPONSIBLE FOR THE SAFE WORKING CONDITIONS AT THE SITE. THE ARCHITECT AND OWNER WILL NOT BE DEEMED TO HAVE ANY RESPONSIBILITY OR LIABILITY IN CONNECTION HEREWITH.

CONSTRUCTION OPERATIONS WILL NOT INVOLVE INTERRUPTION OF HEATING, WATER, ELECTRICAL, OR OTHER SERVICES TO ANY PORTION OF THE BUILDING OUTSIDE THE LIMITS OF THE CONSTRUCTION SITE DESCRIBED IN NOTE 9.

THE CONTRACTOR WILL BE RESPONSIBLE FOR CORRECTING ANY DEFICIENCIES CAUSED BY DEFECTIVE OR ILL TIMED WORK AT NO ADDITIONAL COST TO THE OWNER.

NO SUBSTITUTIONS ARE PERMITTED EXCEPT WHERE THE TERM "APPROVED EQUAL" APPEARS. ALL SUBSTITUTIONS MUST BE APPROVED IN WRITING BY THE ARCHITECT. THE CONTRACTOR IS TO SUBMIT SAMPLES OR CATALOG CUTS OF ALL VISIBLE MATERIALS AND EQUIPMENT FOR THE ARCHITECT'S APPROVAL PRIOR TO INSTALLATION.


ABBREVIATIONS

ABV	ABOVE	HC	HOLLOW CORE
A/C	AIR CONDITIONING	HDWR.	HARDWARE
AFF	ABOVE FINISHED FLOOR	HM	HOLLOW METAL
ALT	ALTERNATE	HVAC	HEATING, VENTILATION, AND AIR
ANJ	AUTHORITY HAVING JURISDICTION	HT	HEIGHT
ALUM	ALUMINUM	INSUL	INSULATION
APPROX.	APPROXIMATELY	JST	JOIST
ARCH	ARCHITECTURAL	LAM	LAMINATED
ASPH	ASPHALT	LF	LINEAR FOOT
BD	BOARD	MAS	MASONRY
BLDG	BUILDING	MATL	MATERIAL
BOTT	BOTTOM OF	MAX.	MAXIMUM
BRG	BEARING	MECH	MECHANICAL
BOTT	BOTTOM	MFG.	MANUFACTURER
BTW	BETWEEN	MIN.	MINIMUM
CF	CUBIC FEET	MISC	MISCELLANEOUS
CIP	CAST IN PLACE	MO	MISCELLANEOUS OPENING
CJ	CONTROL JOINT	MTD	MOUNTED
CLG	CEILING	MTL	METAL
CLR	CLEAR	NOM	NOMINAL
CMU	CONCRETE MASONRY UNIT	NTS	NOT TO SCALE
CONC	CONCRETE	O/	OVER
CO	CLEAN OUT	O.C.	ON CENTER
CONT	CONTINUOUS	OPN	OPENING
DBL	DOUBLE	PREFAB	PREFABRICATED
DEPT	DEPARTMENT	PLYWD	PLYWOOD
DIA	DIAMETER	P. LAM	PLASTIC LAMINATE
DIM	DIMENSION	PR	PAIR
DN	DOWN	PSI	POUNDS PER SQUARE INCH
DR	DOOR	REF	REFERENCE
DS	DOWNSPOUT	RM	ROOM
DTL	DETAIL	RO	ROUGH OPENING
DWG	DRAWING	REQ	REQUIRED
EA	EACH	SC	SOLID CORE
ELEC	ELECTRICAL	SECT	SECTION
EQ	EQUAL	SIM.	SIMILAR
EXH	EXHAUST	STRUC	STRUCTURAL
EXIST	EXISTING	TYP	TYPICAL
EXP	EXPOSED	UNO	UNLESS NOTED OTHERWISE
EXT	EXTERIOR	W/	WITH
FD	FLOOR DRAIN	WVF	WELDED WIRE FABRIC
FDN	FOUNDATION		
FIN	FINISHED		
FLR	FLOOR		
FT	FOOT		
FTG	FOOTING		
FUR	FURRING		
GALV	GALVANIZED		
GA	GAUGE		
GC	GENERAL CONTRACTOR		
GYP. BD.	GYPSON BOARD		
GYP	GYPSON		

DRAWING SYMBOLS

	DETAIL
	EXTERIOR ELEVATION
	BUILDING SECTION
	INTERIOR ELEVATION
	WALL SECTION
	CENTERLINE AND GRID
	DOOR TAG
	WINDOW TAG

SITE PLAN



haraarchitects.com

PROJECT TEAM:

ARCHITECT
HARA ARCHITECTS

STRUCTURAL
DANMARK ENGINEERING

WENCLEWICZ RESIDENCE

27 COLLEGE STREET, HUDSON, OHIO #Site Postcode

PROJECT #: 2302

ISSUE	ID	DATE
REVISION #1	1	03/11/2025
FOR PERMIT	A	12/09/2024

COVER SHEET

G100

ULTIMATE

MARVIN SIGNATURE® COLLECTION



THE MARVIN PORTFOLIO

The Marvin portfolio consists of five product lines organized into three distinct collections defined by the degree of design detail and customization opportunities.

Marvin windows and doors offer exceptional performance, energy efficiency, low maintenance, and quality you can see, feel, and touch to help bring your vision to life.



ULTIMATE

Most extensive selection of features, options, and product types



MODERN

Design flexibility in a purely modern aesthetic available exclusively at Marvin Modern dealers



COASTLINE

Custom windows and doors for high velocity hurricane zones in the coastal Southeast



ELEVATE

Wide range of options and product types



ESSENTIAL

Curated options and product types

	MARVIN SIGNATURE® COLLECTION			MARVIN ELEVATE® COLLECTION	MARVIN ESSENTIAL™ COLLECTION
INTERIORS	WOOD 6 species options + custom 2 painted or primed options 6 stains + clear coat	EXTRUDED ALUMINUM 5 color options	EXTRUDED ALUMINUM 6 solid colors, 4 woodgrain finishes	WOOD Bare pine, painted Designer Black, painted White, or clear coat	FIBERGLASS 3 color options
EXTERIORS	EXTRUDED ALUMINUM 19 colors + custom OR WOOD 3 species + custom	FIBERGLASS 5 color options	EXTRUDED ALUMINUM 6 solid colors, 4 woodgrain finishes	FIBERGLASS 5 color options	FIBERGLASS 5 color options
SIZING	Standard + custom sizing for replacement, remodeling, or new construction	Custom sizing for remodeling or new construction	Custom sizing for replacement, remodeling, or new construction	Standard + custom sizing for replacement, remodeling, or new construction	Standard + custom sizing for replacement, remodeling, or new construction
HARDWARE	Extensive selection including Marvin Gallery Hardware	Minimalist hardware for modern design aesthetic	Available in multiple styles, sizes, and finishes to complement the window + door aesthetics	Available in 6 finish options with 2 door handle styles	Available in 6 finish options with 1 door handle style
COASTAL + WATERFRONT	Hurricane Impact Zones 3 and 4, + PG 50 Products		All products rated for High Velocity Hurricane Zone (IZ4)	Hurricane Impact Zone 3, + PG 50 Products	

Marvin Signature® collection

REDEFINING THE STANDARD

The Ultimate product line, part of the Marvin Signature collection, unites beautiful design with exceptional craftsmanship. Add character to almost any space with our most extensive selection of shapes, styles, sizes, and options—including wood interiors protected by tough wood or aluminum exteriors. With nearly limitless opportunities for customization, Ultimate can match your vision—and give it room to grow.

About Us

At Marvin, we're driven to imagine and create better ways of living, helping people feel happier and healthier inside their homes. We believe that our work isn't just about designing better windows and doors—it's about opening new possibilities for the people who use them.



ULTIMATE PICTURE NARROW FRAME CORNER WINDOW IN EBONY

TABLE OF CONTENTS


8	WINDOWS		
10	WINDOW TERMS + DEFINITIONS		
11	WINDOW OPERATING STYLES		
12	DOUBLE HUNG WINDOWS		
14	ULTIMATE DOUBLE HUNG G2		
18	ULTIMATE DOUBLE HUNG ROUND TOP G2		
20	ULTIMATE DOUBLE HUNG INSERT G2		
22	ULTIMATE SINGLE HUNG G2		
24	ULTIMATE WOOD DOUBLE + SINGLE HUNG		
26	CASEMENT + AWNING WINDOWS		
28	ULTIMATE CASEMENT STYLES		
30	ULTIMATE CASEMENT EASY WASH MODE		
31	ULTIMATE CASEMENT FEATURES + OPTIONS		
32	ULTIMATE CASEMENT ULTIMATE CASEMENT PUSH OUT		
34	ULTIMATE CASEMENT NARROW FRAME ULTIMATE CASEMENT PUSH OUT NARROW FRAME		
36	ULTIMATE FRENCH CASEMENT ULTIMATE FRENCH CASEMENT PUSH OUT		
38	ULTIMATE AWNING ULTIMATE AWNING PUSH OUT		
40	ULTIMATE AWNING NARROW FRAME ULTIMATE AWNING PUSH OUT NARROW FRAME		
42	MORE WINDOW STYLES		
44	ULTIMATE GLIDER		
46	ULTIMATE GLIDER BI-PARTING		
48	ULTIMATE VENTING PICTURE		
50	ULTIMATE PICTURE		
52	ULTIMATE PICTURE NARROW FRAME		
54	ULTIMATE CORNER		
56	ULTIMATE CORNER NARROW FRAME		
58	ULTIMATE SPECIALTY SHAPES		
		60	ULTIMATE BAY + BOW
		62	DOORS
		64	DOOR TERMS + DEFINITIONS
		65	DOOR OPERATING STYLES
		66	DOOR FEATURES + OPTIONS
		68	ULTIMATE SWINGING NARROW PROFILE DOOR
		70	ULTIMATE SWINGING FRENCH DOOR G2
		72	ULTIMATE SLIDING FRENCH DOOR G2
		74	ULTIMATE SLIDING NARROW PROFILE DOOR
		76	ULTIMATE MULTI-SLIDE DOOR
		78	ULTIMATE BI-FOLD DOOR
		80	ULTIMATE LIFT AND SLIDE DOOR
		82	ULTIMATE COMMERCIAL DOOR
		84	OPTIONS
		86	INTERIOR FINISH OPTIONS
		88	EXTERIOR FINISH OPTIONS
		90	EXTERIOR CASINGS + SUBSILLS
		92	DIVIDED LITES
		94	GLASS + GLAZING
		96	HOME AUTOMATION
		98	SCREENS
		102	WINDOW HARDWARE
		104	DOOR HARDWARE
		106	GALLERY HARDWARE
		110	COASTAL
		112	COASTAL PRODUCTS

WINDOWS



ULTIMATE CASEMENT WINDOW

WINDOW TERMS + DEFINITIONS



1. FRAME

There are three components to the frame: the header across the top, the jambs down each side, and the sill across the bottom. Marvin frames are built strong with a variety of high-quality wood species.

2. GLAZING

The glass in a window is called glazing. Marvin's broad range of glazing options can meet both high-performance and refined aesthetic requirements.

3. LITE

Each area of glass is called a lite. Marvin offers divided lite patterns for whatever look you wish to create.

4. HARDWARE

Marvin uses only the highest quality locks, handles, lifts, pulls, and hinges in a wide variety of durable finishes.

5. SASH

The sash—operating or stationary—is comprised of horizontal rails, vertical stiles, and glazing. Marvin's large solid sash offer precise fit and ease of operation.

WINDOW OPERATING STYLES



DOUBLE HUNG

Double hung windows have two movable sashes which operate vertically.




CASEMENT

A window that is hinged to its frame at the side and opens like a door.



FIXED OR PICTURE

An inoperable window with direct glaze or in-sash configurations. Available in a wide range of polygon and radius shapes.



IN-SASH PICTURE

- Fixed window designed to match the profiles of operable windows like casement, awning, or double hung
- Available in large sizes up to 8' wide × 8' high



AWNING

An awning is hinged to the frame at the top and opens outward. If hinged on the bottom, it's called a hopper.



GLIDER

A window with a sash that slides horizontally to open and close.



DIRECT GLAZE PICTURE

- Fixed window with no sash—the glass is glazed directly into the frame
- Available in stunningly large sizes with widths or heights up to 12'

MORE FLEXIBILITY TO MEET ANY DESIGN CHALLENGE.

Marvin has an extensive selection of styles, sizes, shapes, and options.

DOUBLE HUNG WINDOWS

Ultimate Double Hung windows combine state-of-the-art design with classic style. Advanced engineering and high-quality construction make our double hung windows incredibly durable, versatile, and easy to use.



ULTIMATE DOUBLE HUNG G2 WINDOW IN EBONY

ULTIMATE DOUBLE HUNG G2



ULTIMATE DOUBLE HUNG G2 WINDOW IN DESIGNER BLACK



Photo: Laurey W. Glenn

ULTIMATE DOUBLE HUNG G2 WINDOW IN WHITE WITH OIL RUBBED BRONZE HARDWARE

ULTIMATE DOUBLE HUNG G2

The Ultimate Double Hung G2 window is an embodiment of our dedication to the craft of creating windows and doors. Influenced by the rich, historical significance of this window style and inspired by innovative design, each feature is thoughtfully added and every detail is carefully considered. This is all in service of shaping a window that deserves to be in the unique homes our customers desire.



INTERIOR



EXTERIOR



UNIQUE WASH MODE ALLOWS CLEANING OF BOTH SIDES OF GLASS FROM INDOORS

ULTIMATE DOUBLE HUNG G2

Engineered for performance and designed to inspire, each aspect of the Ultimate Double Hung G2 window was made with purpose. Our engineers consider every detail from the most innovative features to the most minute subtleties, all because the windows in your home help illuminate the most important parts of your life.

INTERIOR FEATURES AND PERFORMANCE

RICH WOOD INTERIOR
Offers beauty and warmth with six wood species and ten interior finish options.

NARROW CHECKRAIL
Provides a sleek aesthetic at 1 15⁄16 inches to maximize daylight opening while maintaining historical accuracy.

TILT WASH MODE
Allows easy access to exterior glass for cleaning and maintenance.



EXCLUSIVE AUTOLOCK
Activates when the sashes are closed, locking the window.

ENERGY EFFICIENCY
Multiple glass options for meeting ENERGY STAR® standards in energy efficiency for various regions and climates.


SASH BALANCE SYSTEMS
Enables smooth operation at the largest sizes.

EXTERIOR FEATURES AND PERFORMANCE

DURABLE CLADDING
Extruded aluminum exterior cladding with an AAMA verified 2605 finish and backed by a 20-year warranty against chalking and fading.

EXPANSIVE SIZES
Larger than 5 feet wide by 10 feet high.

TRADITIONAL SILL BEVEL
The 14-degree bevel provides optimal water management while maintaining a classic look.



SUPERIOR WEATHER PERFORMANCE
LC-PG50 on most sizes. Optional commercial (CW) performance and IZ3 certified coastal performance on most sizes.

DESIGN VERSATILITY
An array of simulated divided lite patterns, interior and exterior color options, ten hardware finishes, and archtop models.

ALUMINUM INTER-LOCK
Eliminates drafts and improves the window's overall structural integrity.

ULTIMATE DOUBLE HUNG ROUND TOP G2



ULTIMATE DOUBLE HUNG ROUND TOP G2 WINDOW IN EBONY



EYEBROW RADIUS HALF CIRCLE TRANSOM EYEBROW TRANSOM HALF CIRCLE RADIUS HALF EYEBROW SINGLE HUNG*

ULTIMATE DOUBLE HUNG ROUND TOP G2

The Ultimate Double Hung Round Top G2 window will add traditional arching and elegant lines to your home or historic preservation project. With the same features and grace of the Ultimate Double Hung G2 window, this window offers design flexibility with numerous variations of radius shapes. Choose from multiple divided lite patterns to further enhance the arch of the window. These versatile windows—available in a wide range of sizes—can provide a subtle accent or a dramatic focal point to enhance your home design.

ROUND TOP VARIATIONS

EYEBROW AND HALF EYEBROW RADIUS OPERATING DOUBLE HUNG

A classic look with a gentle eyebrow radius. Beautiful as a stand alone window or as part of an assembly.

HALF CIRCLE TRANSOM

This simulated half circle transom window can be sized to stand alone or easily fit above a double hung window.

EYEBROW TRANSOM AND PICTURE

This stationary window is available as a transom or picture window. These windows are designed to complement the Ultimate Double Hung G2 window with correlating sizes and matching springline.

HALF CIRCLE RADIUS OPERATING DOUBLE HUNG

A dramatic window with a true half circle arch. The look gives a beautifully smooth transition from jamb to header. Both sashes are operable.

HALF EYEBROW SINGLE HUNG

This striking window style adds elegant curve to a two-wide window assembly (not shown)

*Available on Single Hung only.

ULTIMATE DOUBLE HUNG INSERT G2



ULTIMATE DOUBLE HUNG INSERT G2 WINDOW IN SATIN NICKEL



ULTIMATE DOUBLE HUNG INSERT G2 WINDOW IN SATIN NICKEL

ULTIMATE DOUBLE HUNG INSERT G2

The Ultimate Double Hung Insert G2 window adds quality craftsmanship, beauty, and energy efficiency to your home without compromising architectural integrity. Its frame-in-frame design is built precisely to seamlessly fit into your unique window opening, so there's no need to remove the existing frame or disturb the exterior or interior trim of your house.



INTERIOR



EXTERIOR



SASH LOCK IN SATIN NICKEL

ULTIMATE SINGLE HUNG G2



SINGLE HUNG G2 WINDOW WITH CONTEMPORARY LIFT LOCK IN BRASS

ULTIMATE SINGLE HUNG G2

A contemporary classic, the Ultimate Single Hung G2 window blends traditional beauty and state-of-the-art performance. With the top sash stationary and the bottom sash operable, a single hung style is often preferred in a cottage-style window with a small top sash that doesn't need to open. Reliable and energy efficient, the Ultimate Single Hung G2 window offers an auto-lock feature for convenient security, durable hardware for smooth operation, and Marvin's unique Wash Mode for easy cleaning. Customize your design with round top styles or optional Lift Lock, Marvin's exclusive bottom rail locking mechanism for easier operation in hard-to-reach areas.



INTERIOR WITH CONTEMPORARY LIFT LOCK



INTERIOR WITH TRADITIONAL LIFT LOCK



CONTEMPORARY AND TRADITIONAL LIFT LOCKS IN SATIN NICKEL

WOOD DOUBLE + SINGLE HUNG



ULTIMATE DOUBLE HUNG MAGNUM WINDOW



ULTIMATE DOUBLE HUNG MAGNUM ROUND TOP WINDOW

WOOD DOUBLE AND SINGLE HUNG WINDOWS

The Ultimate Wood Double/Single Hung and Ultimate Wood Double Hung Magnum are quintessentially traditional windows designed to fit seamlessly into the historic fabric of your home, neighborhood, or community. With residential and commercial applications, these windows are perfect for any historic building.



WOOD DOUBLE/SINGLE HUNG EXTERIOR



WOOD DOUBLE HUNG MAGNUM INTERIOR

CASEMENT + AWNING WINDOWS

Ultimate Casements and Awnings are innovative, high-performing windows. Delivering exceptional versatility and clean profiles, these state-of-the-art windows are designed to suit virtually any application.



ULTIMATE CASEMENT PUSH OUT WINDOW WITH WOOD INSWING SCREENS

ULTIMATE CASEMENT STYLES




ULTIMATE CASEMENT WINDOW

FULL FRAME OR NARROW FRAME

The Ultimate Casement and Ultimate Casement Narrow Frame windows are the most versatile and innovative casement windows ever produced. Ultimate Casement styles feature concealed multi-point locks, a patented Wash Mode, and durable hardware that operates smoothly even at the largest sizes.



ULTIMATE CASEMENT
A recessed sash for a traditional look, plus a full jamb, offers design flexibility for new construction or full frame replacement.



ULTIMATE CASEMENT NARROW FRAME
A flush sash to the exterior and narrow jamb depth make this window an easy choice for frame-in-frame replacement or more contemporary new construction applications.



ULTIMATE CASEMENT EXTERIOR WITH 4 1/8" FULL JAMB



ULTIMATE CASEMENT NARROW FRAME EXTERIOR WITH 2 1/8" NARROW JAMB

JAMBS + PROFILES
The Ultimate Casement has a recessed sash for a traditional or historic look. The Ultimate Casement Narrow Frame has a flush-to-frame sash for a contemporary look.

ULTIMATE CASEMENT EASY WASH MODE


Ultimate Casement operates in a way so revolutionary that we've patented it, making Marvin the only place you'll find it. The hardware allows access to both sides of the glass from the inside of your home, making window washing stress- and ladder-free.



Marvin exclusive Wash Mode not available on Ultimate Casement windows in sizes less than 20 inches wide or Ultimate French Casement, Ultimate Awning, or Round Top windows.



ULTIMATE CASEMENT FEATURES + OPTIONS




MULTI-POINT LOCKING SYSTEM
Multi-point locking mechanisms enhance performance and make large casements easy to operate.




ENDLESS DESIGN OPTIONS
A variety of divided lite patterns, including a double hung look make energy-efficient casements the perfect replacement window in older homes.



LOCK STATUS SENSOR
Hidden Lock Status Sensor option connects with your smart home to indicate when windows are closed and locked.



LARGE SIZES OPEN WITH EASE
We have developed the most durable hardware in the industry, which provides easy opening and smooth operation on even the largest casements.



WINDOW OPENING CONTROL DEVICE
Limits the casement sash opening to less than 4 inches when engaged. The release mechanism allows for operation beyond 4 inches. This option meets the ASTM F2090-21 standard.



FRICTION LIMITER
Flip a lever to lock the sash securely in place at multiple set angles, allowing you to open your window on windy days. Available for push out only.

ULTIMATE CASEMENT



ULTIMATE CASEMENT WINDOW IN DESIGNER BLACK PAINTED INTERIOR FINISH WITH MATTE BLACK HARDWARE



Photographer: Sara Tramp

ULTIMATE CASEMENT WINDOW WITH MATTE BLACK HARDWARE

ULTIMATE CASEMENT

The Ultimate Casement window is offered in some of the largest sizes in the industry, with a secure multi-point lock, durable hardware that ensures smooth operation, and Marvin’s exclusive Wash Mode for easy cleaning—even on upper floors. With many design options, including round top shapes, the Ultimate Casement window flexes to fit your vision and can be sized to complement the most expansive views.



CASEMENT INTERIOR WITH FOLDING HANDLE IN SATIN NICKEL



CASEMENT PUSH OUT INTERIOR WITH HANDLE IN MATTE BLACK



ULTIMATE CASEMENT NARROW FRAME



ULTIMATE CASEMENT NARROW FRAME WINDOW WITH SATIN NICKEL HARDWARE



ULTIMATE CASEMENT NARROW FRAME WINDOW IN DESIGNER BLACK

ULTIMATE CASEMENT NARROW FRAME

The Ultimate Casement Narrow Frame window is a contemporary option with a flush exterior and narrow jamb, ideal for frame-in-frame replacement and allowing quick and easy installation without disturbing the existing frame or interior wall. With its sleek design and square profiles, this window is a great fit for new construction or remodeling projects that call for slim lines and maximum views.



CASEMENT NARROW FRAME INTERIOR WITH FOLDING HANDLE IN SATIN NICKEL



CASEMENT PUSH OUT NARROW FRAME INTERIOR WITH HANDLE IN OIL RUBBED BRONZE



ULTIMATE FRENCH CASEMENT



ULTIMATE FRENCH CASEMENT PUSH OUT WINDOW IN PINE WITH BRASS HARDWARE

ULTIMATE FRENCH CASEMENT

The Ultimate French Casement window pairs expert engineering with thoughtful design to offer a beautiful architectural window that won't compromise on performance or energy efficiency. The Ultimate French Casement has no center vertical post and opens like a French door. Simply crank open each independent sash or push out each sash and enjoy an unobstructed view.



FRENCH CASEMENT INTERIOR WITH FOLDING HANDLES



FRENCH CASEMENT PUSH OUT INTERIOR



FRENCH CASEMENT PUSH OUT EXTERIOR

ULTIMATE AWNING



ULTIMATE AWNING WINDOW IN STAINED MULTI-GRAIN DOUGLAS FIR WITH MATTE BLACK HARDWARE



ULTIMATE AWNING AND PICTURE WINDOWS WITH MATTE BLACK HARDWARE AND DESIGNER BLACK SASH/WHITE FRAME

ULTIMATE AWNING

A top-hinged alternative or complement to a casement window, the Ultimate Awning window is designed for performance and quality. With industry-leading sizes, the Ultimate Awning can be used on its own as a convenient option for hard to reach areas like over a sink or counter, or as a complement to adjacent windows, allowing fresh air access.



AWNING WITH FOLDING HANDLE
IN SATIN NICKEL



AWNING PUSH OUT WITH PUSH OUT HANDLE
IN OIL RUBBED BRONZE

ULTIMATE AWNING NARROW FRAME



ULTIMATE AWNING NARROW FRAME WINDOW WITH ESPRESSO STAIN



ULTIMATE AWNING NARROW FRAME WINDOW IN EBONY

ULTIMATE AWNING NARROW FRAME

The Ultimate Awning Narrow Frame window is a sleek and versatile top-hinged window with a flush exterior profile and narrow frame—meaning it can be installed in replacement projects without removing the existing window frame or disrupting interior or exterior trim. The Ultimate Awning Narrow Frame window's contemporary aesthetic looks beautiful on its own or as a complement to narrow frame casement or picture windows. Hardware located at the bottom of the window means easy operation—even in hard to reach areas like over a kitchen sink.



AWNING NARROW FRAME
WITH FOLDING HANDLE
IN SATIN NICKEL



AWNING PUSH OUT NARROW FRAME
WITH BLACK PUSH OUT HANDLE

MORE WINDOW STYLES

Distinctive spaces demand distinctive windows. Ultimate offers a wide variety of shapes, sizes, and operating styles to exactly match the design requirements of any building project.



ULTIMATE DIRECT GLAZE, CASEMENT, POLYGON WINDOWS IN CLEAR COAT MULTI-GRAIN DOUGLAS FIR

ULTIMATE GLIDER



ULTIMATE GLIDER WINDOW IN EBONY WITH MATTE BLACK HARDWARE

ULTIMATE GLIDER

The clean look and contemporary styling of Ultimate Glider windows is complemented by innovative performance features and beautiful design options. Comfortable ergonomics make the windows effortless to operate with an easy, one-handed locking system. Choose from one or two operating sash or dual sash configurations.



INTERIOR



EXTERIOR

ULTIMATE GLIDER BI-PARTING



ULTIMATE GLIDER BI-PARTING WINDOW IN WHITE OAK FINISH

ULTIMATE GLIDER BI-PARTING

The Ultimate Glider Bi-parting is a stunning variation on the clean, contemporary look of a glider window. Two center panels slide to each side of the window, providing an unobstructed opening. Perfect for the indoor/outdoor lifestyle, the Ultimate Glider Bi-parting window makes a large and easy pass-through from kitchen to outdoor dining or living space.



INTERIOR



EXTERIOR

ULTIMATE VENTING PICTURE



ULTIMATE CASEMENT VENTING PICTURE WINDOW IN DESIGNER BLACK

ULTIMATE VENTING PICTURE

The Ultimate Venting Picture window-exclusive to Marvin-is a beautiful way to bring natural light and fresh air into a room. Designed with a patented hidden screen system, it opens evenly on all sides for passive air exchange, adding comfort and air flow to your home.



INTERIOR



EXTERIOR



VENTILATION SCREEN

ULTIMATE CASEMENT VENTING PICTURE WINDOW IN DESIGNER BLACK

ULTIMATE PICTURE




ULTIMATE CASEMENT PICTURE WINDOW IN DESIGNER BLACK




ULTIMATE PICTURE WINDOW IN WHITE

ULTIMATE PICTURE

The non-operable Ultimate Picture window is a beautiful way to bring natural light into a room or highlight an unobstructed view. With consistent sizing and profiles, the Picture window makes a perfect complement to the Ultimate double hung, single hung, and casement windows. The non-operable Direct Glaze Picture window provides a clean, contemporary look with a larger daylight opening.



DIRECT GLAZE PICTURE WINDOW
INTERIOR VIEW



IN-SASH PICTURE WINDOW
INTERIOR VIEW

DIRECT GLAZE
Direct glaze refers to a window with no sash. The glass is glazed directly into the frame and is stationary.

IN-SASH
In-sash Picture windows are non-operable, and they can match the profiles of windows with operable sash.

ULTIMATE PICTURE NARROW FRAME



ULTIMATE CASEMENT NARROW FRAME AND PICTURE NARROW FRAME WINDOW IN EBONY

ULTIMATE PICTURE NARROW FRAME

Homes designed to express a unique vision need windows to match. The contemporary look of the Ultimate Picture Narrow Frame window blurs the line between inside and outside with clean lines, narrow frames, and an almost unlimited selection of shapes and sizes. Ideal for transforming multiple units into stunning window wall configurations, the Ultimate Picture Narrow Frame window is available in sizes up to 86 inches wide and 146 inches high.



DIRECT GLAZE PICTURE NARROW FRAME



IN-SASH PICTURE NARROW FRAME

DIRECT GLAZE
Direct glaze refers to a window with no sash. The glass is glazed directly into the frame and is stationary.

IN-SASH
In-sash Picture windows are non-operable, and they can match the profiles of windows with operable sash.

ULTIMATE CASEMENT NARROW FRAME AND PICTURE NARROW FRAME WINDOWS IN DESIGNER BLACK

ULTIMATE CORNER



ULTIMATE DIRECT GLAZE NARROW FRAME CORNER AND PICTURE WINDOWS IN WHITE

ULTIMATE CORNER

Make the most of your panoramic views by incorporating corner windows as a design focal point. Corner windows flood a room with natural light, and a stacked assembly can be a bold architectural statement for both the interior and exterior. Clear sightlines from multiple angles enhance the breathtaking view.



INTERIOR WITH DESIGNER BLACK
PAINTED INTERIOR FINISH*

EXTERIOR IN LIBERTY BRONZE*

CORNER DETAILS

The clad cap on the exterior and wood cap on the interior create a clean aesthetic and minimal visual disruption.



INTERIOR CLOSE UP
SHOWN IN DESIGNER BLACK



EXTERIOR CLOSE UP
SHOWN IN LIBERTY BRONZE

* Pictured above: Direct Glaze Picture Corner Window
In-Sash Picture Corner Window also available

ULTIMATE CORNER NARROW FRAME




CORNER NARROW FRAME WINDOW IN LIBERTY BROWN



CORNER NARROW FRAME AND PICTURE NARROW FRAME WINDOWS IN DESIGNER BLACK

ULTIMATE CORNER NARROW FRAME

The Ultimate Corner Narrow Frame window makes a strong architectural statement in expansive sizes, combining narrow profiles and clean lines with industry-leading performance. Pair this corner window with other Marvin narrow frame windows for consistent sightlines that maximize glass and views.



INTERIOR VIEW
WITH DESIGNER BLACK
PAINTED INTERIOR FINISH

EXTERIOR VIEW
IN LIBERTY BRONZE

CORNER DETAILS
The clad cap sits flush on the exterior, creating a clean-lined contemporary aesthetic. On the interior, the corner cap is stepped with a square profile.



INTERIOR CLOSE UP



EXTERIOR CLOSE UP

* Pictured above: Direct Glaze Picture Narrow Frame Corner Window
In-Sash Picture Narrow Frame Corner window not available

ULTIMATE SPECIALTY SHAPES




ULTIMATE SPECIALTY SHAPE DIRECT GLAZE WINDOWS WITH WHITE PAINTED INTERIOR FINISH



ULTIMATE SKYCOVE, DIRECT GLAZE SPECIALTY SHAPES WINDOWS, AND SLIDING FRENCH DOOR IN EBONY

ULTIMATE SPECIALTY SHAPES


The Ultimate Specialty Shape windows are available in hundreds of geometric shapes customized to add special flair to a window design. Many are available as operating windows, providing access to fresh air in addition to unique aesthetics.



INTERIOR



EXTERIOR



ULTIMATE BAY + BOW



ULTIMATE DOUBLE HUNG G2 BAY WINDOW



ULTIMATE CASEMENT BOW WINDOW IN WHITE

ULTIMATE BAY


Ultimate Bay windows are a group of connected windows extending outward from a room at desired angles—allowing light and views from multiple directions. Some feature a larger operating or stationary window flanked by smaller windows. Ultimate Bay windows can create space indoors for a cozy nook or window seat or maximize a scenic view to serve as a room’s focal point. They can be created with combinations of 3 to 6 casement or double hung windows (fixed or operating).



BAY INTERIOR WITH CASEMENT AND PICTURE WINDOWS

ULTIMATE BOW

Ultimate Bow windows are a series of windows connected to form a gentle outward curve. Typically made up of four or more windows, Ultimate Bow windows can create a small nook, open up a view, bring in more light, and boost visual appeal from inside and out. Bow windows are available with casement, double hung, or picture windows. They can be created with combinations of 3 to 6 casement or double hung windows (fixed or operating).



ULTIMATE CASEMENT BOW WINDOW IN BRONZE

DOORS



ULTIMATE MULTI-SLIDE DOOR AND DIRECT GLAZE POLYGON WINDOW IN VERTICAL GRAIN DOUGLAS FIR

DOOR TERMS + DEFINITIONS



1. FRAME

The door frame includes the head jamb across the top, side jambs, and the sill at the bottom. Marvin frames are built strong to stand up to heavy door usage year after year.

2. STILES + RAILS

The horizontal wood members of a door are called rails; the vertical components are called stiles. With a traditional French door design, the bottom rail is about 8 inches high with 4 ¾ inch stiles and top rail. Doors with a more contemporary style often feature more glass with stiles and rails as sleek as 3 inches.

3. SILL

Our door sills are made of Ultrex®, our proprietary pultruded fiberglass that is exceptionally strong and virtually impervious to time, weather, and pressure. Ultrex door sills provide excellent performance in hot or cold climates, plus durability over the long haul by being resistant to warping, denting, and fading.

4. PANELS

In a door, the panel is the main section, operating or stationary, that is installed into the frame. Marvin doors come in many sizes, some of the industry's largest, but they all share the tight tolerances for fit and quality finishes.

DOOR OPERATING STYLES



OUTSWING DOOR

Single or double swinging doors open to the exterior.



INSWING DOOR

Single or double swinging doors open to the interior.



SLIDING DOOR

Save space with a door panel that operates by sliding along a track.



BI-FOLD DOOR

This door folds open and closed like an accordion and can include up to 16 panels.



LIFT AND SLIDE DOOR

For openings as large as 48 feet wide and 12 feet high, substantial door panels fully open into pocket or stacked configurations.



MULTI-SLIDE DOOR

Another option to blend interior and outdoor living with a modular frame system.


MAKE EVERY ENTRANCE GRAND

Marvin doors are designed to maximize the potential of any opening, view, and living space.


DOOR FEATURES + OPTIONS



BEAUTY WITH PERFORMANCE
Designed for durability and to minimize air and water infiltration. Many of our door products are certified to a light commercial rating of PG40.



SOLID WOOD PANELS + FRAMES
The sound of a Marvin door closing is a quiet statement of quality. Wood in the panels and frames make for an elegant, crafted look and feel, and provides a weather-tight closure for outstanding energy efficiency.



MULTI-POINT LOCKING SYSTEM
Concealed stainless steel head and foot bolts within the door secure it solidly at three points. Choose either a keyed or non-keyed lever handle. Multi-point lock comes standard.

ADJUSTABLE HINGE
Standard on swinging doors, an adjustable hinge makes it easy to fine-tune the fit of a swinging door over the door's lifetime. Available in a variety of finishes, plus coastal options.

SILLS
Our Performance and Accessibility Sills are made of durable Ultrex fiberglass and provide solutions for varying applications.

RAISED AND FLAT PANELS
Raised and flat panels add depth and style to sliding and swinging French doors, including arch top swinging doors. This option changes the overall aesthetic of your door when less than a full lite of glass is desired.



ACCESSIBILITY SILL



PERFORMANCE SILL



ULTIMATE MULTI-SLIDE DOOR IN EBONY

ULTIMATE SWINGING NARROW PROFILE DOOR



ULTIMATE INSWING DOOR IN HAZELNUT WITH UNEQUAL PANEL WIDTHS AND MINIMALIST HANDLE IN MATTE BLACK



ULTIMATE INSWING DOOR IN PINE WITH MATTE BLACK HARDWARE

ULTIMATE SWINGING NARROW PROFILE DOOR


The Ultimate Swinging Narrow Profile door, available in both inswing and outswing, is expertly crafted to provide industry-leading performance with narrow sightlines and robust 2 ¼ inch standard panel thickness. Featuring contemporary 3 inch stiles and rails along with square interior and exterior glazing profiles. Choose from one or two operating panels in configurations up to 4 panels. Sizes up to 10 feet high and 14 feet wide.



INSWING
INTERIOR



INSWING
EXTERIOR



MINIMALIST HANDLE
IN MATTE BLACK

ULTIMATE SWINGING FRENCH DOOR G2



ULTIMATE INSWING FRENCH DOOR G2 WITH OIL RUBBED BRONZE HARDWARE

MARVIN SIGNATURE® COLLECTION



ULTIMATE INSWING FRENCH DOOR G2 AND ELEVATE DIRECT GLAZE WINDOW IN WHITE WITH SIMULATED DIVIDED LITES

ULTIMATE SWINGING FRENCH DOOR G2

The Ultimate Swinging French door G2, available in both inswing and outswing, delivers a traditional aesthetic with a 4 3/4 inch stile and top rail and a 4 3/4 inch or 8 1/8 inch bottom rail. Select sizes up to 10 feet high and 14 feet wide to maximize views and access to the outdoors. Choose up to 4 panels with an Ogee interior glazing profile.



INSWING
INTERIOR



INSWING
EXTERIOR



Available with IZ3

ULTIMATE SLIDING FRENCH DOOR G2



ULTIMATE SLIDING FRENCH DOOR G2 IN BRONZE



ULTIMATE SLIDING FRENCH DOOR G2 IN STAINED MULTI-GRAIN DOUGLAS FIR WITH MATTE BLACK HARDWARE

ULTIMATE SLIDING FRENCH DOOR G2

For the classic elegance of the French door with smooth, space-saving operation, our Ultimate Sliding French door G2 is built to your specifications. With a rich, luxurious fit, feel, and finish, available in configurations up to 16 feet wide and standard heights up to 10 feet, this door G2 offers a view with a grand entrance while conserving space for traffic flow or furniture layout. Available transom and stationary panels further enhance the view, flooding the room with daylight.



INTERIOR



EXTERIOR



HARP HANDLE IN MATTE BLACK

ULTIMATE SLIDING NARROW PROFILE DOOR




ULTIMATE SLIDING NARROW PROFILE DOOR IN BRONZE



ULTIMATE SLIDING NARROW PROFILE DOOR WITH VERTICAL PULL IN SATIN CHROME

ULTIMATE SLIDING NARROW PROFILE DOOR

The Ultimate Sliding Narrow Profile doors are created for smooth operation, performance, and amazing durability. Our tough Performance Sill withstands traffic and seasonal changes, contributing to both the door’s energy efficiency and incredibly smooth operation. The contemporary 3 inch stiles and rails maximize your view, while the multi-point lock system ensures a tight seal and security from top to bottom.



INTERIOR



EXTERIOR



INTERIOR AND EXTERIOR VIEWS OF VERTICAL PULL IN MATTE BLACK. AVAILABLE ON ULTIMATE SWINGING AND SLIDING DOORS.

ULTIMATE MULTI-SLIDE DOOR



ULTIMATE MULTI-SLIDE DOOR IN PEBBLE GRAY



ULTIMATE MULTI-SLIDE DOOR AND SKYCOVE® IN WHITE

ULTIMATE MULTI-SLIDE DOOR

The Ultimate Multi-Slide door is an ideal option to blend indoor and outdoor living, and the performance ratings of these doors match the exceptional views they frame. They're available in styles up to 6 panels uni-directional or 10 panels bi-parting. Both pocket and stacked designs are available with an optional scenic door sliding screen.



EXTERIOR



HARDWARE AND SILL

Pull and latch hardware provides easy operation and squared-off corners for a clean, contemporary look.



DESIGN FLEXIBILITY

Available in pocket or stacked configurations for openings up to 56 feet wide and 12 feet high. Pocketing configuration shown above.



Available with IZ3


ULTIMATE BI-FOLD DOOR



ULTIMATE DOUBLE HUNG AND PICTURE WINDOWS WITH BI-FOLD AND INSWING FRENCH DOORS

ULTIMATE BI-FOLD DOOR

The Ultimate Bi-Fold door provides big glass and clean design aesthetics to give homeowners more flexibility and a deep indoor-outdoor connection. Spanning 55 feet in width, the Ultimate Bi-Fold door is one of the widest panel doors in the industry. Without question, the Bi-Fold door is a simple, elegant solution for adjoining interior spaces or connecting to the outdoors. Available with a wood or clad exterior.



INTERIOR



INTERIOR PANEL HANDLE

The interior panel handle features a minimalist design that smoothly operates folding panels with a 90-degree twist and latches at the head and sill.

ULTIMATE BI-FOLD DOOR

ULTIMATE LIFT AND SLIDE DOOR



ULTIMATE LIFT AND SLIDE DOOR IN HONDURAN MAHOGANY WITH SATIN NICKEL HARDWARE Photo Courtesy of Dwell, Turkel Design, and 22 Waves Creative



ULTIMATE LIFT AND SLIDE DOOR IN BRONZE

ULTIMATE LIFT AND SLIDE DOOR

With openings up to 48 feet wide and 12 feet high, now you can add acres to your floor plan. Available with pocketing panels that slide into the wall, completely disappearing from view, or stacked panels that slide and stack perfectly within the door frame for a seamless transition from inside to out. Both are available with exclusive flush-mount handles and exterior finger pulls that virtually disappear when not in use.



INTERIOR



HARDWARE OPTIONS

Available with exclusive flush-mount hardware, interior finger pull, and optional exterior finger pull.



POCKET AND STACKED CONFIGURATION

When open, panels either slide into the wall cavity or stack neatly into the door frame. They glide on the inconspicuous 3/16 inch high exposed track.

ULTIMATE COMMERCIAL DOOR



ULTIMATE COMMERCIAL DOOR

ULTIMATE COMMERCIAL DOOR

The Ultimate Commercial door combines sophisticated design with the rugged durability to stand up to years of commercial use. Available in a wide variety of design and customization options, they're manufactured with different construction and assembly processes from our residential doors.



INTERIOR



EXTERIOR



PANIC RIM, CLOSER, REMOVABLE MULLION, AND SILL OPTIONS

ULTIMATE COMMERCIAL DOOR

OPTIONS



ULTIMATE INSWING FRENCH DOOR G2 AND ULTIMATE CASEMENT PUSH OUT WINDOW

INTERIOR FINISH OPTIONS

PINE

VERTICAL GRAIN
DOUGLAS FIR

MIXED GRAIN
DOUGLAS FIR

CHERRY

WHITE OAK

HONDURAN MAHOGANY

WOOD SPECIES

Offering a rich, warm look, many custom options, and design versatility, wood is a premium choice. Wood can be used on both the interior and exterior of our Ultimate windows and doors and provides great insulation. Treatments such as stain and paint work well when applied. Marvin sources the best, highest quality raw wood and uses refined techniques to process it.

STAIN + PAINT

Compared to painting or staining on the job site, our factory finishes provide consistent quality and performance. Our extensive knowledge about wood as a material and how it handles stains and paints, and the many years we've spent perfecting our finishing process, ensures your windows and doors arrive ready to install.



CLEAR

WHEAT

HONEY

HAZELNUT

LEATHER

CABERNET

ESPRESSO

Stain colors shown on Pine. To see more about finishes visit [Marvin.com](https://www.marvin.com).

DESIGNER BLACK

WHITE

PRIMED WHITE

EXTERIOR FINISH OPTIONS

STONE WHITE
COCONUT CREAM
SIERRA WHITE
CASHMERE
PEBBLE GRAY
HAMPTON SAGE
CADET GRAY
CLAY
CASCADE BLUE
SUEDE
GUNMETAL
WINEBERRY
BRONZE
BAHAMA BROWN
EVERGREEN
EBONY
BRIGHT SILVER (PEARLESCENT)
COPPER (PEARLESCENT)
LIBERTY BRONZE (PEARLESCENT)

CUSTOM COLOR: ANY COLOR YOU WANT

EXTRUDED ALUMINUM

Extruded aluminum is an extremely tough cladding that protects wood windows, mimics the profiles of wood, and provides superior durability. It is the most commonly ordered exterior material for our Ultimate products.

Select from our palette of 19 durable extruded aluminum colors, including a spectrum of rich hues and three pearlescent finishes. If you have more specialized needs, we can also work with you to create a custom color.

WOOD


Wood is a premium material for windows and doors, offering classic aesthetic appeal, many options for customization, and design versatility.

We treat exposed millwork with a water repellent wood preservative to help it last longer. Choose from one of the four options below. Each is ready to be finished to match your project's exacting requirements.

PINE
VERTICAL GRAIN DOUGLAS FIR
MAHOGANY
WESTERN RED CEDAR Exterior trim package only



Double Hung G2 window in Ebony



Double Hung G2 window in Suede


EXTERIOR CASINGS + SUBSILLS




BRICK MOULD CASING AND SPECIAL SUBSILL WITH CUSTOM MULL COVER IN HAMPTON SAGE

EXTERIOR CASINGS + SUBSILLS

Adding Marvin extruded aluminum or wood casings and subsills to your windows and doors provides great architectural detail to any home. Ultra-durable extruded aluminum casings feature a beautiful factory-applied finish that resists chalking, fading, pitting, corrosion, and marring. Casing profiles are consistent around the sides and top of a window or door, except for the Potter casing profile, which has a taller head. Custom casings and subsills are also available.



BRICK MOULD CASING
WITH A246 SUBSILL



FLAT CASING
WITH A246 SUBSILL



COLUMBUS CASING
WITH A1450 SUBSILL



RIDGELAND CASING
WITH A1453 SUBSILL



GRAYSON CASING
WITH A1451 SUBSILL



THORTON CASING
WITH A1450 SUBSILL



STRATTON CASING
WITH A1453 SUBSILL



POTTER CASING
WITH A217 SUBSILL



Grayson Casing in Bronze



Potter Casing with A1451 Subsill in Cascade Blue

DIVIDED LITES



ULTIMATE INSWING FRENCH DOOR G2 AND ROUND TOP WINDOW WITH CUSTOM SIMULATED DIVIDED LITES



MARVIN SIGNATURE® COLLECTION

DIVIDED LITES

Simulated divided lites, available in a number of different styles, mimic the look of individual panes of glass with the energy efficiency of dual pane insulated glass.

Our custom capabilities allow us to create almost any divided lite pattern to match your design style.




SIMULATED DIVIDED LITE (SDL)

SDL bars are permanently adhered to both sides of the glass. Simulated Divided Lites with Spacer Bars (SDLs) are an energy-efficient way to create the look of authentic divided lites.



AUTHENTIC DIVIDED LITE (ADL)


Separate panes of glass are glazed between muntin bars for historical accuracy. Available exclusively with wood exterior units.




GRILLES-BETWEEN-THE-GLASS (GBG)

Grilles are permanently installed between the glass panes. This low-maintenance grille offers the look of a divided lite pattern with the ease of cleaning just one pane of glass. Available with different interior and exterior colors.

OGEE DIVIDED LITE WIDTHS



SQUARE DIVIDED LITE WIDTHS



GLASS + GLAZING



ULTIMATE AWNING AND PICTURE WINDOWS AND INSWING FRENCH DOOR IN PEBBLE GRAY

GLAZING PROFILES


Interior and exterior glazing profiles are available in Ogee and Square. Choose Ogee for more traditional projects, and Square for a clean, contemporary look. Interior and exterior glazing profile options vary by product type.



OGEE



SQUARE



SQUARE EXTERIOR GLAZING PROFILE



DUAL PANE GLAZING

Our standard glazing is dual pane: two panes of glass with Low E coatings and insulated with argon gas. Compared to a single glass pane, dual pane glass cuts energy costs significantly because of low emissivity coating and the gas-filled insulating space between the glass layers.



TRIPLE PANE GLAZING


Triple pane glazing consists of three panes of glass with Low E coatings applied to the surface. Two glass spaces are insulated with argon gas between the panes. Available in products where glazing thickness can be greater than ¾ inch.

GLASS + GLAZING

The thermal and structural properties of wood combined with the right glazing make Marvin wood and extruded aluminum clad products an optimal choice for energy efficiency. We offer thousands of window and door options with two or three panes of glass and a range of glazing options to meet the performance challenges of any climate.

GLASS COATINGS

Low E coatings are microscopically thin, essentially invisible coatings on the glass surface that help manage the amount of light and heat conducted through a window pane or reflected away from it, reducing a home's dependence on heat and air conditioning. The national ENERGY STAR® program recognizes products that meet strict energy-efficiency guidelines to suit climates in different areas of the country, and Marvin offers products to meet climate and code requirements in every region.



LOW E1

Low E1 coating is a good choice when you want maximum solar heat gain and radiant heating properties. This type of coating is generally used in Northern climates where heating is prioritized over cooling. You'll reap maximum benefits when windows with this type of coating are positioned to receive direct sun exposure.

LOW E2

The most common Low E coating since it works well across most geographic regions and climates. Low E2 with two metallic coatings balances less solar heat gain and improved radiant heating properties.


LOW E3

Used in applications where solar heat gain may be a concern, low E3 coating uses multiple metallic layers for radiant properties similar to Low E2. This type of coating is most commonly used in Southern, sunny climates where cooling is prioritized over heating.

SPECIALTY GLASS

Our specialty options include glass for unique project needs like sound abatement (STC/OITC), high altitudes, Sea Turtle Conservation Codes, and California fire zones. We also offer laminated glass on certain products that are designed specifically for hurricane zones.

A variety of decorative glass options, including those shown below and others, are available to meet the unique needs of each project. Laminated glass is also available in clear, bronze, gray, or green with tinted interlayers.



HOME AUTOMATION



ULTIMATE CASEMENT WINDOW AND SLIDING FRENCH DOOR WITH CONCEALED LOCK STATUS SENSOR



ULTIMATE MULTI-SLIDE DOOR

LOCK STATUS SENSOR

Our Lock Status Sensor brings smart home capabilities to Marvin windows and doors. This affordable solution is installed in the factory and fully concealed—meaning no unsightly sensors attached on the exterior or interior and no additional modification of your product once installed. The sensor can be wired or wirelessly connected, working in tandem with your smart home security system to indicate if windows and doors are closed and locked and providing peace of mind when security is a concern.



SCREENS



ULTIMATE DOUBLE HUNG INSERT G2 WINDOW IN STONE WHITE WITH FULL SCREENS

SCREENS

Choose from an aluminum surround in three finishes or a wood interior surround that complements warm wood interiors. Marvin screens come standard with Marvin Bright View™ – a fiberglass screen mesh that provides improved airflow and more natural light while keeping insects out. Bright View repels water and resists dirt and grime for a sharp, vivid view.

CASEMENT SCREEN OPTIONS




WOOD SCREEN SURROUND
The patented wood screen surround with wood interior and aluminum exterior features Marvin Bright View™ screen mesh. Aluminum screen mesh options also available.




INSWING CASEMENT SCREEN
The beautifully crafted inswing screen adds a classic touch and allows access to operate push-out casement and awning windows.


SCREEN MESH OPTIONS




MARVIN
BRIGHT VIEW™




CHARCOAL
ALUMINUM WIRE




BLACK
ALUMINUM WIRE



BRIGHT
ALUMINUM WIRE



BRIGHT
BRONZE WIRE



CHARCOAL
FIBERGLASS

DOUBLE HUNG SCREEN OPTIONS



FULL OR HALF SCREEN

Exterior aluminum screen with an aluminum surround. The full screen covers both the top and bottom sash. The half screen only covers the bottom sash.



DOUBLE HUNG STORM OPTIONS



TWO-LITE WOOD STORM SASH OR SCREEN

A wood frame containing non-removable glass. The storm sash can be removed during the summer and replaced with a wood-framed screen. Available only for wood windows.



STORM AND SCREEN COMBINATIONS

A combination unit is composed of two glass panels and one screen panel that can be easily removed from the interior for cleaning. Available with a wood (bare or primed) or aluminum surround, panels can be configured multiple ways, glass above screen, screen above glass, or glass above glass.



ENERGY PANEL

Often confused with storm windows, an energy panel is technically a glazing option. It is a removable, exterior glass panel finished on the edges by a surround. Energy panels cover the exposed glass surface of each sash and offer added energy efficiency for wood windows with single glazing.

DOOR SCREEN OPTIONS



SCENIC DOOR SLIDING SCREEN

The Marvin Ultimate Sliding Screen operates with ease and conceals when not in use. The screen is unobtrusive even in large sizes measuring up to 15 feet wide and up to 10 feet high uni-directional or up to 29.5 feet wide bi-parting.



ULTIMATE SWINGING SCREEN DOOR

With profiles that complement the aesthetics of the door, swinging door screens feature robust, durable extruded aluminum surrounds and concealed hinges.




ULTIMATE SLIDING SCREEN DOOR

Aluminum top hung sliding screen with roller bar, adjustable rollers and unmatched sliding operation.

Marvin window and door screens come standard with Marvin Bright View™ – a fiberglass screen mesh that provides improved airflow and more natural light while keeping insects out. Bright View repels water and resists dirt and grime for a sharp, vivid view.

WINDOW OPENING CONTROL DEVICES

Marvin Window Opening Control Devices (WOCD) meet the ASTM F2090-21 standard, created to assist in the prevention of window falls. To meet the standard, our devices limit the window's net clear opening to less than 4 inches (when the sash is open) and have a release function allowing the window to open completely. In order to meet the safety standard, WOCD disengagement takes two independent actions, which helps prevent accidental release. Devices will then automatically reengage once the window is closed and again limit the window opening to less than 4 inches upon re-opening.



ULTIMATE CASEMENT



ULTIMATE DOUBLE HUNG G2



ULTIMATE GLIDER

WINDOW HARDWARE



ULTIMATE DOUBLE HUNG G2 WINDOW WITH AUTO-LOCKING SASH LOCK IN SATIN NICKEL

WINDOW HARDWARE

Ultimate’s durable and elegant hardware is engineered for reliability and to harmonize with any décor. Choose a finish to complement your architectural style. Durable painted finishes in Matte Black, Satin Taupe, Bronze, and White mimic the look of metal. Satin Nickel, Brass, Antique Brass, Polished Chrome, Oil Rubbed Bronze, and Satin Chrome offer the rich appearance and durability of authentic metal finishes.



AUTO-LOCKING HARDWARE SYSTEM

PRODUCTS:
Ultimate Double Hung G2
Ultimate Single Hung G2

AVAILABLE FINISHES:
Matte Black • Brass • Satin Taupe
Satin Nickel • Bronze • White
Antique Brass • Oil Rubbed Bronze
Polished Chrome • Satin Chrome



TRADITIONAL LIFT LOCK

PRODUCTS:
Ultimate Single Hung G2

AVAILABLE FINISHES:
Matte Black • Brass • Satin Taupe
Satin Nickel • Bronze • White
Antique Brass • Oil Rubbed Bronze
Polished Chrome • Satin Chrome



CONTEMPORARY LIFT LOCK

PRODUCTS:
Ultimate Single Hung G2

AVAILABLE FINISHES:
Matte Black • Brass • Satin Taupe
Satin Nickel • Bronze • White
Antique Brass • Oil Rubbed Bronze
Polished Chrome • Satin Chrome



FOLDING HANDLE

PRODUCTS:
Ultimate Casement • Ultimate Awning
Ultimate Casement Narrow Frame
Ultimate Awning Narrow Frame

AVAILABLE FINISHES:
Matte Black • Brass • Satin Taupe
Satin Nickel • Bronze • White
Antique Brass • Oil Rubbed Bronze
Polished Chrome • Satin Chrome



PUSH OUT HANDLE

PRODUCTS:
Ultimate Casement • Ultimate Awning
Ultimate Casement Narrow Frame
Ultimate Awning Narrow Frame

AVAILABLE FINISHES:
Matte Black • Brass • White
Antique Brass • Oil Rubbed Bronze
Satin Nickel



FOLDING HANDLE

PRODUCTS:
Ultimate Glider

AVAILABLE FINISHES:
Matte Black • Brass • Satin Taupe
Satin Nickel • Bronze • White
Antique Brass • Oil Rubbed Bronze
Polished Chrome • Satin Chrome

FINISHES



DOOR HARDWARE



ULTIMATE SWINGING DOOR WITH MINIMALIST HANDLE IN MATTE BLACK

DOOR HARDWARE

Ultimate door hardware is engineered for durability, ergonomics, and to be a beautiful complement to your Marvin door. Satin Nickel, Brass, and Oil Rubbed Bronze finishes are available with a PVD finish. The Physical Vapor Deposition (PVD) process adds a layer of toughness to hardware exposed to environmental factors like direct sun and humidity. PVD finishes resist fading and discoloration, even in coastal areas.



TRADITIONAL¹

- AVAILABLE FINISHES:**
Matte Black • Satin Taupe • Dark Bronze • White
Antique Brass • Satin Chrome
Oil Rubbed Bronze
Polished Chrome
- PVD FINISHES:**
Satin Nickel • Brass
Oil Rubbed Bronze



CONTEMPORARY¹

- AVAILABLE FINISHES:**
Matte Black • Dark Bronze
- PVD FINISHES:**
Satin Nickel
Oil Rubbed Bronze



MINIMALIST²

- AVAILABLE FINISHES:**
Matte Black • Dark Bronze
- PVD FINISHES:**
Satin Nickel
Oil Rubbed Bronze



ADJUSTABLE HINGE

- AVAILABLE FINISHES:**
Matte Black • Satin Taupe
Dark Bronze • White
Antique Brass • Satin Chrome
Polished Chrome
Oil Rubbed Bronze
Goldtone • Silver Frost
- PVD FINISHES:**
Satin Nickel • Brass
Oil Rubbed Bronze



NARROW CONTEMPORARY³

- AVAILABLE FINISHES:**
Matte Black • Dark Bronze
- PVD FINISHES:**
Satin Nickel
Oil Rubbed Bronze



HARP⁴

- AVAILABLE FINISHES:**
Matte Black • Satin Taupe
Dark Bronze • White
Antique Brass • Satin Chrome
Oil Rubbed Bronze
Polished Chrome
- PVD FINISHES:**
Satin Nickel • Brass
Oil Rubbed Bronze



VERTICAL PULL⁴

- AVAILABLE FINISHES:**
Matte Black • Dark Bronze
- PVD FINISHES:**
Satin Nickel • Brass
Oil Rubbed Bronze



EXTERIOR FLUSH PULL⁴

- AVAILABLE FINISHES:**
Matte Black • Dark Bronze
- PVD FINISHES:**
Satin Nickel
Oil Rubbed Bronze

FINISHES



(1) Available on Ultimate Swinging French door G2

(2) Available on Ultimate Swinging door and Ultimate Swinging French door G2

(3) Available on Ultimate Swinging door

(4) Available on Ultimate Sliding door and Ultimate Sliding French door G2

GALLERY HARDWARE



ROCKY MOUNTAIN HARDWARE WITH EDGE ESCUTCHEON, SHIFT LEVER, AND WIRE TEXTURE IN SILICON BRONZE MEDIUM

GALLERY HARDWARE

Marvin Gallery Hardware is a curation of door hardware from three renowned manufacturers. Each set chosen meets Marvin’s high standards for aesthetics, quality, and craftsmanship.

This hardware collection makes it easy for you to find the hardware choice that perfectly reflects your unique design sensibilities, vision, and personality. From contemporary to traditional, each beautiful piece heightens the aesthetics of any Marvin door.



ASHLEY NORTON

Established in 1987, Ashley Norton is one of the leading designers of fine architectural hardware. With a broad range of designs to suit any architectural style and an abundance of finish options. Ashley Norton solid brass and bronze hardware is built by the most talented craftsman for the most discerning customers.



BOUVET

Founded in 1884 in France by famed ironworker Gustave Bouvet. Metal Style Bouvet combines traditional French ironwork craftsmanship and materials with modern technology to create distinctive hardware for equally distinctive doors. Metal Style Bouvet represents the finest of decorative French-inspired hardware.




ROCKY MOUNTAIN HARDWARE

Rocky Mountain Hardware is expertly crafted in America using only the finest art-grade bronze and precision mechanisms. With over three decades of experience, Rocky Mountain Hardware continues to set itself apart with inimitable style, boundless capabilities, and exceptional quality guaranteed to stand the test of time.




GALLERY HARDWARE

ASHLEY NORTON



URBAN ESCUTCHEON
CLAROS LEVER
DARK BRONZE FINISH

URBAN ESCUTCHEON
ATLAS LEVER
SATIN CHROME FINISH



ARCH ESCUTCHEON
CHESTER LEVER
POLISHED BRASS FINISH

ANGULAR ESCUTCHEON
ADONIS LEVER
DARK BONZE FINISH




URBAN ESCUTCHEON
DUNN PULL
DARK BRONZE FINISH

BOUVET



RECTANGULAR
ESCUTCHEON
BIRDCAGE 1054 LEVER
BLACK FINISH

RECTANGULAR
ESCUTCHEON
TWISTED 1055 LEVER
PEWTER FINISH



ARCH ESCUTCHEON
CLASSIC 1052 LEVER
PEWTER FINISH

RECTANGULAR
ESCUTCHEON
SQUARE 1051 LEVER
BLACK FINISH



ARCH ESCUTCHEON
ARRONDIE PULL 3352
BLACK FINISH



ARCH ESCUTCHEON
BIRDCAGE 3353 PULL
PEWTER FINISH

ROCKY MOUNTAIN HARDWARE



CURVED E539 ESCUTCHEON
HOOK L104 LEVER
WHITE BRONZE
MEDIUM FINISH

STEPPED ESCUTCHEON
LEGACY L109 LEVER
SILICON BRONZE
DARK FINISH



STEPPED ESCUTCHEON
SQUIRREL TAIL L102 LEVER
SILICON BRONZE FINISH

CURVED ESCUTCHEON
RIDGE L224 LEVER
WHITE BRONZE
BRUSHED FINISH



TROUSDALE ESCUTCHEON
OFFSET TROUSDALE
GRIP G30300
SILICON BRONZE DARK
LUSTRE FINISH



EDGE ESCUTCHEON
OFFSET D GRIP SDP6
SILICON BRONZE
LIGHT FINISH
BASIC TEXTURE



COASTAL



ULTIMATE DOUBLE HUNG G2 AND ROUND TOP WINDOWS AND OUTSWING FRENCH DOOR G2 IN STONE WHITE

COASTAL PRODUCTS

COASTAL PRODUCTS

Coastal living is beautiful and serene until the storms hit. When you live by the water, you need to know that your windows and doors will stand up to the challenge of coastal conditions. We offer windows and doors specifically designed for the extreme conditions and construction requirements of coastal zones.

	ULTIMATE CASEMENT + AWNING Offer a variety of customization, expert craftsmanship and superior value. Casement is also available in Round Top.
	ULTIMATE DOUBLE HUNG G2 Blends traditional beauty with state-of-the-art window performance. Also available in an operating Round Top.
	ULTIMATE WOOD DOUBLE HUNG Incredibly durable, versatile and easy-to-use. An all-wood exterior and interior bring beautiful and classic style to your project. Also available in Round Top.
	PICTURE / DIRECT GLAZE / TRANSOM Picture (in-operable in-sash glazing - like Casement and Awning) and Direct Glaze (in-operable with direct to frame glazing) windows are available in a wide range of polygon and radius shapes. Transoms are in-sash glazed and can be stationary or operating.
	ULTIMATE BI-FOLD DOOR Creates a wide-open transition to outdoor spaces. Spanning up to 55 feet in width, the Bi-Fold door offers more glass and a clean aesthetic.



ULTIMATE MULTI-SLIDE DOOR

Blends exceptional views and indoor/outdoor living with performance. Available in styles up to six panels uni-directional and ten panels bi-parting.



2 1/4" ULTIMATE SWINGING FRENCH DOOR G2

Combines a traditional French style with expert craftsmanship, engineered for both quality and performance. Select from inswing or outswing operation in configurations up to 14 feet wide.



2 1/4" ULTIMATE SWINGING NARROW PROFILE DOOR

The narrow 3-inch stiles and rails increase the glass opening and help provide larger views. Choose between inswing or outswing operation and configurations of up to four panels.



2 1/4" ULTIMATE SLIDING FRENCH DOOR G2

The elegant look of a traditional French door with a space-saving sliding design. Available in 4 panels up to 16 feet wide x 10 feet high. Superior quality with nearly effortless operation.



2 1/4" ULTIMATE SLIDING NARROW PROFILE DOOR

Features 3-inch stiles and rails for a more contemporary look. Available in 4 panels up to 12 feet wide and 8 feet high.



MULL OPTIONS

Dramatic ocean views are often created by grouping IZ3 windows in an assembly, sometimes joining them both horizontally and vertically. The space between the windows where they are joined together is called a mull. Mulling options for Marvin IZ3 Ultimate Casement windows and Ultimate Double Hung windows with frame-to-frame mulling configurations are WDMA certified in most sizes.



ULTIMATE DIRECT GLAZE PICTURE AND CASEMENT WINDOWS



Since we opened as a family-owned and -operated lumber and cedar company in 1912, Marvin has designed products to help people live better. We remain committed to bringing beauty and simplicity into people's lives with windows and doors that stand the test of time.

MARVIN.COM

©2024 Marvin Lumber and Cedar Co., LLC. All rights reserved.
®Registered trademark of Marvin Lumber and Cedar Co., LLC.
ENERGY STAR® and the ENERGY STAR certification mark are registered US marks.

Cover image: Ultimate Casement and Direct Glaze in Bronze

Part #19980958. November 2024. [MUT]

Colors shown in printed materials are simulations and may not precisely duplicate product or finish colors. Contact your local Marvin dealer to view actual product and finish color samples.