

CHLOE WRIGHT HOUSE
1835



269

It is to be hoped that this is the final resting place of the Chloe Wright House (40, 43).


From 1835 until 1909, it remained on its original site at 2566 Hudson-Aurora Road. In 1909, it was moved 200 yards to the northwest and, over the years, became known as the Grissom farmhouse. It was rescued from the onslaught of housing developers by Katie Coulton in 1983, moved to its present site and restored by Don Reisig. The original barn was never moved from the first farm; an outbuilding from its second site, the Grissom Farm, serves as a garage for this house. There are additions to the original Greek Revival structure at the rear and the west. Heavy moldings, interior and exterior, reflect the late Greek Revival style.

This house is pictured in the 1874 *Combination Atlas Map of Summit County* as the George Bentley House.



H
G
F
E
D
C
B
A

OWEN BROWN STREET



1 SITE PLAN
SCALE: 1/8" = 1'-0"



MORRIS RESIDENCE - GARAGE ADDITION

63 Owen Brown Street
Hudson, Ohio 44236

Date	
05/23/20	PROGRESS SET
07/24/20	PROGRESS SET
08/04/20	AHBR SUBMITTAL

Scale As Noted

Site Plan

A0.1

1 2 3 4 5 6 7 8 9 10

Project Overview

The Grissom farmhouse (1835 Chloe-Wright House) and granary were located at the corner of Hudson-Aurora and Stow Roads, now the site of the Hudson High School. Both structures were rescued from threatened demolition and moved to 63 Owen Brown Street in the summer of 1983, where they were restored and preserved by house restoration contractor Don Reisig.

The renovation/restoration of the house includes replacing the existing windows (not original to the house), adding two shed dormers (one of which was original to the house, but later demolished during the first restoration), and consideration on replacing the existing cedar lap siding (only) with the same material and exposure.

The original double-hung wood windows were two-over-two lite sashes, not six-over-six, as currently seen in the house. Early photographs of the Grissom farmhouse clearly shown this pattern, which is more historically accurate for the period of the house. The six-over-six lite double-hung wood windows were installed during the 1983 restoration, as the originals were beyond repair.

Early photographs of the Grissom farmhouse also show a shed dormer located on the left side of the house, where a bathroom had once existed. The project proposes to re-install the second-floor bathroom and shed dormer, as seen on the proposed west elevation. A similar shed dormer is also being proposed on the north elevation (back) of the house, toward the east side. This shed dormer will also improve the limited head-height/clearances currently inside the existing Master Bathroom. Both shed dormers have 3:12 roof slopes with asphalt shingle to match the existing roof. Both shed dormers would not be directly visible from Owen Brown Street and are stepped-back and concealed behind the main house massing, gabled roof form and front elevation.

H

TOP OF RIDGE
EL. +18'-10"
TOP OF RIDGE
EL. +17'-1"



1 EXISTING SOUTH (FRONT) ELEVATION
SCALE: 1/4" = 1'-0"

G

SECOND FLOOR LEVEL
EL. +8'-4-3/4"

F

FIRST FLOOR LEVEL
EL. +0'-0"



2 EXISTING EAST (RIGHT) ELEVATION
SCALE: 1/4" = 1'-0"

E

TOP OF RIDGE
EL. +18'-10"
TOP OF RIDGE
EL. +17'-1"



3 EXISTING NORTH (BACK) ELEVATION
SCALE: 1/4" = 1'-0"

D

SECOND FLOOR LEVEL
EL. +8'-4-3/4"

C

FIRST FLOOR LEVEL
EL. +0'-0"

SECOND FLOOR LEVEL
EL. +8'-1-1/4"



4 EXISTING WEST (LEFT) ELEVATION
SCALE: 1/4" = 1'-0"

B

A

KEYNOTES: ① →

- 1. EDIT
- 2. EDIT
- 3. EDIT
- 4. EDIT
- 5. EDIT
- 6. EDIT
- 7. EDIT
- 8. EDIT
- 9. EDIT
- 10. EDIT
- 11. EDIT
- 12. EDIT

NOTES:

LEGEND:

MORRIS RESIDENCE - RENOVATION

63 Owen Brown Street
Hudson, Ohio 44236

Date	Progress
05/17/20	PROGRESS SET
05/28/20	PROGRESS SET
07/24/20	PROGRESS SET
08/04/20	AHBR SUBMITTAL


Scale As Noted

Existing Building Elevations

A2.0




1 PROPOSED SOUTH ELEVATION (FRONT)
SCALE: 1/4" = 1'-0"



2 PROPOSED EAST ELEVATION (RIGHT)
SCALE: 1/4" = 1'-0"



3 PROPOSED NORTH ELEVATION (BACK)
SCALE: 1/4" = 1'-0"



4 PROPOSED WEST ELEVATION (LEFT)
SCALE: 1/4" = 1'-0"

KEYNOTES: ① →

- 1. LINE OF EXISTING GRADE
- 2. LINE OF EXISTING CRAWL SPACE CONCRETE SLAB AND CMU BLOCK FOUNDATION WALL BELOW
- 3. EXISTING SANDSTONE BLOCK LANDSCAPE RETAINING WALL
- 4. EXISTING SANDSTONE BLOCK STEPS
- 5. EXISTING PARGE COAT FINISH OVER EXISTING CMU BLOCK FOUNDATION WALL.
- 6. EXISTING SCREENED-IN PORCH
- 7. BID ALTERNATE, NEW CEDAR WOOD HORIZONTAL LAP SIDING TO MATCH EXISTING WITH 4.5" EXPOSURE. PAINTED.
- 8. NEW CEDAR WOOD HORIZONTAL LAP SIDING AT SHED DORMER, TO MATCH EXISTING WITH 4.5" EXPOSURE. PAINTED.

- 9. 1"x4" CORNER TRIM TO MATCH EXISTING. PAINTED.
- 10. 1"x6" RAKE AND FASCIA BOARD. PAINTED.
- 11. NEW WOOD WINDOW SILL TO MATCH EXISTING PROFILE. PAINTED. TYPICAL.
- 12. NEW WOOD WINDOW TRIM/SURROUND TO MATCH EXISTING PROFILE AND DETAILS. PAINTED. TYPICAL.
- 13. EXISTING WOOD PANELED DOOR TO BE RESTORED AND REFINISHED. PROVIDE NEW WEATHER STRIPPING AND THRESHOLD AND HARDWARE. BALDWIN HARDWARE TO HAVE OIL-RUBBED BRONZE FINISH.
- 14. EXISTING WOOD FRIEZE BOARD AND CORNICE RETURN TO REMAIN.
- 15. EXISTING ASPHALT SHINGLED ROOF

- 16. NEW ASPHALT SHINGLED ROOF AT SHED DORMER. PINNACLE PRISTINE "HEARTHSTONE" ARCHITECTURAL SHINGLE. PROVIDE ICE & WATER UNDERLAYMENT FOR ENTIRE ROOF.
- 17. PROVIDE NEW METAL DRIP EDGE, PAINT TO MATCH TRIM COLOR.
- 18. NEW PRE-FINISHED PAINTED ALUMINUM 5" HALF-ROUND GUTTER, HANGERS AND 3" PLAIN ROUND DOWNSPOUT W/ BRACKETS AND CHEATS, AS REQUIRED. PAINT TO MATCH TRIM COLOR.
- 19. NEW PELLA "RESERVE TRADITIONAL" ALUMINUM-CLAD, WOOD DOUBLE-HUNG WINDOW WITH 2/2 LITE AND 1LT GRILLE. ALL HARDWARE TO BE OIL-RUBBED BRONZE FINISH.
- 20. NEW PELLA "RESERVE TRADITIONAL" ALUMINUM-CLAD, WOOD AWNING WINDOW WITH 1LT GRILLE. ALL HARDWARE TO HAVE OIL-RUBBED BRONZE FINISH.

NOTES:

LEGEND:


MORRIS RESIDENCE - RESTORATION
63 Owen Brown Street
Hudson, Ohio 44236

Date	
05/17/20	PROGRESS SET
05/28/20	PROGRESS SET
07/24/20	PROGRESS SET
08/04/20	AHBR SUBMITAL
Scale	As Noted


Proposed Building Elevations

A2.1


H
G
F
E
D
C
B
A



1 EXISTING CRAWL SPACE PLAN
SCALE: 1/4" = 1'-0"



2 EXISTING FIRST FLOOR PLAN
SCALE: 1/4" = 1'-0"



3 EXISTING SECOND FLOOR PLAN
SCALE: 1/4" = 1'-0"

KEYNOTES: 1

1. LINE/EDGE OF NEW MASONRY FOUNDATION WALL/WOOD SILL PLATE BELOW.
2. NEW 2"x10" WOOD JOIST @ 16" O.C.
3. SISTER NEW JOISTS WITH EXISTING 2"x10" WOOD JOISTS OR PROVIDE 2X10 RIM BOARD ANCHORED TO EXISTING RIM BOARD/FRAMING
4. PROVIDE 2X WOOD BLOCKING AT RECESSED STONE SLAB HEARTH AND BUILT-IN BOOKCASES.
5. PROVIDE (3) 2X4 POSTS (EACH SIDE) AT NEW LVL HEADER BEAM OVER POCKET DOOR OPENING.
6. NEW LVL HEADER AT POCKET DOOR OPENING ABOVE. REFER TO FRAMING PLAN
7. NEW DOUBLE 2X8 WOOD HEADER ABOVE WINDOW OPENING W/(2) 2X4 POSTS (EACH SIDE). TYPICAL
8. LINE OF STONE SLAB HEARTH ABOVE
9. NEW 6" DIA. METAL SUPPLY AIR DUCT. SEE BASEMENT/FOUNDATION PLAN. COORDINATE ROUTING OF SUPPLY AIR DUCTS WITH NEW/EXISTING JOIST SPACING
10. RELOCATED METAL SUPPLY AIR BASEBOARD REGISTER.
11. NEW 2-1/4" RED OAK WOOD PLANK FLOORING TO MATCH EXISTING KITCHEN FLOOR LEVEL AND STAIN FINISH/COLOR.
12. PROVIDE FLUSH 2-1/4" RED OAK WOOD BORDER AROUND RECESSED STONE SLAB HEARTH.
13. NEW RED OAK WOOD FLOOR REGISTERS TO BE FLUSH AND MATCH NEW OAK FLOORING
14. 5'-3" X 12" X 1-1/2" STONE SLAB HEARTH TO BE RECESSED/FLUSH W/ WOOD FLOORING. OWNER TO SELECT STONE TYPE AND FINISH.
15. WHITE MOUNTAIN HEARTH, "BRECKENRIDGE SELECT" 36 VENT-FREE GAS FIREBOX, BY EMPIRE COMFORT SYSTEMS. OWNER TO SELECT FINISHES, OPTIONS & ACCESSORIES
16. BUILT-IN WOOD BOOKCASE W/ADJUSTABLE SHELVING, COUNTERTOP AND CABINETS BELOW. PAINTED. SEE SHEET A4.0 FOR INTERIOR ELEVATIONS AND DETAILS.
17. NEW 2'-6" X 6'-8" WOOD FRENCH POCKETING DOORS WITH GLASS-LITES. SEE SHEET A4.0 FOR INTERIOR ELEVATIONS.
18. POCKET DOOR FRAME ASSEMBLY BY JOHNSON HARDWARE, 1500 SERIES, OR EQUAL. OWNER TO SELECT HARDWARE/PULL STYLE AND FINISH.
19. REMOVE AND REINSTALL MODIFIED EXISTING WOOD HANDRAIL AND BALUSTRADE
20. REMOVE AND REINSTALL EXISTING WROUGHT-IRON HANDRAILS
21. LINE OF SLOPED CEILING ABOVE. REFER TO REFLECTED CEILING PLAN AND SECTION DRAWINGS.
22. RECESSED CAN LIGHT ABOVE. REFER TO REFLECTED CEILING PLAN ON SHEET A1.2
23. ELECTRICAL POWER OUTLET. REFER TO INTERIOR ELEVATIONS FOR QUANTITY, LOCATION AND DIMENSIONS.
24. LINE OF MANTEL ABOVE. REFER TO SHEET A4.0 INTERIOR ELEVATIONS FOR DETAILS.

NOTES:

- A. ALL DIMENSIONS ARE TO FACE OF STUD (I.F.O.S.), UNLESS NOTED OTHERWISE
- B. REFER TO SHEET A4.0 INTERIOR ELEVATIONS FOR ADDITIONAL MATERIAL AND FINISH SCOPE OF WORK.

LEGEND:

- EXISTING MASONRY WALL
- EXISTING CONSTRUCTION
- REMOVE EXISTING CONSTRUCTION
- NEW CONSTRUCTION
- NEW CMU BLOCK FOUNDATION WALL
- INDICATES EXISTING/NEW CEILING HEIGHT, ABOVE FINISHED FLOOR (A.F.F.) OR FINISHED FLOOR LEVEL (F.F.L.)
- ELECTRICAL POWER OUTLET

MORRIS RESIDENCE - RESTORATION

63 Owen Brown Street
Hudson, Ohio 44236


Date	Progress Set
05/17/20	PROGRESS SET
05/28/20	PROGRESS SET
07/24/20	PROGRESS SET
08/04/20	AHBR SUBMITTAL
Scale	As Noted

Existing Basement, First & Second Floor Plans


A1.0

1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10


H
G
F
E
D
C
B
A



1 PROPOSED CRAWL SPACE PLAN
SCALE: 1/4" = 1'-0"



2 PROPOSED FIRST FLOOR PLAN
SCALE: 1/4" = 1'-0"



3 PROPOSED SECOND FLOOR PLAN
SCALE: 1/4" = 1'-0"

KEYNOTES: ①

- LINE/EDGE OF NEW MASONRY FOUNDATION WALL/WOOD SILL PLATE BELOW.
- NEW 2"x10" WOOD JOIST @ 16" O.C.
- SISTER NEW JOISTS WITH EXISTING 2"x10" WOOD JOISTS OR PROVIDE 2X10 RIM BOARD ANCHORED TO EXISTING RIM BOARD/FRAMING
- PROVIDE 2X WOOD BLOCKING AT RECESSED STONE SLAB HEARTH AND BUILT-IN BOOKCASES.
- PROVIDE (3) 2X4 POSTS (EACH SIDE) AT NEW LVL HEADER BEAM OVER POCKET DOOR OPENING.
- NEW LVL HEADER AT POCKET DOOR OPENING ABOVE. REFER TO FRAMING PLAN
- NEW DOUBLE 2X8 WOOD HEADER ABOVE WINDOW OPENING W/(2) 2X4 POSTS (EACH SIDE) TYPICAL

- LINE OF STONE SLAB HEARTH ABOVE
- NEW 6" DIA METAL SUPPLY AIR DUCT. SEE BASEMENT/FOUNDATION PLAN. COORDINATE ROUTING OF SUPPLY AIR DUCTS WITH NEW/EXISTING JOIST SPACING
- RELOCATED METAL SUPPLY AIR BASEBOARD REGISTER.
- NEW 2-1/4" RED OAK WOOD PLANK FLOORING TO MATCH EXISTING KITCHEN FLOOR LEVEL AND STAIN FINISH/COLOR.
- PROVIDE FLUSH 2-1/4" RED OAK WOOD BORDER AROUND RECESSED STONE SLAB HEARTH.
- NEW RED OAK WOOD FLOOR REGISTERS TO BE FLUSH AND MATCH NEW OAK FLOORING
- 5'-3" X 12" X 1-1/2" STONE SLAB HEARTH TO BE RECESSED/FLUSH W/ WOOD FLOORING. OWNER TO SELECT STONE TYPE AND FINISH.

- WHITE MOUNTAIN HEARTH, "BRECKENRIDGE SELECT" 36 VENT-FREE GAS FIREBOX, BY EMPIRE COMFORT SYSTEMS. OWNER TO SELECT FINISHES, OPTIONS & ACCESSORIES
- BUILT-IN WOOD BOOKCASE W/ADJUSTABLE SHELVING, COUNTERTOP AND CABINETS BELOW. PAINTED. SEE SHEET A4.0 FOR INTERIOR ELEVATIONS AND DETAILS.
- NEW 2'-6" X 6'-8" WOOD FRENCH POCKETING DOORS WITH GLASS-LITES. SEE SHEET A4.0 FOR INTERIOR ELEVATIONS.
- POCKET DOOR FRAME ASSEMBLY BY JOHNSON HARDWARE, 1500 SERIES, OR EQUAL. OWNER TO SELECT HARDWARE/PULL STYLE AND FINISH.
- REMOVE AND REINSTALL MODIFIED EXISTING WOOD HANDRAIL AND BALUSTRADE
- REMOVE AND REINSTALL EXISTING WROUGHT-IRON HANDRAILS

- LINE OF SLOPED CEILING ABOVE. REFER TO REFLECTED CEILING PLAN AND SECTION DRAWINGS.
- RECESSED CAN LIGHT ABOVE. REFER TO REFLECTED CEILING PLAN ON SHEET A1.2
- ELECTRICAL POWER OUTLET. REFER TO INTERIOR ELEVATIONS FOR QUANTITY, LOCATION AND DIMENSIONS.
- LINE OF MANTEL ABOVE. REFER TO SHEET A4.0 INTERIOR ELEVATIONS FOR DETAILS.

NOTES:

- ALL DIMENSIONS ARE TO FACE OF STUD (F.O.S.) UNLESS NOTED OTHERWISE
- REFER TO SHEET A4.0 INTERIOR ELEVATIONS FOR ADDITIONAL MATERIAL AND FINISH SCOPE OF WORK.

LEGEND:

- EXISTING MASONRY WALL
- EXISTING CONSTRUCTION
- REMOVE EXISTING CONSTRUCTION
- NEW CONSTRUCTION
- INDICATES EXISTING/NEW CEILING HEIGHT, ABOVE FINISHED FLOOR (A.F.F.) OR FINISHED FLOOR LEVEL (F.F.L.)
- ELECTRICAL POWER OUTLET

MORRIS RESIDENCE - RENOVATION

63 Owen Brown Street
Hudson, Ohio 44236

Date	Progress Set
05/17/20	PROGRESS SET
05/28/20	PROGRESS SET
07/24/20	PROGRESS SET
08/04/20	AHBR SUBMITTAL
Scale	As Noted

Proposed Basement, First & Second Floor Plans

A1.1

1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10



Chloe-Wright House, 1835
63 Owen Brown Street Restoration



Existing House West Elevation (Left)

63 Owen Brown Street Restoration



Existing House South Elevation (Front)

63 Owen Brown Street Restoration



Existing House North Elevation (Back)

63 Owen Brown Street Restoration



Existing House North Elevation (Back)
63 Owen Brown Street Restoration



Existing House East Elevation (Side)
63 Owen Brown Street Restoration



Existing House East Elevation (Right) & Window

63 Owen Brown Street Restoration

Pella® Reserve™

Traditional Wood & Clad/Wood



Exquisitely designed windows and doors with unparalleled historical detailing.

Double-Hung Interior



Double-Hung Exterior



- Historical details**
 Our most historically authentic line of wood windows and patio doors. Featuring through-stile construction, deliberate proportions and intricate profiles. Pella Reserve products are the ideal choice for historical renovations and traditional building projects.
- Authentic hardware**
 Complement your project with historically authentic spoon-lock window hardware. Our Antiek casement window hardware is inspired by period furniture to deliver authentic traditional style.
- Architectural interest**
 Featuring the industry's only foam spacer solution, Pella's Integral Light Technology® grille helps capture the look of true-divided-light without sacrificing energy performance. Further your aesthetic with the putty profile, recreated with historically accurate angles – providing meaningful depth and a realistic shadow. Pella Reserve products offer the industry's deepest sash dimension.
- Virtually unlimited customization**
 If you can dream it, we can build it with our most customizable product line. From extra tall to extra wide, Pella can craft unique windows that complement your aesthetic. Custom sizes, grille patterns and designs, finishes, wood types and glass options are available.
- Tailor-made solutions**
 From preliminary drawings to installation, Pella's expert team of architects, engineers, drafters and consultants can work to deliver custom window and door solutions for your project. Partner with Pella to achieve your unique vision without concessions.
- Intentional innovation**
 Winner of the 2019 Most Innovative Window from Window and Door Magazine, the Integrated Rolscreen® retractable screen preserves aesthetic view. It is a double- and single-hung screen that appears when you open the window, and rolls away, out of sight, when you close it.
- Durable interiors and extruded aluminum exteriors**
 Create a custom exterior color to meet your design needs or choose from 27 standard color options. Interior finish options are available in four paints, eleven stains and primed and ready-to-paint.
- ENERGY STAR® certified¹**
 Pella wood products offer energy-efficient options that will meet or exceed ENERGY STAR guidelines in all 50 states. Pella Reserve products with triple-pane glass have been awarded the ENERGY STAR Most Efficient Mark in 2020.¹
- Testing beyond requirements**
 At Pella, our products are tested beyond requirements to help ensure they have long-lasting performance and reduce call-backs for you.
- Best limited lifetime warranty²**
 Pella Reserve products are covered by the best limited lifetime warranty in the business for wood windows and patio doors.²

Available in these window and patio door styles:



Special shape windows also available.

^{1,2} See back cover for disclosures.

Product Specifications

Window & Patio Door Styles	Min. Width	Min. Height	Max. Width	Max. Height	Performance Class & Grade	Performance Values			Frame / Install
						U-Factor	SHGC	STC	
Awning	13-3/4"	13-3/4"	53"	29"	LC40-CW50	0.25-0.29	0.18-0.47	27-33	Fold-out Fin, Block Frame, EnduraClad Exterior Trim / Brickmould
Precision Fit Awning	17"	17"	53"	29"	R50-CW50	0.28-0.32	0.18-0.47	27-33	Pocket Replacement
Casement	13-3/4"	13-3/4"	41"	96"	R35-CW50	0.25-0.29	0.18-0.47	27-35	Fold-out Fin, Block Frame, EnduraClad Exterior Trim / Brickmould
Precision Fit Casement	17"	17"	35"	73"	R45-CW50	0.28-0.33	0.18-0.47	27-30	Pocket Replacement
Fixed Casement	10"	10"	144"	144"	R35-CW50	0.25-0.29	0.18-0.47	27-35	Fold-out Fin, Block Frame, EnduraClad Exterior Trim / Brickmould
Precision Fit Fixed Casement	17"	17"	59"	73"	R45-CW50	0.28-0.33	0.18-0.47	27-30	Pocket Replacement
Double-Hung	14"	24-3/8"	48"	96"	CW40-CW50	0.25-0.30	0.19-0.53	26-34	Fold-out Fin, Block Frame, EnduraClad Exterior Trim / Brickmould
Precision Fit Double-Hung	13-1/2"	23-3/4"	48"	84"	CW40-CW50	0.25-0.31	0.19-0.53	26-30	Pocket Replacement
Monumental Hung	13-3/4"	24"	72"	144"	LC25-CW50	0.25-0.30	0.17-0.47	29-34	Fold-out Fin, Block Frame, EnduraClad Exterior Trim / Brickmould
In-Swing Hinged Patio Door (Single)	18"	36"	48"	199-1/2"	LC40-LC55	0.25-0.29	0.14-0.40	31-32	
In-Swing Hinged Patio Door (Double)	36"	36"	96"	119-1/2"	LC40-LC55	0.25-0.29	0.14-0.40	31-32	
Out-Swing Hinged Patio Door (Single)	18"	36"	48"	119-1/2"	R50-LC70	0.25-0.30	0.14-0.39	30-32	
Out-Swing Hinged Patio Door (Double)	36"	36"	96"	119-1/2"	R50-LC70	0.25-0.30	0.14-0.39	30-32	
Sliding Patio Door (O)	30-3/4"	74"	60-3/4"	119-1/2"	LC25-LC70	0.29-0.32	0.15-0.42	-	
Sliding Patio Door (OX, XO)	59-1/4"	74"	119-1/2"	119-1/2"	LC25-LC70	0.29-0.32	0.15-0.42	29-35	
Sliding Patio Door (OXO)	90"	74"	180"	119-1/2"	LC25-LC70	0.29-0.32	0.15-0.42	-	
Sliding Patio Door (OXXO)	116-1/8"	74"	236-1/8"	119-1/2"	LC25-LC70	0.29-0.32	0.15-0.42	-	
Multi-Slide Patio Door	40-1/4"	50-1/2"	701-5/8"	119-1/2"	R15-LC25 ³	0.30 - 0.36	0.15 - 0.46	-	
Bifold Patio Door	31-3/4"	55-1/2"	312"	119-1/2"	R15-R25 ³	0.26-0.44	0.13-0.45	-	For more info visit PellaADM.com


Window sizes available in 1/8" increments

Special sizes available. For more information regarding performance, visit installpella.com/performance. For more information regarding frame and installation types, visit PellaADM.com.


Grilles

Integral Light Technology®


Choose the look of true divided light featuring the industry's only foam spacer.



Putty Glaze Exterior with Ogee Interior⁴
5/8", 7/8", 1-1/4" or 2"



Putty Glaze Exterior with Ogee Interior⁴
5/8", 7/8", 1-1/4" or 2"




Ogee Exterior with Ogee Interior⁴
5/8", 7/8", 1-1/4" or 2"

Cross Sections

Cross Sections

The double-hung cross sections provide visual reference to the historic putty exterior profile and traditional, beveled Ogee interior that add architectural interest to your project.



Optional Fold-out Installation Fin

^{3,4} See back cover for disclosures.

Window Hardware

Classic Collection

Get a timeless look with authentic styles in classic finishes.



Fold-away Crank
Antiek



Spoon-Style Lock

Finishes:



Champagne

White

Brown

Matte Black



Oil-Rubbed Bronze

Satin Nickel

Bright Brass

Antique Brass

Rustic Collection

Create a distinct and charming look with distressed finishes.



Fold-away Crank
Antiek



Spoon-Style Lock

Finishes:



Distressed Bronze

Distressed Nickel

Essential Collection

Select from popular designs and finishes to suit every style.



Fold-away Crank



Cam-Action Lock

Finishes:



Champagne

White

Brown

Matte Black



Oil-Rubbed Bronze

Satin Nickel

Bright Brass

Patio Door Hardware

Classic Collection

Choose timeless pieces, created in collaboration with Baldwin® Hardware, for a look that will never go out of style.

BALDWIN



Hinged & Bifold Patio Door Handle
Locus | Virago



Sliding & Multi-Slide Patio Door Handle
Ambrose



Multi-Slide Patio Door Handle^{5,6}

Finishes:



Matte Black

Oil-Rubbed Bronze

Satin Nickel

Bright Brass



Antique Brass

Essential Collection

Elevate your style and transform a home with elegant selections.



Hinged & Bifold Patio Door Handle



Sliding Patio Door Handle



Multi-Slide Patio Door Handle^{5,6}

Finishes:



Champagne

White

Brown

Matte Black



Oil-Rubbed Bronze

Satin Nickel

Bright Brass

^{5,6} See back cover for disclosures.

Pinnacle® Pristine

High Performance Architectural Shingles



PROTECTS




Lifetime
LIMITED WARRANTY


130 mph
WIND RESISTANCE



ATLAS
Signature Select®
ROOFING SYSTEM

Pinnacle® Pristine Shingles Brochure

First Impressions Are Everything.

Don't let the black streaks caused by algae ruin it.



**APPROVED
PRODUCTS**

"I've been a contractor for over 35 years and I've seen it all. And I know the right products for the right job," says Mike Holmes. "I only partner with brands that share my core values — quality, integrity and trust. 3M has all of those in spades."

Mike Holmes
- Mike Holmes

To learn more about HOLMES Approved Products, please visit: makeitright.scotchgard.com

A Brand You Know And Trust Scotchgard™ Protector

25+ years of proven performance.

Copper Fights Black Streaks

Atlas shingles featuring Scotchgard™ Protector have:

- Copper-containing granules with a proprietary 3M porous ceramic coating that allow copper ions to release slowly over time.
- A minimum 10% blend of evenly distributed 3M™ Copper Granules among standard colored granules.
- Third-party verification of the 3M copper granule application.
- An Atlas Lifetime* Algae Resistance Limited Warranty against black streaks caused by algae.

Keep your roof looking beautiful and protect the long-term investment in your home by installing Atlas shingles featuring Scotchgard™ Protector.

10% or more 3M copper-containing granules = protection against the black streaks caused by algae.





Illustration of a 3M copper roofing granule.



Dreaming Of A Home Redesign?

Get creative with the Roof Inspiration Center, a suite of home design tools from Atlas.

From shingles to siding, reinvent the look of your home with the Roof & Home Design Studio. Like all your ideas in one spot? With RoofSwap! you can upload home photos, swipe for different looks and save your ideas to a mood board. Explore shingle styles, features and colors with the Visual Product Selector.

Whether you have 3 minutes or 30, your new look is just around the corner.

AtlasRoofing.com/Roof-Inspiration

Pristine Appearance. Pristine Appeal.

Pinnacle® Pristine *High Performance Architectural Shingles*



Pinnacle® Pristine High Performance Architectural Shingles provide a wide array of color choices to complement any exterior color palette. Advanced technology implemented by Atlas protects the shingles against high winds while Scotchgard™ Protector helps prevent ugly black streaks caused by algae. With Pinnacle® Pristine shingles, roofs maintain their look and performance for years.



Classic



Special Order Limited regional availability. Please contact your local supplier.





Lifetime

LIMITED WARRANTY

Warranty

Be confident in your purchase with a long-lasting Lifetime Limited Warranty**.



Protection

Beauty meets protection with the help of the Atlas 130 mph Wind Limited Warranty**.



Curb Appeal

Maintain your home's appearance with a roof that looks beautiful for years by resisting the black streaks caused by algae.



Pinnacle® Pristine Natural Expressions

Designer colors, inspired by our natural world, preserved with Scotchgard™ Protector from 3M.

The colors of nature will be an integral part of your home when you choose the Pinnacle® Pristine Natural Expressions color palette from Atlas Roofing. Make a statement with the bold, impactful, long-lasting colors of Pinnacle® Pristine Natural Expressions with Scotchgard™ Protector from 3M.



Coastal Granite

Imagine standing on the windswept coast of Maine. Feel a little thrill to see how the color of the rocks almost matches the pounding seas? If so, then **Coastal Granite**, a deep gray that's anything but neutral, may be your shingle of choice.




Copper Canyon

Are you drawn to wide-open spaces and big, dramatic vistas? Then **Copper Canyon** shingles may be for you. Looking like they came directly from the rugged landscapes of the Old West, these shingles can't help but inspire your sense of adventure.



Majestic Shake

You know how historic trees have a certain dignity about them? Some homes do too. When your aesthetic is formal and traditional, you want a shingle to match. **Majestic Shake** delivers with a look that's serious without being severe.



Morning Harvest

Golden sunlight and a market basket overflowing with the bounty of the garden – if anything inspires warmth and contentment, this is it. **Morning Harvest's** golden tones offer a simple message: welcome.



Summer Storm

The world just seems fresher after a good rain. The air smells clean and rain-washed cobblestone streets shimmer like jewels. **Summer Storm** shingles capture that mood of renewed optimism, all with not a cloud on the horizon.



To provide homeowners the most accurate representation of color options, several photo scans and house shots were utilized in various lighting conditions. Variations in lighting illustrate the color gradients on asphalt shingle roofs.

Color blends vary from shingle to shingle. Before installation, consult with your contractor and request to view the actual shingles being installed on your roof to ensure confidence in your final color selection.

Pinnacle® Pristine

High Performance Architectural Shingles



With Atlas you get more than a roof. You get beautiful, lasting protection, backed by the industry's best warranty** coverage — and the peace of mind that comes with it.

Colors	Limited Warranty**	Algae Resistance*	Signature Select® Eligible ¹
19 Colors	Lifetime	Scotchgard™ Protector	Yes

Increase your Premium Protection Period by installing an Atlas Signature Select® Roofing System.

10
YEARS

Increases To

15
YEARS



Roof System Components:

- 1 Atlas WeatherMaster® Ice & Water Underlayment
- 2 Atlas Premium Underlayment
- 3 Atlas Pro-Cut® Starter Shingles
- 4 Atlas Roof Shingles
- 5 Atlas Pro-Cut® Hip & Ridge Shingles

Demand Peak Coverage

When you install an Atlas Signature Select® Roofing System¹, all of the components are designed and backed by an Atlas warranty. In the unlikely event that you have a problem with your roof, you have a single company to turn to for support.

Unlike many other roofing warranties that promise more than they deliver, Atlas packs value and assurance into an enhanced Premium Protection Period with the installation of an Atlas Signature Select® Roofing System.

The Premium Protection Period includes:

- Non-prorated labor and materials
- Tear off and disposal fees
- Coverage of the full Atlas product system
- Transferability



Pinnacle® Pristine Pearl shingles are Energy Star® certified. Both durable and beautiful, they reflect more of the sun's rays – which keeps the roof cooler, helps it last longer and lowers air conditioning costs.

* In order to qualify for the Atlas Lifetime Algae Resistance Limited Warranty against black streaks caused by blue-green algae, installation must include Atlas Pro-Cut® Hip & Ridge shingles featuring Scotchgard™ Protector or Atlas Pro-Cut® High Profile Hip & Ridge shingles featuring Scotchgard™ Protector with Atlas shingles featuring Scotchgard™ Protector.

** Refer to the Atlas Roofing Limited Shingle Warranty for all coverage requirements.

¹ Refer to the Atlas Signature Select® Limited Warranty for all system coverage requirements.

Scotchgard and the Scotchgard Protector logo, including the plaid design and 3M logo, are all trademarks of 3M.

© Copyright 2018, Atlas Roofing Corporation ATL-184529-00 9/18



#AtlasProtects

AtlasRoofing.com

Colors

Wood Types

Choose the wood species that best complements your project's interior.



Prefinished Pine Interior Colors

Custom interior finishes, unfinished or primed and ready-to-paint are also available.



Extruded Aluminum-Clad Exterior Colors

Our low-maintenance EnduraClad® exterior finish resists fading. Take durability one step further with EnduraClad Plus which also resists chalking and corrosion.⁷



Custom colors are also available.

Added Peace of Mind

Integrated Security Sensors

Integrated wireless security sensors maintain aesthetics, streamline security installation and ensure no warranty loss is caused by post-installation drilling. Sensors can be monitored via the free Pella® Insynctive® App and are compatible with major security panel systems.⁸ For more information, go to connectpella.com.




The confidence of Pella's warranty.

Pella® Reserve™ products are covered by the best limited lifetime warranty for wood windows and patio doors.²

¹ Some Pella products may not meet ENERGY STAR® guidelines in Canada. For more information, contact your local Pella sales representative or go to energystar.gc.ca.
² Based on comparing written limited warranties of leading national wood window and wood patio door brands. See written limited warranty for details, including exceptions and limitations, at installpella.com/warranties or contact Pella Customer Service.
³ Ratings are contingent on product configurations.
⁴ Color-matched to your product's interior and exterior color.
⁵ Flush multi-slide handle is a Pella exclusive design.
⁶ Flush multi-slide handle is not available in Antique Brass, Champagne or Polished Nickel.
⁷ EnduraClad Plus protective finish is not available with all colors. See your local Pella sales representative for availability.
⁸ Requires the Insynctive App on a smart device, an Insynctive Bridge and a wireless home router with internet connection.

OHIO HISTORIC INVENTORY

1. No.		4. Present Name(s) Residence, K. Coulton	
2. County Summit		5. Other Name(s) Chloe Wright House; Grisson farmhouse	
3. Location of Negatives N.A. 66-1		18. Thematic Category C	
6. Specific Location 63 Owen Brown Street		17. Dates or Period 1835	
7. City or Town - If Rural, Township & Vicinity Hudson		19. Style or Design Greek Revival	
8. Site Plan with North Arrow 		20. Contractor or Builder	
9. Coordinates Lat. _____ Long. _____ U.T.M. Reference 17 416284 434566		21. Original Use, if apparent residence	
10. Zone Easting Northing Site <input type="checkbox"/> Structure <input type="checkbox"/> Building <input checked="" type="checkbox"/> Object <input type="checkbox"/>		22. Present Use residence	
11. Final Register? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		23. Ownership Public <input type="checkbox"/> Private <input checked="" type="checkbox"/>	
12. Is R Eligible? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>		24. Owner's Name & Address, if known K. Coulton 63 Owen Brown Street Hudson 44736	
13. Part of Estab. Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Hist. Dist.? No <input type="checkbox"/>		25. Open to Public? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	
14. District Yes <input type="checkbox"/> No <input type="checkbox"/> Potent? No <input type="checkbox"/>		26. Local Contact Person or Organization Hudson Heritage Association	
15. Name of Established District Hudson Local Historic District		27. Other Surveys in Which Included	
42. Further Description of Important Features Addition to original house moved, to rear and west.		28. No. of Stories 2	
		29. Basement? partial Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	
		30. Foundation Material poured concrete/block	
		31. Wall Construction wood frame	
		32. Roof Type & Material gable - asph shingle	
		33. No. of Bays Front 5 Side 3	
		34. Wall Treatment beveled siding	
		35. Plan Shape rect	
		36. Changes (Explain in #42) Addition <input checked="" type="checkbox"/> Altered <input type="checkbox"/> Moved <input checked="" type="checkbox"/>	
		37. Condition interior good Exterior good	
		38. Preservation Underway? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	
		39. Endangered? By What? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	
		40. Visible from Public Road? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	
		41. Distance from and Frontage on Road 50' 60'	
43. History and Significance First record in tax lists 1839, for Thomas Wright, frame house, \$150.00. Moved from 2494 Aurora Road in 1983. House moved 200' yards northwest of original site in 1909 by Daniel Henderson to make room for house now on site; original barn remains with Henderson House. Barn at new location built 1912 for prize herd of Ayshire cattle; barn now destroyed. Pictured in 1874 Summit County Atlas. Owned in 1850 by William Dawes, abolitionist		Photo	
44. Description of Environment and Outbuildings At end of residential section of Owen Brown Street, to east of Brandywine Creek, which divides residential area from commercial. Moderate traffic		45. Prepared by L. Newkirk, F. Barlow	
46. Sources of Information Summit County Tax Assessment records IHA Architectural Survey & Research Comm. files Hudson Library & Historical Society Personal inspection		47. Organization IHA	
		48. Date	
		49. Revision Date(s)	