


OHIO HISTORIC INVENTORY

Ohio Historic Preservation Office
Ohio Historical Center
Columbus, Ohio 43211

1. No.		4. Present Name(s) Residence, Brian Strachan		1. No.	
2. County Summit		5. Other Name(s) Brown-Strong House			2. County Summit
3. Location of Negatives HHA 37-37					
6. Specific Location 258 North Main Street		16. Thematic Category C	28. No. of Stories 2	5. Other Name(s) Brown-Strong House	
7. City or Town If Rural, Township & Vicinity Hudson		17. Date(s) or Period 1834	29. Basement? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>		
8. Site Plan with North Arrow 		18. Style or Design Greek Revival	30. Foundation Material tooled sandstone		
9. Coordinates Lat. _____ Long. _____ U.T.M. Reference 17 463046 4565732		19. Architect or Engineer	31. Wall Construction wood frame		
10. Site <input type="checkbox"/> Structure <input type="checkbox"/> Building <input checked="" type="checkbox"/> Object <input type="checkbox"/>		20. Contractor or Builder	32. Roof Type & Material gable - asphalt shingle		
11. National Register? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>		21. Original Use, if apparent residence	33. No. of Bays Front 3 Side 2		
12. Is It Eligible? Yes <input type="checkbox"/> No <input type="checkbox"/>		22. Present Use residence	34. Wall Treatment clapboard		
13. Part of Estab. Hist. Dist.? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>		23. Ownership Public <input type="checkbox"/> Private <input checked="" type="checkbox"/>	35. Plan Shape rect		
14. District Potent'l? Yes <input type="checkbox"/> No <input type="checkbox"/>		24. Owner's Name & Address, if known Brian Strachan 258 North Main St. Hudson 44236	36. Changes (Explain in #42) Addition <input checked="" type="checkbox"/> Altered <input checked="" type="checkbox"/> Moved <input type="checkbox"/>		
15. Name of Established District Hudson Historic District		25. Open to Public? Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	37. Condition Interior good Exterior good		
42. Further Description of Important Features Low gable roof with returns, modillions; lunette in front gable; symmetrical facade; full entablature with pilasters; 2/2 double hung windows; southeast corner porch added; two rear additions, the first in the 1880's, the second in the 1940's. Basement windows in the first addition are very old. Entry door is replacement, with the original surrounds; c. 1880 windows set in original frames; beaded corner boards and water table; center and corner posts visible in living room and dining room (over)		26. Local Contact Person or Organization Hudson Heritage Association	38. Preservation Underway? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>		
43. History and Significance Erected by Owen Brown in 1834 for his son, Oliver H. Brown, a tanner, who later purchased John Brown's tannery on Hines Hill Road; sold in 1836 to Ephraim Strong.		27. Other Surveys in Which Included	39. Endangered? By What? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> *see below		
44. Description of Environment and Outbuildings 1913 garage. A barn from 95 South Main Street, slated to be razed by the Village, was disassembled and moved here, will later serve as garage. Residential area, close to downtown commercial area; heavy traffic.		40. Visible from Public Road? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>	41. Distance from and Frontage on Road 20' 71'		
45. Sources of Information Summit County Tax Assessment records Archives, Hudson Heritage Association Personal inspection		46. Prepared by L Newkirk, F. Barlow	47. Organization HHA		
		48. Date	49. Revision Date(s) 5/88		


258 NORTH MAIN STREET


 Brown-Strong House
1834

Greek Revival, with delicate Federal moldings and a noted Asher Benjamin door surround, built in 1834 by Owen Brown for his son, Oliver. Like his father and his brother, John, Oliver was a tanner. In 1836, the house was sold to Brown's fellow Abolitionist, Ephraim Strong. At one time Ephraim's son, Nathan, carried on his father's business here, and his daughter, Mary, conducted the Hudson Female Seminary on the property. The foundation is tooled sandstone, with some rough sandstone in the rear; the southeast corner porch is an addition.



201





A
sp1 SCALE:
1" = 20'-0"


SITE PLAN

Existing




Proposed





2ND LEVEL - OPT B



MAIN LEVEL - OPT B






[VIEW 3D MODEL](#)

Roof	Area	Total	Length
Roof facets	2295 ft ²	14	-
Ridges / Hips	-	9	75' 6"
Valleys	-	1	2' 4"
Rakes	-	11	143' 10"
Eaves	-	15	172' 7"
Flashing	-	10	34' 8"
Step Flashing	-	19	82' 6"
Drip Edge/Perimeter	-	-	316' 5"

Roof Pitch	Area	Percentage
6/12	2110 ft ²	91.91%
3/12	182 ft ²	7.94%
1/12	3 ft ²	0.15%



Waste Factor Calculation

	Zero Waste	+5%	+10%	+15%	+20%
Area	2295 ft ²	2410 ft ²	2525 ft ²	2639 ft ²	2754 ft ²
Squares	23	24 ¹ / ₃	25 ¹ / ₃	26 ² / ₃	27 ² / ₃

The table above provides the total roof area of a given property using waste percentages as noted. Please consider that area values and specific waste factors can be influenced by the size and complexity of the property, captured image quality, specific roofing techniques, and your own level of expertise. Additional square footage for Hip, Ridge, and Starter shingles are not included in this waste factor and will require additional materials.

