

## City of Hudson Ohio

### **Department of Community Development**

115 Executive Parkway, Suite 400, Hudson, OH 44236

Phone: (330) 342-1790

www.hudson.oh.us

## **Zoning Certificate**

PROJECT AI	DDRESS: 1940 GEORGETO		
Parcel Number:	3009980		Zoning District: 8
Subdivision:	n/a		Lot #: n/a
Applicant:	Highfields	Owner:	KGK PROPERTIES LLC
	1936 Georgetown Road		1975 E NORTON RD
	Hudson, OH 44236		HUDSON, OH 44236
Permit Number:	2017-004		Issue Date: 1/5/17
Project: New	Principal non-residential structure		Picked up Date:
Permit Descript	ion: Event center		1-6-2017
Square footage	: 5070		
FEMA Floodpla	in: N		

CONDITIONS - PC approval on June 8, 2015 per case 2015-14

Building Permit must be obtained from the Summit County Department of Building Standards prior to commencing work. Certificate shall expire unless construction is commenced within six months and completed within two years of the date of issuance, Not valid without Staff signature.

Mul Rehaden	1/5/17
Authorized City Staff	Date

# HUDSON

COMMUNITY DEVELOPMENT • 115 Executive Parkway, Suite 400 • Hudson, Ohio 44236 • (330) 342-1790

## APPLICATION FOR ZONING CERTIFICATE

Project Address: 1940 GEORGETOWN ET	> HUD	501	) OH 44236	· · · · · · · · · · · · · · · · · · ·		_
Project Description: [check all that apply and describe below]				G'		
New Construction[residential]FenceAccessory	Structure	Alte	rationDemolition	_sign	•	
New Construction[other]AdditionUse (Change Detailed Explanation: EUEN T CENTER	ge of)Re	-inspe	ction Other			
Project Area (sf): 5070 Subdivision:			Sublot: 7 Zoni	ng Dis	it: <u>3C</u>	2_
Project Cost: 12 MILLION Commence M&Y: MARC	H 2017	7	Complete M&Y:MAR	<u>CH</u>	2018	<u>3</u>
Please note: Applications will not be accepted as complete fulfill all requirements listed within the AHBR submittal p payable to the "City of Hudson".	by the City acket. All a	of Hu applic	ndson until the applicant an ation fees are accepted in	d prop cash o	perty ov or by cl	vner heck
Affidavit of Applicant and Property Owner  The undersigned do hereby certify that the information to the and consents to employees and/or agents of the City of Huds inspection and verification of information pertaining to conformance to requirements and conditions of such approve the subject property from deed restrictions, easements, or regarding structures and uses on the property.	son entering the applicati al. I acknov r homeowne	upon ion, a wledge er asse	the premises of this application is that City reviews or appropriation covenants, restrict	approv approv avals (	or purp ved, to do not a	oses of verify absolve
Applicant: HIGHFIELDS	Property	v Owi	ner: HIGH FIELDS			
Address: 1936 GEORGE TOWN RE	Address	. 19	36 GEORGETOWN	1 12	$\overline{D}$	
1756 00066 (1100 100 110 110 110 110 110 110 110 1			DD50N_OH 44Z			
HUDSON OH 44236 Telephone: 330-650-4337 Fax: 330-650-4330	> Telepho	ne.3	30-650-4337 Fax	: 334	0-650	<u> 15-433</u>
Brail: JOYCE . KURYLA @ GMAIL, COM	Email:	$\sqrt{2}$	E. KURYLA@GMA	A16 ,	CON	7
Applicant relationship to Owner:AgentAttorney _	Contract	OI.	Architect Other			
Lund & // Date: 12/28/14	· Fra	1	S/M_DE	ate: <u> </u>	2/28	16
Applicant Signature	Propert	ty Ow	ner Signature			
					<u>-</u> 1	
Staff Use Only Application No. 2017-004 Landscape Req	į. Y	N	GMA#/		-	
Date Received  2/29   0 GMA Letter	Y	N	Tree Plan App.	Y	N	
Fee Paid ROW Form	Y	N	Site Plan App.	Y	N	
Receipt RITA Form	Y	N	Staked/Pinned	Y	N	
No. FEMA Floodpl	lain Y	N	<u>Initials</u>			

#### KGK – Highfields Event Center


PC approval (Conditional Use and Site Plan) – 2015-14 – approved June 8, 2015 Zoning certificate 2017-004 – issued January 5, 2017

#### 1203.05 - Conditional Use

- (c)Lapse.
- (1) Failure of an applicant to commence substantial construction or action with regard to the conditional use approval within one (1) year of receiving approval of the conditional use and to complete such construction or action within two (2) years of receiving approval of the conditional use shall automatically render the decision of the PC, or the BZBA on appeal, null and void.

#### 1203.02

(4) Time Limit on Zoning Certificates. Unless construction is commenced within six (6) months of the date of issuance of a zoning certificate and completed within twenty four (24) months of the date of issuance, such certificate shall then automatically lapse and be null and void. These time limits may be extended by the City upon a showing that there has been continuing construction activity on the site during the twenty four (24) months of the date of issuance. Construction or improvement of a new or existing structure shall be deemed to have commenced upon completion of the in-ground permanent foundation, or if constructed utilizing slabs, piers, pilings, or pole construction, completion of the structural framework of the building constituting the authorized work under the permit.



GENERAL NOTES

6340

EXTERIOR FINISH SCHEDULE

MATERIAL STANDING SEAM METAL ROOF

MANUFACTURER TO BE SELECTED BY

COLOR "CLAY" - VERIFY WITH OWNER

David L. Sommers, Lic.#6340 Expiration Date 12/31/2017 © COPYRIGHT 2016

DS ARCHITECTURE

ALL RIGHTS RESERVED


A301


1.5.17


PROJECT: 15070 DATE: 11/14/2016


DRAWN: JV

CHECKED: LK










ADDITIONS AND ALTERATIONS TO:
HIGHFIEL DS EVENT CENTER
FOR.
KEN AND JOYCE KURYLA
1340 GEDRGETOWN ROAD
HUDSON, OH 44236



PROJECT: 16070 DATE: 11/14/2016 DRAWN: JV CHECKED: LX

A302




DAVID L. SOMMERS 6340 David L. Sommers, Lic.#6340 Expiration Date 12/31/2017 © COPYRIGHT 2016 DS ARCHITECTURE ALL RIGHTS RESERVED


HIGHFIELDS EVENT CENTER
FOR:
KEN AND JOYCE KURYLA
1940 GEORGETOWN ROAD



PROJECT: 16070 DATE: 11/14/2016 DRAWN: JV

A303








© COPYRIGHT 2016 DAVID SOMMERS & ASSOCIATES, LLC ALL RIGHTS RESERVED


0 S S AND ASSOCIATES, SIGNERS AND SURVEYORS SOON, ONE 4439 4439 440-248-1339, P. HEJDUK --- COX

PROJECT: 12283

11/14/2016 <u>drawn</u>: Jlk CHECKED: JLK

> C101 UTILITY PLAN





STORM SEWER PROFILE



20# 17 5014 APPROVED VAST-51

Mark Religion 1997

C102

PROJECT: 12283

DRAWN: JEK

DATE: 11/14/2018

JASON L KEKIG E-61676 a


> DAVID SOMMERS & ASSOCIATES, LLC ALL RIGHTS RESERVED

HEJDUK-COX AND ASSOCIATES, INC.

HIGHFIELDS EVENT CENTER
FOR:


The de sent has find a sent has

4



SOIL TYPE LEGEND

HYDROL. SOIL DEPTH TO SEASONAL RANGE OF GEORGE BEDROCK WATER TABLE SLOPE PERMEABILITY EIB ELLSWORTH SILT LOAM C > 6' 1.5' TO 2.5' 0 - 2% SLOW MAHONING SILT LOAM Ид₿ > 5' 1.0' TO 2.5' 2 - 6% SLOW b



INSTALL AT PERMANENT SPILLWAY LOCATION; NOTE

DIFFERENT ELEVATIONS

BASIN/ TRAP	LATERAL WIDTH OF ROCK WEIR	BOTTON ELEV. 'A'	DEPTH	SPILLWAY ELEV. 'B'	неснт "н"	TOP WEIR	TOP BANK
<b>#</b> 1	Б,	1104,17	2,83	1107.00	1.40'	1108.40	1109.90

### TEMPORARY SEDIMENT TRAP DETAIL

#### SEDIMENT & EROSION CONTROL NOTES:

MINIMIZE TRACKING OF SEDIMENT BY VEHICLES BY UTILIZING THE CONSTRUCTION ENTRANCE AS THE ONLY ENTRANCE FOR VEHICLES, MAINTAIN THIS ENTRANCE WITH STORE AS NEEDED TO PREVENT DIRT AND MUD FROM TRACKING ONTO THE ROMOWAY. REQUIALS SWEEPING MAY BE NECESSARY TO ENSURE ROADWAY DOES NOT BUILD UP WITH SEDIMENT.

THE CWINER OF RECORD MUST PROMDE REQULAR INSPECTION AND MAINTENANCE FOR ALL EROSION AND SEDIMENT CONTROL PRACTICES. PERMANENT RECORDS OF ALL MAINTENANCE AND INSPECTIONS MUST BE KEPT THROUGHOUT THE CONSTRUCTION PERIOD. INSPECTIONS MUST BE MADE A MINIMUM OF ONCE EVERY SEVEN (?) DAYS AND IMMEDIATELY AFTER STORM EVENTS GREATER THAN 0.5 INCHES OF RAIN WITHIN A 24-HOUR PERIOD. THE NAME OF OWNER'S DESIGNATED INSPECTION, MAJOR OSSERVATIONS, DATE OF INSPECTIONS AND CORRECTIVE MEASURES TAKEN MUST BE NOTED ON ALL INSPECTIONS.

OTHER EROSION AND SEDIMENT CONTROL ITEMS MAY BE NECESSARY DUE TO ENVIRONMENTAL CONDITIONS AND MAY BE REQUIRED AT THE DISCRETION OF THE SUMMIT SOIL AND WATER CONSERVATION DISTRICT OR ITS REPRESENTATIVES.

SEDIMENT/STORMWATER PONDS AND EROSION AND SEDIMENT CONTROLS SHALL BE IMPLEMENTED AS THE FIRST STEP IN GRADING AND WITHIN 7 DAYS FROM THE START OF CRUBBING. UPON COMPLETION OF CONSTRUCTION OF FONDS, SEEDING AND MULCHING OF ENTIRE CONSTRUCTED POND AREA SHALL IMMEDIATELY FOLLOW TO AD IN THE STABILIZATION AND MINIMIZE EROSION AND SEDIMENT TRANSPORT OF THE SOIL BEFORE WATER LEAVES THE POND, ALL FROSION AND SEDIMENT TOWNSTORMS SHALL CONTINUE TO FUNCTION UNTIL DISTURBED AREAS ARE FULLY RESTABILIZED.

NO SOUD OR LIQUID WASTE SHALL BE DISCHARGED INTO STORM WATER RUNOFF, INCLUDING WASHING OUT OF CEMENT TRUCKS. DESIGNATED WASH PIT AREAS ARE SHOWN ON THE PLANS AND ARE PRESET FOR THIS PURPOSE AWAY FROM AREAS OF STORM WATER RUNOFF.

IF AN INSPECTION REVEALS A CONTROL PRACTICE NEEDS REPAIR OR MAINTENANCE, EXCEPTING SEDMENT PONDS, IT MUST BE CORRECTED WITHIN THREE DAYS OF THE INSPECTION. SEDIMENT PONDS MUST BE REPAIRED WITHIN 10 DAYS OF INSPECTION.

IF AN INSPECTION REVEALS A CONTROL PRACTICE IS FAILING TO PERFORM ITS INTENDED FUNCTION, THE SWP3 MUST BE AMERICED TO SHOW A MORE APPROPRATE CONTROL PRACTICE, WHICH MUST BE INSTALLED WITHIN 10 DAYS OF INSPECTION.

IF AN INSPECTION REVEALS A CONTROL PRACTICE HAS NOT BEEN INSTALLED IN ACCORDANCE WITH THE SCHEDULE OF IMPLEMENTATION, THE CONTROL PRACTICE MUST BE IMPLEMENTED WITHIN 10 DAYS OF INSPECTION.

SITE STABILIZATION EITHER PERMANENT OR TEMPORARY MUST FOLLOW THE REQUIREMENTS

area requiring permanent stabilization	TIME FRAME TO APPLY EROSION CONTROLS
ANY AREA THAT WILL LIE DORMANT	WITHIN 7 DAYS OF THE MOST
FOR ONE YEAR OR MORE	RECENT DISTURBANCE
ANY AREA WITHIN 50 FEET OF A	WITHIN 2 DAYS OF REACHING
WATERCOURSE AND AT FINAL GRADE	FINAL GRADE
ANY AREA AT FINAL GRADE	WITHIN 7 DAYS OF REACHING FINAL GRADE WITHIN THAT AREA

area requiring temporary stabilization	TIME FRAME TO APPLY EROSION CONTROLS
ANY DISTURBED AREA WITHIN 50 FEET OF A WATERCOURSE AND NOT AT FINAL GRADE	WITHIN 2 DAYS OF THE MOST RECENT DISTURBANCE, IF THAT AREA WILL REMAIN IDLE FOR MORE THAN 14 DAYS
FOR ALL CONSTRUCTION ACTIVITIES, ANY DISTURBED AREA, INCLUDING SOIL STOCKPIESE. THAT WELL BE DORMANT FOR WORE THAN 14 DAYS BUT LESS THAN ONE YEAR, AND NOT WITHIN 50 FEET OF A WATERCOLURSE.	WITHIN 7 DAYS OF THE MOST RECENT DISTURBANCE WITHIN THE AREA
DISTURBED AREAS THAT WILL BE IDLE	PRIOR TO NOVEMBER 1st

NOTE: WHERE VEGETATIVE STABILIZATION TECHNIQUES MAY CAUSE STRUCTURAL INSTABILITY OR ARE OTHERWISE UNOBTAINABLE, ALTERNATIVE STABILIZATION TECHNIQUES MUST BE EMPLOYED, THESE TECHNIQUES MAY INCLIDE MULCHING, EROSION MATTING OR PLACEMENT OF STONE.

© COPYRIGHT 2016 ALL RIGHTS RESERVED

> CENTER KURYLA EVENT

JOYCE HIGHFIELDS FOR: KEN AND JOY

0 S S AND ASSOCIATES, SERVING AND SURFICES AND SUR HEJDUK-COX ONSULTING

4



PROJECT: 12283 DATE: 11/14/2018 DRAWN: JLX CHECKED; JLK

C104 EROSION & SEDIMENT CONTROL NOTES

CITY OF HUE

Mark Polar

OWNER: KGK PROPERTIES, LLC 1940 GEORGETOWN ROAD HUDSON, OHIO 44236 CONTACT: KEN & JOYCE KURYLA 330-650-4337

ESTIMATED CONSTRUCTION PERIOD: DECEMBER 6, 2016 THRU OCTOBER 27, 2017

OHIO EPA NPDES PERMIT NUMBER: 3 G C 0 8 7 7 3 \* A G

RECEIVING WATER: UNNAMED TRIBUTARY OF POWERS BROOK

SIZE OF PARCEL: 19.89 AC.

PROPOSED AREA OF SOIL DISTURBANCE: 2.25 AC.

PERCENTAGE SOIL DISTURBED: 11.3%

EXISTING IMPERVIOUS SURFACE: 0.61 AC.

NEW IMPERVIOUS SURFACE: 1.06 AC.

ULTIMATE PERCENTAGE IMPERVIOUS AREA: 8.4%

#### LAND USE

THE CONSTRUCTION ACTIVITY PROPOSED FOR THIS SITE WILL BE CLEARING, GRADING, UTILITY INSTALLATION AND PAYING TO SERVE A NEW EVENT CENTER, CURRENT GROUND COVER CONSISTS OF NATURAL GRASS AND LIGHT WOODS. THE SITE HAS PREVIOUSLY BEEN PARTIALLY DEVELOPED FOR AN OFFICE BUILDING.

#### RATIONALE

RUNOFF FROM THE DEVELOPED AREA OF THIS PROJECT WILL BE CARRIED TO A DETENTION BASIN WITH A BIORETENTION CELL FOR STORM WATER ATTENIATION AND WATER QUALITY TREATMENT. THE LOCATION WAS CHOSEN BY NECESSITY FOR GRAVITY FLOW OF STORM SEWERS AND AVAILABLE DISCHARGE POINT. SELECTION OF THIS METHOD IS SUPPORTED BY HAVING LIMITED CATCHMENT AREAS AND A GENERAL HISTORY OF EFFECTIVENESS.

#### CALCULATIONS

STORM WATER MANAGEMENT: CONSTRUCTION VARIOUS STRUCTURAL PRACTICES (SEE PLAN SHEET C103) WILL BE USED. INCLUDING A TEMPORARY SEDIMENT TRAP.

Trap dematering volume required: 2.10 Ac. x 67 CY PER AC. = 141 CY DEMATERING VOLUME PROVIDED = 185 CY STORAGE ZONE REQUIRED: 2.10 Ac. x 37 CY PER AC. = 78 CY STORAGE VOLUME PROVIDED = 80 CY

#### STORM WATER MANAGEMENT: POST-CONSTRUCTION

THE DETENTION BASIN INCLUDES A BIORETENTION CELL

OEPA RUNOFF COEFF, EQ: C = 0.8581  $^3$  - 0.781  $^2$  + 0.7741 + 0.04 WQV = (C x P x A) / 12, P = 0.75 INCHES RAINFALL, A = LAND AREA

BASH CONTRIBUTING AREA X IMPERVIOUS IS 41% (i = 0.41), THUS C = 0.29 WATER QUALITY VOLUME: WGV = (0.29  $\times$  0.75  $\times$  1.084 Åz) / 12 = 0.0193 AC-FT EDV PROMDED = 0.0193 AC-FT. (842 CU. FT.)

#### DARCY EQUATION: Q = K · i · A

K=0.5 ft/day (0.25 in/hr), cell area  $\lambda=5\%$  of impervious area = 970 so. Ft. i = 1.12 (htdraulic gradient) for of mulcin = 1107.85, woy high water surface = 1108.20 max. Water depth in bioretention cell = 9°

Q = 0.50 \* 1.12 \* 970 = 543 CU. FT./DAY

DRAWDOWN TIME = WOV/Q = 842 / 543 = 1.6 DAYS (37.2 HRS)

TARGET DRAWDOWN TIME = 12 TO 48 HOURS ---> OK

REQUIRED FOREBAY VOLUME = 10% WQV = 84 CU. FT FOREBAY VOLUME PROVIDED = 276 CU. FT. —> 0K

#### SCHEDULE OF IMPLEMENTATION

	SCHEDOLE OF INFLEMENTATION	
ORDER OF OPERATION	ACTIVITY	RESPONSIBLE CONTRACTOR
1	SELECT AND MARK OFF AREAS OF TREES, SHRUBS AND VEGETATION TO BE REMOVED WITH PAINT OR RIBBON.	SURVEYOR
2	CLEARING AND GRUBBING WITHIN DESIGNATED LIMITS	CLEARING
3	INSTALL SILT FENCE & CONSTRUCT TEMPORARY DIVERSIONS	SITE
4	TOPSOIL STRIPPING & STOCKPILING	SITE
5	EXCAVATE TEMP. SEDIMENT TRAP / DETENTION BASIN	SITE
6	MASS GRADING	SITE
7	INFRASTRUCTURE:  - SANITARY SEMERS - STORM SEMERS (ADD STORM DRAIN INLET PROTECTION AS WORK PROGRESSES)	SITE
8	PLACE TOPSOL & TEMPORARY SEEDING ON ALL AREAS TRENCHED FOR UTILITIES AND ALL AREAS AT FINAL GRADE.*	SEEDING
9	FINE GRADING FOR PAVEMENT AREAS	SITE
10	LITELITY TRENCHING: ELECTRIC, TELEPHONE, CABLE & GAS	SITE/UTIL CO's
11	SUBGRADE PREPARATION AND PAVEMENT INSTALLATION	PAVER
12	PERMANENT SEEDING	SEEDING
13	INSTALL BIORETENTION SYSTEM**	SITE
14	MODEFY EXISTING OUTLET CONTROL STRUCTURE (SEE C-108)	SITE
15	REMOVE SEDIMENT & EROSION CONTROL DEVICES ***	SITE

\* When seeding is occurring after september 15, all disturbed areas must be temporarily seeded and mulched, including areas for utilities.

\*\*\* ALL SEDMENT CONTROL MEASURES SHALL REMAIN IN PLACE UNITS. THE SITE IS STREAMED.
WESTERINE SINFACE STABLIZZION, MECTICS TERPORATY OF PETAMENT, SHALL SO
DISSURED TO BE IN PLACE AND FUNCTIONAL WIRT THE UNFORM AND OF YES

POLICINO BUILDING BUILDING \*CLEAN OUT THE TRAP WHEN SET HAS ACCUMULATED TO FILL 40% OF THE STORGE 70NF PROPOSED PARKING GEORGETOWN RD. CONTIBUTING DRAINAGE AREAS TO PROPOSED EAST DETENTION BASIN 1,084 Ac. Pazelly Brilder Brilder Brilder TEMPORARY SEDIMENT PROPOSED TRAP (TO BE CONVERTED INTO DETENTION BASIN) PARKING

MgB TEMPORARY SPILLWAY

DUSTING BUILDING #1840

CONTIBUTING DRAINAGE-AREA TO EXISTING SOUTH DETENTION BASIN 2.075 Ac.

EIB SCHEMATIC PLAN


- 70 ft. (exception; apply 30 ft. minimum on single
- Thickness The stone layer shall be at least 6 inches thick for light-duly entrances or at least 10 inches for heavy-duly use.
- 4. Width The entrance shall be at least 14 feet wide, but not less than the full width at points where Ingress or
- Geotextile A geotextile shall be laid over the entire area prior to placing stone and shall be composed of strong rot-proof polymeric fibers meeting the following

Minimum Tensile Strength	200 lb.
Minimum Puncture Strength	80 psl
Minimum Tear Strength	50 lb.
Minimum Burst Strength	320 psi
Minimum Elongation	20%
Equivalent Opening Size	EOS < 0.6 mm
F3 200-14	4 463



- Culvert A culvert shall be constructed under the entrance if needed to prevent surface water from flowing across the entrance or to prevent runoff from being directed out onto paved surfaces.
- Water Bar A diversion shall be constructed as part of the construction entrance if needed to prevent surface rundf from flowing the length of the construction entrance and out onto paved surfaces.
- Maintenance Top dressing of additional stone shall be applied as conditions demand. Mud spilled, dropped, washed or tracked onto public roads, or any surface where runoff is not checked by sadiment controls shall be removed immediately. Removal shall be accomplished by scraping or sweeping.
- 10. Construction Entrances shall not be relied upon to remove mud from vehicles and prevent off-site tracking Vehicles that enter and leave the construction site shal be restricted from muddy areas.
- Removal The entrance shall remain in place until the disturbed area is stabilized or replaced with a permanent roadway or entrance.

(P)







- All sitt fence shall be placed as close to the confour as possible so that water will not concentrate at low points in the fence and so that small swales or depressions that may carry small concentrated flows to the sitt fence are dissipated along its length.
- Ends of the slit fences shall be brought upslope slightly so that water ponded by the slit fence will be prevented from flowing around the ends.
- 4. Silt fence shall be pleced on the flattest area
- Where possible, vegetation shall be preserved for 5 feet (or as much as possible) upslope from the silt tence. If vegetation is removed, it shall be reestablished within 7 days from the installation of
- The height of the silt fence shall be a minimum of 16 inches above the original ground surface.
- The slit fence shall be placed in an excavated or sliced trench cut a minimum of 6 inches deep. The trench shall be made with a trencher, cable laying machine, slicing machine or other suitable device which will ensure an adequately uniform trench death.
- 8. The slit fence shall be placed with the stakes on the downslope side of the geolextile. A minimum of 8 inches of geotextile must be below the ground surface. Excess material shall lay on the bottom of the 6-inch deep trench. The tranch shall be

Specifications



© COPYRIGHT 2016

DAVID SOMMERS & ASSOCIATES, LLC

ALL RIGHTS RESERVED

CENTER

EVENT

KURYLA

JOYCE

HIGHFIELDS
FOR:
KEN AND JOY
1840 GEDRAETOWN ROAT
HUDSON, OH 44286

0

INC.

ASSOCIATES,

AND No ENGINEER

HEJDUK-COX

4

- Seams between sections of silt tence shall be spilced together only at a support post with a minimum 6-inch
- Maintenance Silt fence shall allow runoff to pass only as diffuse flow through the geotectie. If runoff overlops the silt fence, flows under the father or around the ends, or in any other way allows a curcumstrated flow discharge, one of the following shall be performed, as appropriate 1) layout of the silt fence shall be changed 2) accumulated sediment shall be removed 3) other practices shall be installed.

Sediment deposits shall be routinely removed when the deposit reaches approximately one-half of the height of the sit tence.

Silt fences shall be inspected after each reinfall and at least delity during a prolonged reinfall. The location of existing silt fence shall be reviewed delity to ensure its proper location and effectiveness. If damaged, the silt fence shall be repaired immediately.

#### Criteria for SIII Fence Materials

- 1. Fence Posts. The length shall be a minimum of 32 inches. Wood posts will be 2-by-2-in, nominally dimensioned hardwood of sound quality. They shall be free it knots, spills and other visible imperfections. The maximum spacing between posts shall be 10 feet. Posts shall be driven a minimum 16 inches into the ground, where possible. Otherwise, the posts skall be adequately secured to prevent overturing of the fence due to sediment/water loading.
- 2. Sit Fence Fabric See chart below

Cetoria	for	Sili	Fence	Enhaic	

Fabric Properties	Values	Test Method
Mnimum Tensile Strength	120 lb.	ASTM D 4632
Maximum Elongation @ 50 lbs.	50%	ASTM D 4632
Minimum Puncture Strength	50 lb.	ASTM D 4833
Minimum Tear Strength	40 lb.	ASTM D 4533
Apparent Opening Size	≤ 0.84 mm	ASTM D 4751
Minimum Permittivity	1x10 <sup>-2</sup> sec <sup>-1</sup> ·	ASTM D 4491
UV Exposure Strength Retention	70%	ASTM G 4355


# for Concrete Washout Area - Erect a sign identifying the washout area for ⊸ y y y y y y Plan 1. The washout area shall be installed prior to any concrete placement gosite. Sediment tracking control (e.g. temporary stone drive) is required leading to the washout area where concrete trucks will be off a paved surface. 3. The washout area shall be enlarged as necessary to maintain capacity for waste concrete.

Waste material from washout operations must be removed and legally disposed of when two-thirds of the wet storage capacity of the containment basin has been reached.

At the end of concrete operations, all waste concrete shall be removed and legally transported to an approved disposal site.

After removing the washout area, restore the ground grade to original level; seed and mulch (or otherwise stabilize) the disturbed area as per final seeding specifications.






- The earth around the inlet shall be excavated completely
- 3. The wooden frame shall be constructed of 2-inch by 4-inch construction-grade lumber. The 2-inch by 4-inch posts shall be driven one (1) ft, in for the ground at four context of the initial and the but portion of 2-inch by 4-inch frame assembled using the overlap joint shown. The top of the trans shall be all east lines below adjourn roads if ponded water will pose a safety hazard to traffic.
- Wire mesh shall be of sufficient strength to support fabric with water fully impounded against it. It shall be stretched lightly around the frame and fastened securely to the frame.
- Geotextile material shall have an equivalent opening size of 20-40 given and be resistant to smitght, it shall be stretched tightly around the frame and fastened securely. It shall extend from the top of the frame to 18 inches below the inlet notch elevation. The geotextite shall overlap s one side of the inlet so the ends of the cloth are not
- 6 Pack#il shall be placed amount the lelet in compacted 6-inch tayers until the earth is even with notch elevation on ends and top elevation on sides.
- A compacted earth dike or check dam shell be A compacted earn once or onesk dame and to constructed in the dilich line below the inlet if the inlet is not in a depression. The top of the disks shall be at least 6 inches higher than the top of the frame.

#### Specifications for Temporary Diversion





#### CROSS - SECTION


- Dreinage area should not exceed 10 acres. Larger areas require a more extensive design.
- Dika Top Width (R.) Height (ft.) Side Slope Shape
- 1.5 4:1 1.5 2:1
- etion traffic will cross, the top width may be
  - 6. Diversions shall be seaded and mulched in accordance with the requirements in practice standards TEMPORR, SEEDING for PERMANENT SEEDING and MULCHIN as soon as they are constructed or other suitable stabilization in order to preserve dike height and reduce mulchenance.

Temporary Diversion Stabilization Treatment
Diversion Silope «2 ac. 2 -5 cv. 5 -10 ac.
0 -3% seed & size seed & straw
3 -5% seed & size seed & straw
6 -6% seed & size seed & straw
6 -8-20% seed & size seed & straw
6 -20% seed & size s

4. The grade may be variable depending on the


(TD)

- No solid or fiquid waste, including building materials or their packaging, shall be discharged in storm water runoff.
- Concrete trucks are not permitted to wash directly into storm sewers, streams or drainage channels.
- 3. Off-site tracking of sediment by construction vehicles must
- Waste disposal via open burning is prohibited where not permitted under the State of Ohlo open burning laws,
- Contaminated soils or soils where construction site chemicals or petroleum products have been spilled must be treated and/or dispo-of st an Oho EPA-approved solid waste management facility or a hazardous waste tractment, sturage or disposal facility (TSDF).
- Storm water that comes in contact with contaminated soils or soild and industrial waste must be collected and disposed of as a wastewater.
- Fuel tanks and drums or other containers holding construction site chemicals must be stored within a diked erea.
- Sediment-laden trench or ground water must pass through a sediment-settling pond or be dewatered in place using a sump pit, liker bag or other comparable method prior to being discharged from the site.
- Trench and ground water free from sediment or other pollutants
  may be discharged without treatment provided this water does not
  become pollutant-laden by traversing over disturbed soils or other
  pollutant sources.
- No toxic or hazardous wastes shall be disposed into storm drains, septic tanks or by burying, burning or mixing the wastes.
- Provide covered and leak-proof containers to store debris, trash, and hazardous or petroleum wastes for proper disposal.
- All construction and demolition debris waste must be disposed of in an Ohio EPA approved C&DD landfill as required by Ohio Revised Code 3714.
- A spill-prevention and countermeasures (SPCC) plan must be developed for sites with one above-ground storage tank of 660 A spin-prevention and countermeasures (SPCC) prefit must be developed for sites with one above-ground storage tank of 660 gallons or more, total above-ground storage of 1,330 gallons, or below-ground storage of 42,000 gallons of fuel.
- Process wastewaters (equipment washing, feechate and concrete wash-outs) must be collected and disposed of at a publicly-owned treatment works.
- Use proteoled storage areas for industrial and construction materials to minimize exposure of such materials to storm water.
- 16. Petroleum waste spills of 25 gallons or more require notification of Ohio EPA (800-282-5378), local fire department (and if application the local emperancy planning committee within 30 minutes. For smaller spills of petroleum-based or concrete cubin 30 minutes, reconsult manufacturer's special handling procedures.



PROJECT: 12283 DATE: 11/14/2016 DRIAWN: JLK CHECKED: JLK

C105




#### EXISTING OUTLET STRUCTURE MODIFICATIONS

#### CITY OF HUDSON CONSTRUCTION NOTES

- THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING AND PAYING FOR ALL PERMITS REQUIRED FOR THE PROJECT.
- ALL EXISTING APPURTENANCES (UTILITY POLES, VALVES, HYDRANTS, MANHOLES, ETC.) ARE TO BE MAINTAINED BY THE CONTRACTOR UNLESS OTHERWISE SHOWN ON THE PLANS.
- 6. ALL KNOWN ABOVE AND UNDERGROUND SERVICES HAVE BEEN HOTED ON THE DRAWINDS, THE CONTRACTOR ACCEPTS PULL RESPONSIBILITY FOR ANY SERVICES DAMAGED DURNO THE CURSTRUCTION OF THE PROLECT WHETHER SHOWN OR NOT ON THE DRAWINGS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESTORMO THE SERVICE AS SOON AS POSSIBLE AT THE CONTRACTORS OWN EXPENSE.
- VIDEO TARING OF PROJECT SHALL BE DELIVERED AND ACCEPTED BY THE CITY OF HUDGON ENGINEERING DEPARTMENT A MINIMUM OF 14 CALENDAR DAYS PRIOR TO START OF CONSTRUCTION ACTIVITIES.
- 9. A PRECONSTRUCTION MEETING SHALL BE SCHEDULED A MINIMUM OF 48 HOURS (2 WORKING DAYS) AFTER SUBMISSION OF A MINIMUM OF 8 APPROVED SETS OF PLANS AND ALL SHOP DAMINES APPLICATE TO THE PROPOSED IMPROVEMENTS. A PRECONSTRUCTION MEETING MUST BE HELD PROR TO START OF ANY
- 10. THE LIMITS OF CLEARING AND GRADING SHALL BE FIELD STANED AND LINED WITH ORANGE CONSTRUCTION FERDING AB HOURS (2 WORKING DAYS) PRIOR TO THE PRECONSTRUCTION MEETING, AREA BESTOND THE LIMITS OF CLEARING AND GRADING SHALL NOT BE DISTURBED INCLUDING THE STOCKPILE OF ANY MATERIALS
- THE CONTRACTOR SHALL IMMEDIATELY NOTIFY THE CITY OF HUDSON OR ITS REPRESENTATIVE IF SUSPECTED HAZARDOUS MATERIAL OR ANY OTHER MATERIAL THAT MAY CREATE A HEALTH RISK IS DISCOVERED ON SITE.
- 13. ALL DISTURBED STORM SEWERS AND/OR APPURTENANCES, SIGNS, GUARD RAILING, MAIL AND/OR PAPER BOXES, DRIVE CULVERIS, FENCES, TREES, LANDSCAPING, OR OTHER TIESD SISTURBED BY THE CONSTRUCTION SHALL BE RESTORED OR REPARE! TO AT LEAST THE BEFORE—CONSTRUCTION CONDITION.
- ANY DEFECTS DISCOVERED IN NEW CONSTRUCTION, WORKGANSHIP, EQUIPMENT OR MATERIALS SHALL BE REPAIRED OR CORRECTED BY APPROVED METHODS AS DIRECTED BY THE CITY OF HUDSON.
- 16. APPROVAL BY THE CITY OF HUDSON ENGINEER CONSTITUTES NETHER EXPRESSED NOR IMPUED WARRANTIES AS TO THE FITNESS, ACCURACY, OR SUFFICIENCY OF PLANS, DESIGNS OR SPECIFICATIONS.
- 17. DURING TAPPING OF EXISTING UTILITIES, ANY TRAFFIC CONTROL REQUESTED OR REQUIRED BY THE CITY OF HUDSON WILL BE PROVIDED BY THE CONTRACTOR AT NO COST TO THE CITY.
- 18. COMPLIANCE WITH THE OCCUPATIONAL AND SAFETY ACT OF 1970 IS REQUIRED BY ALL CONTRACTORS ON THIS PROJECT.
- ROOF DRAINS, FOUNDATION DRAINS AND OTHER CLEAN WATER CONNECTIONS TO THE SANITARY SEWER ARE PROHIBITED.
- 20, ALL DISTURBED AREAS SHALL RECEIVE 4" OF TOPSOIL AND BE SEEDED AND MULCHED AS PER SECTION 9 LANDSCAPING AND STREET TREES OF THE CITY'S "ENGINEERING STANDARDS FOR INPRASTRUCTURE CONSTRUCTION", LITEST DUTION.
- 21. IF MUD, SOIL OR OTHER DEBRIS IS DEPOSITED ON ADJACENT STREETS, ROADS OR OTHER PROPERTY, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF SUCH AS DIRECTED BY THE CITY OF HUSSON OR ITS ENGINEER AT THE END OF EACH WORK DAY, OR AS REQUIRED DURING THE WORK DAY.
- 23. ALL STORM SENERS WITHIN PUBLIC RIGHTS-OF-WAY AND CITY OF HUDSON EASEMENTS SHALL BE PER SECTION 4 STORM COLLECTION OF THE CITY'S "ENGINEERING STANDARDS FOR INFRASTRUCTURE CONSTRUCTION", LATEST EDITION.

- 24. ALL PIPES SHALL BE PLACED OVER 4" OF BEDDING, BEDDING MATERIAL SHALL BE AS SPECIFIED IN CITY'S "ENGINEERING STANDARDS FOR INFRASTRUCTURE CONSTRUCTION", LATEST EDITION, FOR THE TYPE OF PIPE
- CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING AND PROTECTING THE FLOW OF VEHICULAR AND PEDESTRUM TRAFFIC AROUND THE JOB SITE, TRAFFIC CONTROL SHALL BE COORDINATED WITH THE CITY OF HUDSON POLICE DEPARTMENT.
- 26. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING PLANT TICKETS FOR ALL WATERIALS DELIVERED TO THE STIE. PLANT TICKETS WORST SHOW NET QUANTITY OF DELIVERED MATERIAL WATERIA, DELIVERED OR PLACED WITHOUT PLANT TICKETS SHALL BE REMOVED AND PROPERLY DISPOSED AT THE EXPENSE OF THE CONTRACT
- ALL DELIVERED MATERIALS SHALL MEET THE STANDARDS AND SPECIFICATIONS OF THE CITY OF HUDSON OR OTHER APPLICABLE AGENCIES, THE CITY OF HUDSON, OR ITS REPRESENTATIVE, RESERVES THE RIGHT TO REJECT ANY DELIVERED MATERIAL
- 28. THE CITY OF HUDSON, OR ITS REPRESENTATIVE, RESERVES THE RIGHT TO HALT ALL CONSTRUCTION ACTIVITY FOR NONCONFORMANCE OF PLANS, SPECIFICATIONS AND OTHER APPLICABLE STROMARDS OR REGULATIONS.
- 29, ALL CHANGES TO APPROVED DRAWINGS AND/OR SPECIFICATIONS MUST BE REAPPROVED BY THE CITY OF HUDSON PRIOR TO CONSTRUCTION.
- 30. ALL PAVING MATERIAL MUST BE PROVIDED BY ODOT CERTIFIED SUPPLIER, WRITTEN PROOF SHALL BE REQUIRED UPON DELIVERY OF MATERIALS. THE CERTIFIED MIX DESIGN MUST BE SUBMITTED TO, AND APPROVED BY, THE CITY OF HUDSON PRIOR TO
- 31. CONTRACTOR/DEVELOPER SHALL PROVIDE ALL REQUIRED ROADWAY SIGNAGE AS PER COOT WANUAL OF UNIFORM TRAFFIC CONTROL DEVICES INCLUDING STREET IDENTIFICATION SIGNAGE PER CITY STANDARDS FOR ALL ASPECTS OF THE IMPROVEMENT.
- 32. ALL BONDS AND OR LETTERS OF CREDIT SHALL NOT BE RELEASED OR REDUCED AND NO WATER OR SANITARY SEWER CUSTOMERS CAN BE CONNECTED UNTIL ALL RECORD DRAWINGS HAVE BEEN SUBMITTED, REVIEWED AND APPROVED BY THE CITY
- 33. ALL WORK, EXCEPT SIDEMALKS, STREET TREES AND STREET LIGHTS, AS PART OF THESE PLANS SHALL BE COMPLETED, INCLUDING PUNCH LIST ITEMS AND DEPICIENCY WORK WITHIN 1 YEAR OF THE DATE OF APPROVAL BY THE CITY ENGINEER. SIDEWALKS, STREET TREES AND STREET LIGHTS SHALL BE COMPLETED WITHIN TWO YEARS OF THE DATE OF APPROVAL BY THE CITY ENGINEER
- 34. FAILURE TO COMPLETE THE PROJECT IN ITS ENTIRETY AS APPROVED BY THE PLANNING COMMISSION, INCLUDING PUNCH UST ITEMS, WILL RESULT IN THE CITY OF HUDSON HOLDING ALL FUTURE ZONING CERTIFICATES UNTIL ALL WORK HAS BEEN
- WANUFACTURERS OR SUPPLIERS AFFIDANT FOR ALL CONSTRUCTION MATERIALS SHALL BE PROVIDED AS PER THE CITY'S "ENGINEERING STANDARDS FOR RAPASTRUCTURE CONSTRUCTION", LATEST EDITION PRIOR TO THE START OF
- THE CONSTRUCTION OF SANITARY SEWERS, WATER MAINS, LET STATIONS AND APPURTENANCES IS PROHIBITED UNTIL ALL PLANS HAVE BEEN APPROVED BY THE OHIO ENVIRONMENTAL PROTECTION AGENCY.
- 37. ALL SANITARY SEWERS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE CITY OF HUDSON "ENGINEERING STANDARDS FOR INFRASTRUCTURE CONSTRUCTION",
- 3B. ALL SANITARY SEWERS CONSTRUCTED IN SUMMIT COUNTY DEPARTMENT EMMROHMENTAL SERVICES (SC-DOES) SERVICE DISTRICTS AND SERVED BY SC-DOES SHALL COMPLY WITH SC-DOES REQUIREMENTS.
- 39, SHOP DRAWINGS FOR THE PROPOSED LIGHT FIXTURES SHALL BE ATTACHED TO SHUP INFORMED LIGHTING FUN AND SUBMITTED WITH THE SX SETS OF FLANS AS REQUIRED IN NOTE 0. THE LIGHT FIXTURES SHALL HAVE A RECESSED LAMP, FLAT LENESS AND OPHIONAL HOUSE SHEILDING ANALIEL. THE CITY MAY REQUIRE HOUSE SHIELDS TO BE ADDED AND OTHER MODIFICATIONS AFTER CONSTRUCTION AT
- 40, THE OWNER SHALL SUBMIT A NOTICE OF INTENT (N.O.L) APPLICATION TO THE OHIO ENVIRONMENTAL PROTECTION ASSENCY (E.P.A.) AND DETAIN AUTHORIZATION FOR STORM WATER DISCHARGES ASSOCIATED WITH CONSTRUCTION AUTHORIT MOBILE THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (N.P.D.E.S.) OR THE LATEST FEDERAL, STATE AND/OR LOCAL RESULCTIONS. THE OWNER SHALL SUBMIT A COPY OF THE N.P.D.E.S. PERMIT TO THE CITY OF TUDSON 48 HOURS (2 WORKING DAYS) PRIOR TO SCHEDULING A PRECONSTRUCTION MEETING.


- 1 472-2 1/2" NST 90: SIAMESE W/ CAPS (FDC) FIRE DEPT, CONNECTION 2) -- 4 "x8" CALV. THREADED MIPPLE TAPPED &" FROM BOTTOM END w/ 1/2"
- (4) -- 4" FLANGED SIT ELSOW
- (5) + EZ FLANGE (EBBA)
- (6) -- +" PIPE (RESTRAINED)
- 7 -4" MJ 90" ELBOW W/ MEGALUGS




SECTION FIRE DEPARTMENT CONNECTION (SIAMESE CONNECTION)

SEE DISCLAIMER STATEMENT ON THE TITLE PAGE OF THESE ENGINEERING STANDARDS

FIG 2.15.6





GRANULAR EMBEDMENT PVC PIPE


GRANULAR EMBEDMENT. REINFORCED CONCRETE PIPE

BEDDING DETAILS


- 2. EXCAVATE RIO--CRI TO FINAL DEPTH AND DESIGN DIMENSIONS AND INSTALL 4" UNDERDRAIN
- PLACE BIO-RETENTION DESIGN MATERIAL (PLANTING MEDIA) "KB BIORETENTION SOIL" FROM KURTZ BROS., INC. 6415 GRANGER ROAD, INDEPENDENCE, OH, 44131 PH: 216-986-7000

IT IS RECOMMENDED THAT BIORETENTION DESIGN MATERIAL BE TESTED AND CERTIFIED TO MEET THE FOLLOWING CRITERIA:

Loamy sand (at least 80% sand and no more than 10% clay) ph range from 5.2-8.0, dreame matter 3 to 5% by weight (8 to 20% by volume) phosphorius 15 to 80 mg/ $^{\prime}$ g (ppm) soluble. Salts not to exceed 540 ppm



#### DETAIL OF BIORETENTION CELL



JASON L. KEKIC E-61676 ALL RIGHTS RESERVED

CENTER **EVENT** JOYCE

HIGHFIELDS AND KEN 1940 GEC

0 S N ASSOCIATES, AND SKIENE HEJDUK-COX CONSILATIVE STATE OIL SOUTH MILES ROOF

4

PROJECT: 12283 DATE: 11/14/2016 DRAWN: JLK CHECKED: JLK

C106

CONSTRUCTION DETAILS

#### APPROVED PIPE, FITTINGS, BOLTS, ETC.

#### FOR AKRON SYSTEM WATER MAIN INSTALLATIONS

Pipe: Class 53 6 AWWA C1

1810 - 1 1 1

Class 53 dictile from per AWWA C151 specifications, with cement-lining per AWWA 6104. Labeled polyethylene encasement per AWAMA C105 is required:

Pipe Joints:

Push-ön joints (Tytim, Bell-Tite, etc.), per AWWA.C151 specifications with plain or restraining rubber gaskets per AWWA.C111 specifications.

Fittings:

Chast 450 ductile from compact tittings per AWWA C153 or full thickness apatings per AWWA 0.110 are acceptable, with mechanical joint ends and ductile from follower glands. Alterior tiple is required on all hydrant runs between this tee and fuddrant runsvalve.

Push-on Joint with Field Lock (4 through 12 inch only) or Fast Grip gaskets (4 through 12 inch only), or mechanical joint with restationed follower plands, and 6 office alteriorable caps on every other bull thread. Super-Lock, TR-Tlax or Flex-Ring required, on all 16 inch or larger pipe diameters.

Restrained fitting devices:

Restrained pipe

All valves, bends, offseis, hydrant inlets, caps, pluips, and branches of tees and wyes mustrbe restrained using mechanical joint with restrained follower glands or restraining gaskets: Hardwood blocking is required for all dameters & through not, concrete blocking and strapping for all dameters all through concrete blocking is required on all fine lines and orgal dameters in area over 100 ps; Restrained joints for disperties 12 gloch and under shall be installed for a length of 30 feet on each side of a valve, bend or offset using Field-Lock of Fast-Giff, restraining gaskets or mechanical joint with restrained follower glands. Restrained follower glands. Restrained follower glands. Better on each side of a valve, bend or offset using Field for a length of 30 feet on each side of a valve, bend or offset using mechanical joint with restrained follower.

Mechanical Join Thead Bolts: Hydrantai All mechanical joints shall be made with Sor-Ten or construction grade alloyed dualite iron bolts. Thead bolts shall be ½ inch longer than standard length and must include a 6 52 zinc anode cap on every other bolt thread.

Akron-style Mueller Centurian Model (A423, Kennedy Guardian Model K-61A. American Flow Control Model 8528 with 8 not holet, American Flow Costol Model 8848 with 8 inch tirlet. Threads shall be Akron style as chown on Akron Water Works Standard Construction Drawings F-3268 and E-3440.

Gate Valves:

Resilient seat wedge (RSW) yaives with restrained mechanical joints. Valves shi have non-rising stems and shall open to the right (clackwise).

Butterfly Valves 16 Inch and op Restrained mechanical joint or aboutdered (not grooved) Victablic ends with Style 44N doublings and attnitess steel \$16 bolts. Rubber eyes in his valve must be replaceable. Plangad and or water-style valves are not acceptable.—

Only Bibby, Tyrick, East Jordan, or Bingham and Texton brands acceptable for

Valve Boxes:

companions.

Riser place must be of yoloy compsion resistent material. Philip must be cast from and thread-fints a brass ring.

Revised 3/07

Acc: F-14908

REDUCE

## CITY OF AKRON PUBLIC UTILITIES BUREAU

#### BACKFLOW PREVENTION PROGRAM (330) 375-2690

#### REDUCED PRESSURE PRINCIPLE BACKFLOW PREVENTION ASSEMBLY

#### Installation Requirements

- All piping to conform to Akroa Water Works Standard Construction Drawings and Specifications.
- 2. Bypassing of this assembly is specifically prohibited,
- Installation of this assembly in vaults is specifically prohibited.
- 4. Unions prior to backflow prevention assemblies are prohibited.
- 5. Installed directly after the meter setting ahead of any outlets.
- 6. Installed so as to be readily accessible for inspection, testing, and maintenance.
- Provided with adequate space for inspection, testing, maintenance, and disassembly.
- Protected from freezing by installation within a heated building
- Mounted in a horizontal position with abutting stiut-off valves, as supplied with the assembly, three feet above finished floor.
- 10. Provided with adequate drainage.
- 15. installed so that there is a visible free discharge from the relief port with no extension ploing.
- Installed as per manufacturer's specifications. Where manufacturer's specifications conflict with these guidelines, these guidelines shall govern.
- 13. Because of their design, backflow prevention assemblies create a closed system and a detectable pressure loss. Because of these facts, the installation may after the hydraulics, of the Internal plumbing system. The owner should contact a mechanical designer prior to last lating.
- 14. Upon installation, assemblies must be tested by a backflow prevention assembly tester; certified by the Ohio Department of Commerce. The assembly must be dismantled, inspected internally, cleaned, and repaired, if necessary.

Rev. 3/07

Page#15

The state of the s

tcc\_F-13859



### CITY OF AKRON PUBLIC UTILITIES BUREAU

#### BACKFLOW PREVENTION PROGRAM (330) 375-2690

#### DOUBLE CHECK DETECTOR ASSEMBLY

#### Installation Requirements

- All plping to conform to Akron Water Works Standard Construction Drawings and Specifications.
- 2, Bypassing of this assembly is specifically prohibited.
- The bypass meter and the small double check valve assembly on the bypass line shall be approved by the City of Akron Water Department, furnished and installed by the owner.
- 4. Unions prior to backflow prevention assemblies are prohibited.
- 5. Installed so as to be readily accessible for inspection, testing, and maintenance:
- 6. Provided with adequate space for inspection, testing, maintenance, and disassembly.
- 7. Protected from freezing by installation within a heated building or an approved precast
- Mounted in a horizontal position with abuilting shut-off valves, as supplied with the assembly, three feet above finished floor.
- Installations above ground level are preferred. Where above ground installations are not reasonably practical, a yault may be used with the approval of the Public Utilities Bureau.
- Installed as per manufacturer's specifications. Where manufacturer's specifications conflict with these guidelines, these guidelines shall govern.
- 41. Because of their design, backflow prevention assemblies create a closed system and a detectable pressure loss. Because of these facts, the installation may alter the hydrautics of the internal plumbing system. The owner should contact a mechanical designer prior to installation.
- 12. Upon installation, assemblies must be tested by a backflow prevention assembly tester, certified by the Ohlo Department of Commerce. The assembly must be dismantled, inspected internally, cleaned, and repaired, if necessary.

Rev. 3/07

Page #

Acc. F-14909

AMERICAN FLOW CONTROL BBZS WITH 6" INLET,
RESTRAINED FOLLOWER GLAND OR PUSH-OM
WITH FIELD LOCK OR FAST GROP CASKET.

AMERICAN FLOW CONTROL BBZS WITH 6" INLET,
RESTRAINED FOLLOWER GLAND OR PUSH-OM
WITH FIELD LOCK OR FAST GROP CASKET.

AMERICAN FLOW CONTROL BBZS WITH 6" INLET,
RESTRAINED FOLLOWER GLAND OR PUSH-OM
WITH FIELD LOCK OR FAST GROP CASKET.


AMERICAN FLOW CONTROL BBZS WITH 6" INLET,
RESTRAINED FOLLOWER GLAND OR PUSH-OM
WITH FIELD LOCK OR FAST GROP CASKET.


TRAFFIC

ABOVE

VALVE BOX

VALVE BO







NS AND ALTERATIONS TO:
HFIELDS EVENT CENTER
I AND JOYCE KURYLA
EORGETOWN HOAD

ADDITIONS AND ALTERATE
HIGHFIELDS FOR:
CMEN AND JOY
1340 GEORGETOWN HOAD
HUBSON, DH 4238

HEJDUK-COX AND ASSOCIATES, INC.

HE HE




PROJECT: 12283


DATE: 11/34/2018


DRAWN: JLK


CHECKED: JLK

C107









ADDITIONS AND ALTERATIONS TO:
HIGHFIELDS EVENT CENTER FOR:
KEN AND JOYCE KURYLA
1800 GEORGETOWN ROAD

JASON L. KEKIC E-61676

© COPYRIGHT 2016

DAVID SOMMERS & ASSOCIATES, LLC

ALL RIGHTS RESERVED

HEJDUK—COX AND ASSOCIATES, INC.

0



PROJECT: 12283

DATE: 11/14/2016

DRAWN: JLK

CHECKED: JLK

C108

CITY OF HUDSON

200 17 JULY APPROVED SING-

			DECIDU	OUS SHAD	E TREES & C	DRNAMENTALS
CODE	COMMON NAME	LATIN NAME	SIZE	COND.	SPACING	NOTES (ALL SUBSTITUTIONS REVIEWED FOR APPROVAL)
	Autumn Flame Red Maple	Acer rubrum 'Autumn Flame'	4" CAL.	B&B	PER PLANS	TRUNK FREE OF BRANCHES, 6-7' HEIGHT. MATCH HABIT & FORM. SUBSTITUTIONS: 'AUTUMN BLAZE' OR 'OCTOBER GLORY' - 4" CAL., MIN.
AC SA	Green Mountain Sugar Maple	Acer saccherum 'Green Mountain'	5" CAL.	B&B	27'-0" O.C. TYP.	TRUNK FREE OF BRANCHES, 6-7' HEIGHT, MATCH HABIT & FORM. SUBSTITUTIONS: 'COMMEMORATION' OR 'LEGACY' - 4" CAL. MIN.
	Autumn Brilliance Serviceberry	Amelenchier x grandifolia 'Autumo Brilliance'	12' HT. CLUMP	B&B	8'-6" O.C. TYP.	MULTISTEM TREE. MATCH HABIT & FORM.
	Heritage Riverbirch	Betula Niga 'Heritage' (Singlestern)	3" CAL, MIN	B&B	PER PLANS	SINGLESTEM TREE, MATCH HABIT & FORM, SUBSTITUTIONS; NYSSA SYLVATICA - 4" CAL. MIN.
	Whitespire Birch	Betula populifolia "Whitespire"	14' HT. CLUMP	B&B	6'-0" O.C.TYP.	MULTISTEM TREE. MATCH HABIT & FORM. SUBSTITUTIONS: CORNUS FLORIDA 'CHEROKEE PRINCESS' - 2" CAL. MIN.
CR VI	Winterking Hawthorn	Crataegus viridus Winter King' ver. inermis	3" CAL	B&B	PER PLANS	SINGLESTEM TREE, MATCH HABIT & FORM
CE CA	Eastern Redbud	Cercis Canadensis	2" CAL.	B&B	PER PLANS	MULTISTEM TREE. MATCH HABIT & FORM
MA PR	Prairifire Crabapple	Malus 'Prairifire'	10' HT. CLUMP	B&B	15'-0" O.C. TYP.	MULTISTEM TREE, MATCH HABIT & FORM
	Sweetbay Magnolia	Magnolia virginiana	10' HT. CLUMP	B&B	PER PLANS	MULTISTEM TREE. MATCH HABIT & FORM
PL AC	Bloodgood London Plans Tree	Platanus x acerifolia 'Bloodgood'	4" CAL.	B&B	18'-0" O.C. TYP.	TRUNK FREE OF BRANCHES, 6-7 HEIGHT. SINGLESTEM TREE. MATCH HABIT & FORM
	American Sycamore	Platanus occidentalis	4" CAL.	B&B	PER PLANS	SINGLESTEM TREE, MATCH HABIT & FORM
QU BI	Swarnp White Oak	Quercus bicolor	3" CAL.	B&B	PER PLANS	SINGLESTEM TREE, MATCH HABIT & FORM
	Scarlet Oak	Quercus coccinea	3" CAL.	B&B	PER PLANS	TRUNK FREE OF BRANCHES, 6'-7' HEIGHT, SINGLESTEM TREE, MATCH HABIT & FORM
	Shingle Oak	Quercus imbricaria	3" CAL.	B&B	PER PLANS	TRUNK FREE OF BRANCHES, 6-7 HEIGHT, SINGLESTEM TREE, MATCH HABIT & FORM
QUIM	Pin Oak	Quercus palustris	3" CAL.	B&B	PER PLANS	TRUNK FREE OF BRANCHES, 6"-7" HEIGHT. SINGLESTEM TREE, MATCH HABIT & FORM
		Querous shumardii	3" CAL.	B&B	PER PLANS	TRUNK FREE OF BRANCHES, 5'-7' HEIGHT. SINGLESTEM TREE. MATCH HABIT & FORM
QUSH	Shumard Oak		<del>  -  </del>			TRUNK FREE OF BRANCHES, 6'-7' HEIGHT, SINGLESTEM TREE, MATCH HABIT & FORM. SUBSTITUTIONS: TILIA CORDATA, TILIA MONGOLICA
TICO	Greenspire Littleleaf Linden	Tilia Cordata 'Greenspire'	4" CAL.	886	PER PLANS	'HARVEST GOLD' - 4" CAL MIN., ALNUS GLUTINOSA
ULPA	Allee Lacebark Elm	Ulmus parvifolia 'Emer II' (ellee)	4" CAL.	B&B	PER PLANS	TRUNK FREE OF BRANCHES, 8-7' HEIGHT. SINGLESTEM TREE. MATCH HABIT & FORM. SUBSTITUTIONS: ULMUS AMERICANA 'PRINCETON' OF ULMUS PARVIFOLIA BOSQUE' - 4" CAL. MIN.
			DEC	IDLIOUS &	EVERGREE	N SHRUBS
					SPACING	NOTES (ALL SUBSTITUTIONS REVIEWED FOR APPROVAL)
CODE	COMMON NAME	LATIN NAME	SIZE	COND.		SUBSTITUTIONS: DEUTZIA GRACILIS WIKKO-NO. 3 CONT.
BU DA	Butterfly Bush	Buddleia davidii	-	NO 3. CONT.	3'-0" O.C. TYP.	
BU GR	Green Velvet Boxwood	Buxus 'Green Velvet'	24"	: 8&B	2'-0" O.C. TYP.	
BU SE	Vardar Valley Boxwood	Buxus sempervirens "Vardar Valley"	24"	B&B	2'-0" O.C. TYP.	SUBSTITUTIONS: ARNOIA MELANOCARPA 'AUTUMN MAJIC' - 30" NO. 5 CONT.
FO GA	Mt. Airy Fothergilla	Fothergilia gardenii 'Mt. Airy'	24"	NO. 5 CONT.	3'-0" O.C. TYP.	SUBSTITUTION ACTION ACCUMENTATION OF THE CONTRACT OF THE CONTR
HY PA	Little Lime Hydrangea	Hydrangea paniculata 'Little Lime'	30"	NO. 5 CONT.	3'-0" O.C. TYP.	SUBSTITUTIONS: HYDRANGEA QUERCIFOLIA "SIKES DWARF" - 36" B&B
HY QU	Pea Wee Oakleaf Hydrangea	Hydrangea quercifolia 'Pee Wee'	36	NO. 5 CONT.	3'-0" O.C. TYP.	SUBSTITUTIONS: ILEX VERTICILLATA - 26" B&B
ILVE	Gacapon Winterberry	ilex verticiliata 'Cacapon'	36"	8&8	4'-0" O.C. TYP.	SUBSTITUTIONS, REA VERY MICHAIN - 30 DRD
IT VI	Little Henry Dwarf Sweetspire	Itea virginica 'Little Henry'	24"	NO. 3 CONT.	PER PLANS	SUBSTITUTIONS: ILEX X MESERVEAE 'CHINA GIRL' & ILEX X MESERVEAE 'CHINA BOY' - 36" B&B. (PLANT 1 'CHINA BOY' FOR 6 'CHINA GIRL')
MYPE	Northern Bayberry	Myrica pensylvanica	36"	B&B	3'-0" O.C. TYP.	SUBSTITUTIONS: ILEX X WESERVERE CHINA GIRL & ILEX X WESERVERE CHINA GOT - 30 BAB. (FEMAL) CHINA GOT FORG CHINA GIRL)
NE FA	Walker's Low Catmint	Nepeta x faassenii 'Walker's Low'	-	NO. 2 CONT.	2'-0" O.C. TYP.	
RH AR	Gro-low Fragrant Sumac	Rhus aromatica 'Gro-low'	24"	B&B	3'-0" O,C. TYP.	
SP JA	Little Princess Spirea	Spirea japonica 'Little Princess'	30"	848	3'-0" O.C. TYP.	
SY JU	Red Pixie Lilac	Syringə jullanəs 'Reds Pixie'	36" B&B	B&B	PER PLANS	SUBSTITUTIONS: SYRINGA PATULA 'MISS KIM' 36" 8&B
TA ME	Chadwlck Yew	Taxus x media 'Chadwick	24"	8&8	3'-0" O.C. TYP.	SUBSTITUTIONS: ILEX CRENATA 'GREEN LUSTRE' - 24" B&B
VICA	Compact Korean Spice Viburnum	Vibumum carlesii 'Compactum'	24"	NO, 3 CONT.	PER PLANS	· · · · · · · · · · · · · · · · · · ·
WE FL	Sonic Bloom Pearl Welgela	Welgele flordia 'Sonic Bloom Pearl'	24"	NO. 3 CONT.	3'-0" O.C. TYP.	
			]			
			GR	ASSES & PE	RENNIALS/A	ANNUALS
CODE	COMMON NAME	LATIN NAME	SIŻE	COND.	SPACING	NOTES (ALL SUBSTITUTIONS REVIEWED FOR APPROVAL)
AN PL	ANNUAL PLANTING	·	-	-		BY OWNER
CA GR	Gray's Sedge	Carex grayl	12" HT.	NO. 1 CONT.	12" O.C.	BIOSWALE PLANT MIX
	Shallow Sedge	Carex lurida	12" HT.	NO. 1 CONT.	12" O.C.	BIOSWALE PLANT MIX
CALU	Yellow Flag	Iris pseduacorus	12" HT.	NO. 2 CONT.	12" O.C.	BIOSWALE PLANT MIX
IR PS	American Blue Flag	Iris versicolor	12" HT.	NO. 2 CONT.	12" O.C.	BIOSWALE PLANT MIX
IR VI		Lobelia cardinalis	-	NO. 2 CONT.	12" O.C.	BIOSWALE PLANT MIX
LOCA	Red Cardinal Flower	Lobelia siphilitica	-	NO. 2 CONT.	12" O.C.	BIOSWALE PLANT MIX
LOSP	Great Blue Lobelia			PLUGS	8" O.C.	
NA RC	Daffodil	Pennisetum alopecuroides 'Little Bunny'	12" HT.	NO. 1 CONT.	10" O.C.	
PE AL	Little Bunny Fountain Grass	Гентаевин ворестоков вкое сенту	12 (1).	- 10, , 00,41,	- 10 0.0.	BYOWNER
PEPL	PERENNIAL PLANTING	-	<del>                                     </del>		-	
<u> </u>	<u> </u>		<u></u>		COVED 4 :	// ITC
			·		COVER & V	
	COMMON NAME	LATIN NAME	SIZE	COND.	SPACING	NOTES (ALL SUBSTITUTIONS REVIEWED FOR APPROVAL)
CODE		Clematis 'Jackmanii'	-	NO. 2 CONT.	18" O.C.	
CODE CL EM	Clematis	Olemana paovinam				1
	Clematis Creeping Lily Turf	Liriope spicata	-	NO. 1 CONT.	12" O.C.	
CL EM LI SP	Creeping Lily Turf	·	- 2" CELL	NO. 1 CONT. BARE ROOT	12" O.C. 4" O.C.	SUBSTITUTIONS: AJUGA REPTANS - 4" O.C.
CL EM		Liriope spicate				SUBSTITUTIONS: AJUGA REPTANS - 4" O.C. SUBSTITUTIONS: VINCA MINOR 'ATROPURPUREA' - 4" O.C.

© COPYRIGHT 2015 DAYID SOMMERS & ASSOCIATES, LLC

ALL RIGHTS RESERVED

ADDITIONS AND ALTERATIONS TO:
HIGHFIELDS EVENT CENTER FOR:
KEN AND JOYCE KURYLA
1940 GEORGETOWN ROAD
HUDSON, OH ACTOR

BID SET CONSTRUCTION DOCUMENTS



PROJECT: h14001


DATE: 06/13/2016

DRAWN: DLK

DRAWN: DLK
CHECKED: DLK-KGK

200 17 11 Mark Follows Planting schedule

L-400



GENERAL NOTES - PLANTING PLAN

STAKE ALL TREE LOCATIONS FOR REVIEW PRIOR TO INSTALLATION. ALL PLANTING PROCEDURES ARE SUBJECT TO THE REVIEW OF THE OWNER AND THE CONTRACTOR SHALL CORRECT ANY DEFICIENCIES FOUND AT NO ADDITIONAL COST TO THE OWNER.

SECURE PLANT MATERIAL AS SPECIFIED ON PLANS. IN THE EVENT THAT PLANT MATERIALS SPECIFIED ARE NOT AVAILABLE, CONTACT OWNER FOR APPROVED SUBSTITUTIONS. NO SUBSTITUTIONS FOR PLANT MATERIALS WILL BE ALLOWED WITHOUT PRIOR WRITTEN APPROVAL.

3. VERIFY THAT ALL PLANTING PRODUCTS, PLANT MATERIAL, AND PLANT QUANTITIES DELIVERED TO THE SITE MATCH WHAT IS INDICATED ON THE PLANS AND SPECIFICATIONS.

PROTECT ALL PLANT MATERIAL DURING DELIVERY TO PREVENT DAMAGE TO ROOT BALLS, TRUNKS, BRANCHES AND THE DESICCATION OF LEAVES. PROTECT ALL PLANT MATERIAL DURING SHIPPING WITH SHADE CLOTH OR SHIP WITH ENCLOSED TRANSPORT. MAINTAIN PROTECTIONS AND HEALTH OF PLANT MATERIAL STORED ON SITE. HANDLE ALL TREES WITH NYLON STRAPS. NO CHAINS OR CABLES WILL BE ALLOWED. REMOVE UNACCEPTABLE PLANT MATERIAL IMMEDIATELY FROM THE SITE.

ALL PLANT MATERIAL SHALL BE NURSERY GROWN, WELL FORMED, TRUE TO SPECIES, HARDENED OFF WITH VIGOROUS ROOT SYSTEMS, FULL CROWN AND CANOPIES, AND FREE FROM DISEASE, PESTS AND INSECTS, AND DEFECTS SUCH AS KNOTS, SUN SCALD, WINDBURN, LEAF DIS-COLORATION, IRREGULAR BRANCHING OR INJURIES.

6. ALL ROOT BALLS SHALL CONFORM TO THE SIZE STANDARDS SET FORTH IN "AMERICAN STANDARDS FOR NURSERY STOCK".

7. ALL PLANT MATERIAL DELIVERED TO THE SITE IS SUBJECT TO THE REVIEW OF THE OWNER BEFORE, DURING AND AFTER INSTALLATION.

PROVIDE PLANT SAMPLES OR PHOTOGRAPHS OF EACH PLANT SPECIFIED TO THE LANDSCAPE ARCHITECT FOR COMPLIANCE REVIEW PRIOR TO INSTALLATION.


. TEST FILL ALL TREE AND PLANTING PITS WITH WATER, PRIOR TO PLANTING, TO ASSURE PROPER SOIL PERCOLATION. PITS WHICH DO NOT ADEQUATELY DRAIN SHALL BE FURTHER EXCAVATED TO A DEPTH SUFFICIENT FOR DRAINAGE TO OCCUR ANDIOR BACKFILLED WITH SUITABLE DRAINAGE GRAVEL. NO ALLOWANCES SHALL BE MADE FOR PLANT MATERIAL LOSS DUE TO IMPROPER DRAINAGE. CONTRACTOR SHALL REPLACE DEAD OR DAMAGED PLANT MATERIAL AS A RESULT OF IMPROPER DRAINAGE WITH SAME SIZE AND SPECIES AT NO ADDITIONAL COST TO OWNER.

10. ALL PLANT MATERIALS SHALL BE PLANTED IN A PROFESSIONAL MANNER TYPICAL TO THE INDUSTRY STANDARDS OF THE AREA TO ASSURE COMPLETE SURVIVABILITY OF ALL INSTALLED PLANT MATERIALS AS WELL AS TO PROVIDE AN AESTHETICALLY APPROVED PROJECT. CONTRACTOR SHALL REFER TO THE PLANTING BETAILS FOR MINIMUM SIZE AND WIDTH OF PLANTING PITS AND BEDS, GUYING AND STAKING, MULCHING, AND OTHER PLANTING REQUIREMENTS.

11. ALL PLANTING AREAS SHALL BE WEED FREE PRIOR TO PLANTING INSTALLATION.

REMOVE ALL PLANTING AND LANDSCAPE DEBRIS FROM THE PROJECT SITE AND SWEEP AND WASH CLEAN ALL PAVED AND FINISHED SURFACES AFFECTED BY THE LANDSCAPE INSTALLATION.

LEGEND - PLANTING PLAN



#### CODED NOTES - PLANTING PLAN

(1) EXISTING TREE & PLANTING AREA TO REMAIN, PROTECT IN PLACE

2 POTTED PLANTERS, PLANTINGS AND PLANTER BY OWNER

(3) FIELD VERIFY LAYOUT OF PROPOSED TREE(SYPLANTINGS WITH LANDSCAPE ARCHITECT UPON TIME OF CONSTRUCTION

4' DIA, MULCH RING AROUND TREE, TYP.

A COPYRIGHT 2016

ALL RIGHTS RESERVED

KURYLA **EVENT** 

AND JOYCE HIGHFIELDS E FOR: KEN AND JOY(

BID SET CONSTRUCTION DOCUMENTS




PROJECT: h14001 DATE: 08/13/2016

DLK DRAWN: CHECKED; DLK-KGK

CITY OF HUDO . PLANTING PLAN -NORTH Mark Peliarons L-401

200



.

© COPYRIGHT 2015

DAVID SOMMERS & ASSOCIATES, LLC

ALL RIGHTS RESERVED

TER

HIGHFIELDS EVENT CENTER FOR.
KEN AND JOYCE KURYLA 1940 GEORGETOWN ROAD

BID SET CONSTRUCTION DOCUMENTS



PROJECT: h14001

DATE: 08/13/2016

DRAWN: DLK

CHECKED: DLK-KGK

PLANTING PLAN -SOUTH

L-402