

PHYSICAL CONDITION REPORT



**OTIC DESIGN PROJECT NO. 71-22-12
PROSPECT ROAD BRIDGE (CR 34) OVER THE OHIO TURNPIKE
MILEPOST 182.1
SUMMIT COUNTY, OHIO**

Prepared for:

Ohio Turnpike and Infrastructure Commission
682 Prospect Street
Berea, Ohio 44017-2799



Prepared by:

Compass Infrastructure Group
2800 Corporate Exchange Drive Suite 100
Columbus, Ohio 43231
Phone: (567)-644-2818
(as subconsultant to American Structurepoint Inc.)



COMPASS
INFRASTRUCTURE GROUP

CIG Project No.: 10043

August 2023

Table of Contents

1.0 INTRODUCTION	3
1.1 Description	3
1.2 Bridge Inspection Procedure	6
1.3 Nomenclature	6
2.0 BEAMS	8
2.1 Fatigue Prone Connections	11
3.0 SUBSTRUCTURE	12
3.1 Abutments	12
3.2 Piers	17
4.0 LOAD RATING SUMMARY	26
5.0 VERTICAL ALIGNMENT	30
6.0 REHABILITATION ALTERNATIVES	31
7.0 ESTIMATED COST	42
8.0 RECOMMENDED REHABILITATION ALTERNATIVE	42

Appendix A: Bridge Inspection Field Notes

Appendix B: Construction Cost Estimate

Appendix C: Exaggerated Roadway Profiles Exhibit & Vertical Clearance

Appendix D: Asbestos Containing Materials Bridge Survey Report MP 182.1 Prospect

Appendix E: Existing and Proposed Transverse Section

Appendix F: Bikeway Alternative Sketches

1.0 INTRODUCTION

Compass Infrastructure Group (Compass) performed an in-Depth inspection of the beams and substructures of the Prospect Road Bridge over the Ohio Turnpike, Milepost 182.1, on April 26th and April 27th, 2023. As the deck is scheduled for complete replacement as a minimum goal of the project it received a cursory review for any existing issue that could be mitigated in future design and was not included in the report.


1.1 Description

Prospect Road Bridge over the Ohio Turnpike, located at Milepost 182.1 carries two lanes of Prospect Road over the Ohio Turnpike in the City of Hudson, Summit County, Ohio. The structure is a continuous four-span steel beam bridge over the Ohio Turnpike. The superstructure consists of four rolled beams with cover plates at the piers, supported on reinforced concrete piers and reinforced concrete cellular abutments supported on driven piles. Span lengths are 44'-0"±, 69'-4"±, 69'-4"±, and 34'-8"± measured from center-to-center of bearings. The overall length of the bridge is approximately 246.27-ft. from end of approach slab to beginning of approach slab, per the existing plans.



Photograph #1 - Partial Elevation of Right Fascia (looking West)

PHYSICAL CONDITION REPORT
Prospect Road Bridge Over the Ohio Turnpike, Milepost 182.1



PROSPECT ROAD BRIDGE OVER
THE OHIO TURNPIKE, MILEPOST
182.1

Figure 1 - General Bridge Location Map

PHYSICAL CONDITION REPORT
Prospect Road Bridge Over the Ohio Turnpike, Milepost 182.1




Figure 2 - Detailed Bridge Location Map

**PROSPECT ROAD BRIDGE
OVER THE OHIO TURNPIKE,
MILEPOST 182.1**

1.2 Bridge Inspection Procedure

The 2023 inspection consisted of an in-depth inspection of the steel beam superstructure and concrete substructures, which was performed in accordance with the guidelines of the current ODOT Manual of Bridge Inspection and National Bridge Inspection Standards.

The in-depth inspection was limited to the rolled steel beams and substructure units as part of the rehabilitation strategy for the structure. The deck and parapets were not inspected because they are scheduled to be replaced. Hands-on inspection of the beams was performed at the substructure units using ladders. The steel beams in middle spans were inspected visually from the ground and from the substructures using ladders and no areas requiring further investigation were observed. The inspection work was made possible with lane closures and flagging services provided by the Ohio Turnpike.

The CIG staff members who performed the inspection were David Buchanan, Ian Foye and Justin Koesel.

1.3 Nomenclature

The following nomenclature will be utilized throughout this report:

Element Location:

1. The bridge is on south to north alignment with stationing increasing to the south. (downstation is north)
2. Piers are numbered from 1 to 3 from south to north looking downstation.
 - Pier #1 is adjacent to the Ohio Turnpike Eastbound outside shoulder
 - Pier #2 is in the Ohio Turnpike median
 - Pier #3 is adjacent to the Ohio Turnpike Westbound outside shoulder
 - Pier columns are numbered 1 to 3 from left to right (looking downstation)
3. The rolled steel beams are numbered G1 through G4 from the left to right (looking downstation).

Steel Elements:

The levels of rust and section loss are defined as follows:

- Light: A light, loose rust formation pitting the paint surface of the steel element.
- Moderate: A looser rust formation with scales or flaking forming. Definite areas of rust are discernable.
- Severe: A heavily stratified rust or rust scale with pitting of the metal surface. This rust condition eventually culminates in the perforation of the steel section.
- Steel Section Loss Categories:
 - Minor Section Loss: Up to 25%.
 - Moderate Section Loss: Greater than 25% and up to 50%.
 - Severe Section Loss: Greater than 50% with perforations to primary members.

Concrete Elements:

- Concrete Cracking: Cracking will usually be large enough to be seen with the naked eye. Efflorescence will often appear at the locations of cracks and is comprised of white calcium deposits protruding through the concrete surface. The size and extent of cracks is documented based on the criteria as follows:
 - Minor or Hairline Cracks: Up to 1/16"
 - Moderate Cracks: Greater than 1/16" up to 1/4"
 - Significant Cracks: Greater than 1/4"
- Concrete Spalling: Spalling is caused by the separation and removal of a portion of the surface concrete revealing a fracture of the concrete face. It is typically caused by corrosion of the reinforcing steel that expands the steel surface, pushing the cover concrete cover away from the reinforcing steel, often exposing the reinforcing steel.
- Hollow Sounding Area: An area of concrete which gives off a hollow sound when struck with a hammer or steel bar, indicating the existence of a fracture plane below the concrete surface.

2.0 BEAMS

Type: Rolled Steel Beams (4 - 33WF130 beams)

The rolled steel beams are in good condition and received a system OZEU painting in 2008. The beams exhibit localized patches of rust-stained protective coating system, and light surface rust in small patches along the bottom flange where the protective coating system has failed. These minor rust locations are small patches less than 3" wide. The moment plates and splices of the beams are in similar condition. The end diaphragms at the abutments are in good condition. The current condition of the protective coating system does not warrant replacement at this time.



Photograph #2 - Typical Beam and Intermediate Diaphragm Condition (End Spans) MP 182.1



Photograph #3 - Typical Beam and Intermediate Diaphragm Condition (Main Spans) MP 182.1



Photograph #4 - Typical End Diaphragm Condition (Main Span) MP 182.1



Photograph #5 - Beam 2 Splice with Light Rust, Span 1 MP 182.1

2.1 Fatigue Prone Connections

The fatigue prone connections are in good condition. For this structure the fatigue prone connections are the transverse welds at the ends of the welded moment cover plates over Pier 1, Pier 2, and Pier 3. No distress was observed in the bottom flange cover plate welds at the piers. The top flange cover plates could not be inspected because they are encased in the concrete deck and should be inspected after deck removal.



Photograph #6 - Typical Moment Plate Condition MP 182.1

3.0 SUBSTRUCTURE

3.1 Abutments

The abutments are in good condition. No spalls were observed on the exposed portions of the backwall. The exposed portions of the abutment stems are also free from spalls but do have some minor vertical cracks. No evidence of deterioration on the exposed faces of the wingwalls was observed. The catch basins at the north approach have failed. The northeast catch basin has collapsed in on itself, and the northwest catch basin has erosion and piping around the drain pipe. These drainage issues are causing the embankment along the wingwalls to erode, pulling away from the side faces of the north abutment wingwalls. The following figures and sketches indicate the limits of cracks recommended to be repaired via epoxy injection to protect against further deterioration in the future. In addition the erosion around the wingwalls should be backfilled with rock channel protection to mitigate further erosion regardless of repairs to the catch basins.



Photograph #7 - Rear (South) Abutment Vertical Crack MP 182.1




Figure 3 - Location of Proposed Concrete Repairs - Rear (South) Abutment Plan MP 182.1




Figure 4 - Location of Proposed Concrete Repairs - Rear (South) Abutment Elevation MP 182.1



Photograph #8 - Forward (North) Abutment Vertical Crack MP 182.1




Figure 5 - Location of Proposed Concrete Repairs - Forward (North) Abutment Plan MP 182.1




Figure 6 - Location of Proposed Concrete Repairs - Forward (North) Abutment Elevation MP 182.1



Photograph #9 - Collapsed Forward Right (Northeast) Catch basin MP 182.1



**Photograph #10 - Typical Wingwall Condition and Slope Erosion at Forward Left
(Northwest) MP 182.1**

3.2 Piers

In all three pier caps, a few minor cracks were observed and measured 0.013" to 0.025" wide. Additional minor cracks exist at old patch material cold joints on both faces of Piers 1 and 3. Hammer sounding indicated localized delaminated areas on all three pier caps. The northwest corner on the cap of Pier 3 has a deep spall with reinforcing steel stirrups exposed with moderate section loss and delamination extending to the side face. This spall extends to the bearing seat pedestal, which is missing a corner of concrete extending to the bearing masonry plate with the plate overhanging 1/8".

Pier 1 Column 1 has minor delamination present on the traffic face (north face) that extends onto the west face. No deterioration was observed to Pier 2 columns. Pier 3 Column 2 has minor delamination on the traffic face (south face) that leads to the east face. Pier 3 Column 3 has a spall in the patch on the south east corner, exposing three stirrups with minor section loss. The entire patch on the west, south, and east faces and a halo around the patch are delaminated with wire mesh rust showing through on the face.

Details showing the extents of these deteriorations and recommend areas to be repaired are detailed in the Figures below.





Figure 7 - Location of Proposed Concrete Repairs - Pier 1 Plan View MP 182.1



**Figure 8 - Location of Proposed Concrete Repairs - Pier 1 Downstation (North) Face
Elevation MP 182.1**





Figure 8 - Location of Proposed Concrete Repairs - Pier 1 View A-A MP 182.1



**Figure 10 - Location of Proposed Concrete Repairs - Pier 1 Upstation (South) Face
Elevation MP 182.1**




Figure 11 - Location of Proposed Concrete Repairs - Pier 2 Plan View MP 182.1




Figure 12 - Location of Proposed Concrete Repairs - Pier 2 Upstation (South) Face
Elevation MP 182.1




Figure 13 - Location of Proposed Concrete Repairs - Pier 2 Downstation (North) Face
Elevation MP 182.1




Figure 14 - Location of Proposed Concrete Repairs - Pier 3 Plan View MP 182.1





Figure 15 - Location of Proposed Concrete Repairs - Pier 3 Upstation (South) Face Elevation MP 182.1



**Figure 16 - Location of Proposed Concrete Repairs - Pier 3 Downstation (North) Face
Elevation MP 182.1**




Figure 17 - Location of Proposed Concrete Repairs - Pier 3 View A-A - View C-C MP 182.1





Figure 18 - Location of Proposed Concrete Repairs - Pier 3 Underside of Pier Cap MP 182.1



Photograph #12 - Pier 3 Column 3 Spall MP 182.1



Photograph #11 - Pier 1 Cap Cracks at Patch MP 182.1



Photograph #12 - Pier 3 Column 3 Spall MP 182.1

4.0 LOAD RATING SUMMARY

Load ratings were performed of the bridge's current conditions, including findings from our field inspection, and for a re-decking utilizing AASHTOWare Bridge Rating (BrR) software.

The existing bridge (current conditions) has a HS20 inventory rating of 1.380 and 1.351 for the fascia and interior beams, respectively. The HS20 inventory ratings for a re-decking are 1.253 and 1.284 for the fascia and interior beams, respectively. With the re-decking the exterior and interior beam rating decreases slightly due to the overhang width increase to accommodate the SBR-1-13 barrier while matching the existing width of 27'-10" toe-to-toe of parapets. Overall, the re-decking slightly reduces the controlling HS20 inventory rating from 1.351 to 1.284.

A summary of the load rating results is provided in Tables 1, 2 and 3.

Table 3 provides results that verify the additional widening does not reduce the overall load carrying capacity of the bridge. As shown with the additional beams available to distribute the composite dead loadings with minimal additional live loadings from pedestrians, the widening actually provides a slight increase in the available load carrying capacity.

PHYSICAL CONDITION REPORT
Prospect Road Bridge Over the Ohio Turnpike, Milepost 182.1

		Rating		Controlling Member	Location
		Factor	Tonnage		
Fascia Beams	HS-20 (Inventory)	1.380	49.68	Beams G1 & G4	Pier 2
	HS-20 (Operating)	2.304	82.96	Beams G1 & G4	Pier 2
	Ohio 2F1	5.880	88.20	Beams G1 & G4	0.5 of Span 2
	Ohio 3F1	3.995	91.87	Beams G1 & G4	0.5 of Span 2
	Ohio 4F1	3.574	96.50	Beams G1 & G4	0.5 of Span 2
	Ohio 5C1	2.838	113.51	Beams G1 & G4	Pier 2
	SU4	3.534	95.42	Beams G1 & G4	0.5 of Span 2
	SU5	3.233	100.22	Beams G1 & G4	0.5 of Span 2
	SU6	2.915	101.29	Beams G1 & G4	0.5 of Span 2
	SU7	2.698	104.56	Beams G1 & G4	0.5 of Span 2
	EV2	3.481	100.07	Beams G1 & G4	0.5 of Span 2
	EV3	2.280	98.02	Beams G1 & G4	0.5 of Span 2
Interior Beams	HS-20 (Inventory)	1.351	48.63	Beams G2 & G3	0.5 of Span 2
	HS-20 (Operating)	2.256	81.21	Beams G2 & G3	0.5 of Span 2
	Ohio 2F1	4.381	65.71	Beams G2 & G3	0.5 of Span 2
	Ohio 3F1	2.972	68.36	Beams G2 & G3	0.5 of Span 2
	Ohio 4F1	2.661	71.86	Beams G2 & G3	0.5 of Span 2
	Ohio 5C1	3.069	122.77	Beams G2 & G3	Pier 1
	SU4	2.632	71.06	Beams G2 & G3	0.5 of Span 2
	SU5	2.409	74.68	Beams G2 & G3	0.5 of Span 2
	SU6	2.172	75.47	Beams G2 & G3	0.5 of Span 2
	SU7	2.011	77.92	Beams G2 & G3	0.5 of Span 2
	EV2	2.590	74.47	Beams G2 & G3	0.5 of Span 2
	EV3	1.698	73.03	Beams G2 & G3	0.5 of Span 2

Table 1 - Load Rating Results of Existing (Continuous Spans)

		Rating		Controlling Member	Location
		Factor	Tonnage		
Fascia Beams	HS-20 (Inventory)	1.253	45.12	Beams G1 & G4	Pier 2
	HS-20 (Operating)	2.093	75.34	Beams G1 & G4	Pier 2
	Ohio 2F1	5.622	84.34	Beams G1 & G4	0.5 of Span 2
	Ohio 3F1	3.819	87.85	Beams G1 & G4	0.5 of Span 2
	Ohio 4F1	3.418	92.27	Beams G1 & G4	0.5 of Span 2
	Ohio 5C1	2.577	103.09	Beams G1 & G4	Pier 2
	SU4	3.379	91.23	Beams G1 & G4	0.5 of Span 2
	SU5	3.091	95.83	Beams G1 & G4	0.5 of Span 2
	SU6	2.787	96.85	Beams G1 & G4	0.5 of Span 2
	SU7	2.580	99.98	Beams G1 & G4	0.5 of Span 2
	EV2	3.328	95.68	Beams G1 & G4	0.5 of Span 2
	EV3	2.180	93.73	Beams G1 & G4	0.5 of Span 2
Interior Beams	HS-20 (Inventory)	1.284	46.21	Beams G2 & G3	0.5 of Span 2
	HS-20 (Operating)	2.144	77.17	Beams G2 & G3	0.5 of Span 2
	Ohio 2F1	4.163	62.44	Beams G2 & G3	0.5 of Span 2
	Ohio 3F1	2.824	64.96	Beams G2 & G3	0.5 of Span 2
	Ohio 4F1	2.529	68.29	Beams G2 & G3	0.5 of Span 2
	Ohio 5C1	2.909	116.37	Beams G2 & G3	Pier 1
	SU4	2.501	67.53	Beams G2 & G3	0.5 of Span 2
	SU5	2.289	70.96	Beams G2 & G3	0.5 of Span 2
	SU6	2.064	71.72	Beams G2 & G3	0.5 of Span 2
	SU7	1.911	74.05	Beams G2 & G3	0.5 of Span 2
	EV2	2.461	70.77	Beams G2 & G3	0.5 of Span 2
	EV3	1.614	69.40	Beams G2 & G3	0.5 of Span 2

Table 2 - Load Rating Results of Proposed (Continuous Spans)

PHYSICAL CONDITION REPORT
Prospect Road Bridge Over the Ohio Turnpike, Milepost 182.1

		Rating		Controlling Member	Location
		Factor	Tonnage		
Fascia Beam	HS-20 (Inventory)	1.284	46.22	Exisiting Beam G4	Pier 2
	HS-20 (Operating)	2.144	77.18	Exisiting Beam G4	Pier 2
	Ohio 2F1	5.584	83.76	Exisiting Beam G4	0.5 of Span 2
	Ohio 3F1	3.79	87.16	Exisiting Beam G4	0.5 of Span 2
	Ohio 4F1	3.394	91.64	Exisiting Beam G4	0.5 of Span 2
	Ohio 5C1	2.637	105.49	Exisiting Beam G4	Pier 2
	SU4	3.355	90.58	Exisiting Beam G4	0.5 of Span 2
	SU5	3.069	95.15	Exisiting Beam G4	0.5 of Span 2
	SU6	2.768	96.19	Exisiting Beam G4	0.5 of Span 2
	SU7	2.567	99.34	Exisiting Beam G4	0.5 of Span 2
	EV2	3.308	95.09	Exisiting Beam G4	0.5 of Span 2
	EV3	2.164	93.03	Exisiting Beam G4	0.5 of Span 2
Interior Beam	HS-20 (Inventory)	1.309	47.12	Ex. Beams G2 & G3	0.5 of Span 2
	HS-20 (Operating)	2.186	78.69	Ex. Beams G2 & G3	0.5 of Span 2
	Ohio 2F1	4.244	63.66	Ex. Beams G2 & G3	0.5 of Span 2
	Ohio 3F1	2.88	66.23	Ex. Beams G2 & G3	0.5 of Span 2
	Ohio 4F1	2.579	69.63	Ex. Beams G2 & G3	0.5 of Span 2
	Ohio 5C1	2.985	119.40	Ex. Beams G2 & G3	0.5 of Span 2
	SU4	2.550	68.85	Ex. Beams G2 & G3	0.5 of Span 2
	SU5	2.334	72.36	Ex. Beams G2 & G3	0.5 of Span 2
	SU6	2.104	73.13	Ex. Beams G2 & G3	0.5 of Span 2
	SU7	1.948	75.50	Ex. Beams G2 & G3	0.5 of Span 2
	EV2	2.51	72.16	Ex. Beams G2 & G3	0.5 of Span 2
	EV3	1.646	70.76	Ex. Beams G2 & G3	0.5 of Span 2

Table 3 - Load Rating Results of Proposed Widening (Continuous Spans)

5.0 VERTICAL ALIGNMENT

The existing surveyed minimum vertical clearance is 17.31'. This is more than the required minimum vertical clearance of 15'-6" per Section 207.1A of the OTIC Bridge Design Manual. The adjustment to the vertical profile is worked off the existing beam elevations, and the increase in deck thickness from 8.0" to 8.5" and an added 2" haunches over the beams. The difference in top of deck elevations is shown in the table and exaggerated profile below.

Node	Station	Existing Deck Thickness (in.)	Existing Deck Haunch (in.)	Existing Deck Elevation	Proposed Deck Thickness (in.)	Proposed Deck Haunch (in.)	Proposed Deck Elevation	Elevation Difference (in.)
Rear Abut.	13+86.6 7	8.00	0.00	1063.78	8.50	2.00	1064.01	2.87
Pier 1	14+30.6 7	8.00	0.00	1062.71	8.50	2.00	1062.97	3.03
Pier 2	15+00.0 0	8.00	0.00	1061.03	8.50	2.00	1061.32	3.42
Pier 3	15+69.3 3	8.00	0.00	1059.43	8.50	2.00	1059.66	2.86
Forward Abut.	16+13.3 3	8.00	0.00	1058.45	8.50	2.00	1058.62	1.94

Table 4 - Profile Data MP 182.1




Figure 18 - Prospect Road Graphical Vertical Profile MP 182.1

To chase back the proposed vertical alignment, the profile will extend 60' beyond the limits of the bridge. To ensure a smooth transition from existing to proposed pavement, 50' of resurfacing will be constructed.

6.0 REHABILITATION ALTERNATIVES

Three rehabilitation alternatives were evaluated based on direction from the OTIC in consultation with the City of Hudson due to the City's desire to add pedestrian and bike crossing over the Ohio Turnpike.

Alternative 1 - The first "baseline" alternative is deck replacement essentially in kind with no accommodation for pedestrian and or bikeway access. This is the original OTIC required rehabilitation work and costs.

Alternative 2 - The second alternative includes: a bridge deck replacement on existing substructure with a new pedestrian bridge constructed west of the existing rehabilitated bridge. This alternative is discussed in detail in Section 5.1 below. Existing OTIC bridge rehabilitation work is common between alternative 1 and 2 with the difference being the addition of the parallel truss bridge.

Alternative 3 - The third alternative includes: a bridge deck replacement that includes widening of the bridge deck, abutments and piers. This alternative is discussed further in Section 5.2 below.

All rehabilitation alternatives will include the following:

- New reinforced concrete composite deck, abutment slabs, approach slabs, parapets and chain link safety fencing
- Abutment & Pier pedestals where deterioration warrants replacement. Other pedestals will remain with bearing height differences accommodated with HP Pedestals
- Patching and other repairs of the existing substructures as noted in this report.
- Expansion bearing replacements with elastomeric bearings in accordance with OTIC's requirements for bridge re-decking projects. The existing steel rocker bearings at both Abutments will be replaced for all alternatives. We recommend retaining the existing good condition steel bolster bearings at Pier 2, as the existing bridge meets existing vertical clearance requirements, and the good condition of beams and limited repairs on the pier will eliminate the need for extensive lane and shoulder closures. If alternative 3 is implemented with the additional steel work we would recommend replacing all Pier 1 and 3 bearings as well to mitigate differential movement.
- Installing new guardrail; reconstructing two catch basins; relevant earthwork; and resurfacing the approach roadway pavement.

Maintenance of Traffic All Alternatives:

Prospect Road shall be closed during construction. Barricades are expected to be placed 225' north of the structure, and 500' south of the structure. Notes for the contractor to coordinate road closures with the work on the North Main Street bridge over the Ohio Turnpike will be included in the plan notes.

The detailed detour route is: Prospect Road to the south, East Hines Hill Road to the north, and North Main Street (SR-91) connecting the two. Of note additional coordination for this route will be required with the various local municipalities as there are truck restrictions on this route.

Existing Structure:

The existing bridge is a four-span structure with four 33WF130 non-composite beams with cover plates at Pier 1, Pier 2 and Pier 3 which support a reinforced concrete deck on reinforced concrete abutments and piers supported by piles and spread footings. The existing beams are spaced at 7'-8"± with a 3'-4"± overhang. The toe to toe of parapet width is 26'-8"± and out to out of bridge is 30'-0"±. See Figure 19 for Existing Transverse Section.




Figure 19 - Existing Transverse Section MP 182.1

6.1 Bridge Deck Replacement & Pedestrian Bridge (Alternative 1 and 2):

Alternative 1 and 2 - Proposed Deck Replacement: The existing deck, parapets and chain link safety fence will be removed and replaced with an 8 1/2" composite concrete deck with SBR-1-13 railing and chain link safety fence. The overhang will be increased to 4'-1" from 3'-4" to accommodate the change in barrier transitions from the Jersey style existing to the SBR-1-13 straight faced transition. These large overhangs will need to be taken into consideration during design and construction to prevent global superstructure distortion as the deck is poured, as the tributary deck load carried by the fascia beams exceeds 120% of the average tributary deck load carried by the interior beams. These loadings can be accommodated by temporary blocking and tie rods as necessary if the existing diaphragms do not have sufficient capacity. This will provide 27'-10" toe to toe of parapet and 31'-2" out to out bridge width. The proposed transverse section for the deck replacement alternative is shown as Figure 20.




Figure 20 - Proposed Transverse Section MP 182.1

Alternative 2 - Proposed Deck Pedestrian Bridge: To accommodate the pedestrian traffic, a new stand-alone pedestrian bridge will be constructed to the west of the existing rehabilitated bridge. The bridge will consist of two 120' long spans and 10' width. The proposed plan view for the deck replacement and pedestrian bridge alternative is shown as Figure 21.




Figure 21 - Proposed Pedestrian Bridge - Plan View MP 182.1

Proposed Pedestrian Bridge Abutments: Rear and forward reinforced concrete abutments will be constructed to support the pedestrian bridge. Similar to the existing bridge, the rear abutment will be supported by spread footing and the forward abutment will be supported by piles. See Figure 22 for the Plan View and Figure 23 for the Elevation and Section Views.




Figure 22 - Proposed Abutment Alternative 2 - Plan View MP 182.1




Figure 23 - Proposed Abutment Alternative 2 - Elevation and Section Views MP 182.1

Proposed Pier Pedestrian Bridge: A pier will be constructed to support the pedestrian bridge. The pier will consist of two 3' columns with a pier cap supported by drilled shafts to bedrock. See Figure 24 for the Plan View and Figure 25 for the Elevation View.




Figure 24 - Proposed Pier Plan View MP 182.1




Figure 25 - Proposed Pier Plan View MP 182.1

6.2 Bridge Deck Replacement & Widening (Alternative 3):

Proposed Deck Replacement and widening: The existing deck, parapets and chain link safety fence will be removed and replaced with an 8 ½" composite concrete deck with SBR-1-13 railing and chain link safety fence. Two additional W33x130 painted beams will be added with MC18x45.7 intermediate diaphragms. The right overhang will be increased to 4'-1" from the centerline of the existing fascia beam, the left overhang will be 1'-7" from the centerline of the proposed fascia beam. The large 4'-1" overhang will need to be taken into consideration during design and construction to prevent global superstructure distortion as the deck is poured, as the tributary deck load carried by that beam exceeds 120% of the average tributary deck load carried by the interior beams. These loadings can be accommodated by temporary blocking and tie rods as necessary if the existing diaphragms do not have sufficient capacity. This will provide 27'-10" toe to toe of parapet for vehicle traffic and a 10' shared use path with a BR-2 railing with a chain link safety fence. The overall out to out bridge width will be 42'-2". The proposed transverse section for the deck replacement alternative is shown as Figure 22.




Figure 22 - Proposed Transverse Section MP 182.1

Proposed Abutment Removal and Widening: A portion of the abutment will be removed and the abutment will be widened to accommodate the two new beams. See Figure 23 for Abutment Plan View and Figure 24 for Abutment Elevation and Section Views.




Figure 23 - Abutment Plan View MP 182.1




Figure 24 - Abutment Elevation and Section Views MP 182.1

Proposed Pier Widening: To support the two new beams, new independent two-column reinforced concrete piers will be required, built in-line with existing piers. These will be supported by drilled shafts. See Figure 25 for Pier Plan View and Figure 26 for Pier Elevation View.




Figure 26 - Pier Elevation View MP 182.1

7.0 ESTIMATED COST

Per the revised Phase 1A scope under Modification 1, estimated construction costs are provided for the rehabilitation of the Prospect Road Bridge (MP 182.1) and the additional costs incurred by providing a multi-use path crossing the Ohio Turnpike as outlined in Section 5.0 for each alternative. The structures, roadway and total estimated costs for the three alternatives are summarized in Table 5 and are provided in Appendix B.



With the current inflationary environment we have used a factor of 15% for inflation to 2024 construction based on recent trends in similar ODOT projects as OTIC has not let a significant number of similar project to date in the current inflationary environment to accurately gage its impacts on pricing.

Table 5 - Estimated Construction Cost				
	MP182.1 Rehabilitation Cost	Additional Multi-Use Path Cost	Additional Design Costs Beyond Alternative 1	Total Project Cost
Alternative 1	2,247,000			
Alternative 2	\$2,247,000	\$1,890,000	\$190,000	\$4,327,000
Alternative 3	\$2,247,000	\$1,541,000	\$217,000	\$4,005,000

8.0 RECOMMENDED REHABILITATION ALTERNATIVE

With the assumption that bike and pedestrian access will be provided Compass recommends Alternative 3. This alternative is the lowest total project cost as shown in section 7.0. In addition, it provides a structurally redundant option over the Ohio Turnpike mainline compared to the non-redundant fracture critical pedestrian truss. It also minimizes the number of structures required to be inspected and maintained by the OTIC and or by local agencies by agreement. Alternative 3 also minimizes project footprint and associated environmental impacts.

APPENDIX A:
BRIDGE INSPECTION FIELD NOTES



SP 519 REPAIR AREAS

MEASURED QUANTITY (SQ. FT.)	CONTINGENT QUANTITY (SQ. FT.)	TOTAL (SQ. FT.)
0	0	0

SP 516A AREAS

MEASURED QUANTITY (SQ. FT.)	CONTINGENT QUANTITY (SQ. FT.)	TOTAL (SQ. FT.)
0	0	0

NOTES:

1. THE AREAS OF REPAIR SHOWN ARE APPROXIMATE AND ARE BASED ON A FIELD INSPECTION. FINAL DETERMINATION OF THE AREAS TO BE REPAIRED WILL BE MADE BY THE ENGINEER AT THE TIME OF CONSTRUCTION.
2. THE TOTAL CONCRETE PATCHING AND CRACK REPAIR AREAS INDICATED ON THE DETAILS HAVE BEEN INCREASED TO ACCOUNT FOR ANY FURTHER DETERIORATION THAT MAY HAVE OCCURRED SINCE THE FIELD INSPECTION.


LEGEND:




- DENOTES AREAS TO BE REPAIRED AS PER ITEM SP 519



- REMOVAL PER SP 202, SEE SHEET X OF X.



PLAN
FORWARD ABUTMENT



ELEVATION
FORWARD ABUTMENT

Forward

SP 519 REPAIR AREAS		
MEASURED QUANTITY (SQ. FT.)	CONTINGENT QUANTITY (SQ. FT.)	TOTAL (SQ. FT.)
0	0	0
SP 516A AREAS		
MEASURED QUANTITY (SQ. FT.)	CONTINGENT QUANTITY (SQ. FT.)	TOTAL (SQ. FT.)
0	0	0

NOTES:

1. THE AREAS OF REPAIR SHOWN ARE APPROXIMATE AND ARE BASED ON A FIELD INSPECTION. FINAL DETERMINATION OF THE AREAS TO BE REPAIRED WILL BE MADE BY THE ENGINEER AT THE TIME OF CONSTRUCTION.
2. THE TOTAL CONCRETE PATCHING AND CRACK REPAIR AREAS INDICATED ON THE DETAILS HAVE BEEN INCREASED TO ACCOUNT FOR ANY FURTHER DETERIORATION THAT MAY HAVE OCCURRED SINCE THE FIELD INSPECTION.

LEGEND:



- DENOTES AREAS TO BE REPAIRED AS PER ITEM SP 519



- REMOVAL PER SP 202, SEE SHEET X OF X.

JFK pics
1 - Brg, 1/2 S. Beam 2
Delam area

Pic cont

- 6 - Moment plates have minor surface rust on Bot/R no section loss welds ok
- 7 - Bm 2 F.S. 1 minor rust from Bot/Flange interface with chalk
- 8 - hairline cr at N Face look S. Btm B3/4

IMF / JFK 4/27/23

Photos

- 1 - Pier beam 4 brg w/minor rust (typ)
- 2 - rest of P1 brgs tilted back twd abut
- 3/4 crack at patch S. face (look N)
- 5 - minor pack on Brg rust plates

Caulked bearings
interface of rocker and low plate
Keeperside of rocker

SP 519 REPAIR AREAS		
MEASURED QUANTITY (SQ. FT.)	CONTINGENT QUANTITY (SQ. FT.)	TOTAL (SQ. FT.)
0	0	0
SP 516A AREAS		
MEASURED QUANTITY (SQ. FT.)	CONTINGENT QUANTITY (SQ. FT.)	TOTAL (SQ. FT.)
0	0	0

NOTES:


- THE AREAS OF REPAIR SHOWN ARE APPROXIMATE AND ARE BASED ON A FIELD INSPECTION. FINAL DETERMINATION OF THE AREAS TO BE REPAIRED WILL BE MADE BY THE ENGINEER AT THE TIME OF CONSTRUCTION.
- THE TOTAL CONCRETE PATCHING AND CRACK REPAIR AREAS INDICATED ON THE DETAILS HAVE BEEN INCREASED TO ACCOUNT FOR ANY FURTHER DETERIORATION THAT MAY HAVE OCCURRED SINCE THE FIELD INSPECTION.

LEGEND:


-  DENOTES AREAS TO BE REPAIRED AS PER ITEM SP 519
-  REMOVAL PER SP 202, SEE SHEET X OF X.




UNDERSIDE OF CAP
PIER 1



PLAN
PIER 1



ELEVATION
PIER 1: LOOKING AHEAD
(North)





ELEVATION
PIER 1: LOOKING BACK
(South)

S. Pier
width 12" on N Face
18" on west face
36" tall on N
72" tall on W




UNDERSIDE OF CAP



ELEVATION

PIER 1: LOOKING AHEAD

2



ELEVATION

PIER 1: LOOKING BACK

2

PIER 2

SP 519 REPAIR AREAS		
MEASURED QUANTITY (SQ. FT.)	CONTINGENT QUANTITY (SQ. FT.)	TOTAL (SQ. FT.)
0	0	0
SP 516A AREAS		
MEASURED QUANTITY (SQ. FT.)	CONTINGENT QUANTITY (SQ. FT.)	TOTAL (SQ. FT.)
0	0	0

NOTES:

1. THE AREAS OF REPAIR SHOWN ARE APPROXIMATE AND ARE BASED ON A FIELD INSPECTION. FINAL DETERMINATION OF THE AREAS TO BE REPAIRED WILL BE MADE BY THE ENGINEER AT THE TIME OF CONSTRUCTION.
2. THE TOTAL CONCRETE PATCHING AND CRACK REPAIR AREAS INDICATED ON THE DETAILS HAVE BEEN INCREASED TO ACCOUNT FOR ANY FURTHER DETERIORATION THAT MAY HAVE OCCURRED SINCE THE FIELD INSPECTION.




LEGEND:



DENOTES AREAS TO BE REPAIRED AS PER ITEM SP 519



REMOVAL PER SP 202, SEE SHEET X OF X.



ELEVATION
PIER 3: LOOKING BACK

looking S. columns

PIER 3

MPics

9 - ELEV. VIEW

10 - CR under bn 4

11 - CR under bn 3

12 - CR top width ~0.013"

13 - Pier 3, column 3
spall/delam

14 - " column 2

15/16 - corner spall

17 - West side of N face
cap showing marked
cracks - hairline
except noted

18 - Bm 3 pedestal N side top
delam onto pedestal

19 - EAST End top cap cr/cr/cr

SP 519 REPAIR AREAS

MEASURED QUANTITY (SQ. FT.)	CONTINGENT QUANTITY (SQ. FT.)	TOTAL (SQ. FT.)
0	0	0

SP 516A AREAS

MEASURED QUANTITY (SQ. FT.)	CONTINGENT QUANTITY (SQ. FT.)	TOTAL (SQ. FT.)
0	0	0

NOTES:

- THE AREAS OF REPAIR SHOWN ARE APPROXIMATE AND ARE BASED ON A FIELD INSPECTION. FINAL DETERMINATION OF THE AREAS TO BE REPAIRED WILL BE MADE BY THE ENGINEER AT THE TIME OF CONSTRUCTION.
- THE TOTAL CONCRETE PATCHING AND CRACK REPAIR AREAS INDICATED ON THE DETAILS HAVE BEEN INCREASED TO ACCOUNT FOR ANY FURTHER DETERIORATION THAT MAY HAVE OCCURRED SINCE THE FIELD INSPECTION.

LEGEND:



• DENOTES AREAS TO BE REPAIRED AS PER ITEM SP 519



• REMOVAL PER SP 202, SEE SHEET X OF X.

APPENDIX B:
CONSTRUCTION COST ESTIMATES

PROJECT NO. 71-22-12 (PROSPECT ROAD BRIDGE OVER OTIC MAINLINE MP 182.1)
ENGINEER'S ESTIMATE - ALTERNATIVE 1

Ref. No.	Item No.	Item Description	Approx. Quantity	Unit	Unit Cost	Extended Bid Amount
GENERAL (Ref. Nos. 1-5)						
1	IB.ART.6	PREMIUM FOR CONTRACT PERFORMANCE BOND AND PAYMENT BOND	1	LUMP	\$ 50,000.00	\$ 50,000.00
2	SP 614	MAINTAINING TRAFFIC	1	LUMP	\$ 65,000.00	\$ 65,000.00
3	SP 619	FIELD OFFICE	1	LUMP	\$ 60,000.00	\$ 60,000.00
4	SP 623	CONSTRUCTION LAYOUT SURVEY	1	LUMP	\$ 50,000.00	\$ 50,000.00
5	624	MOBILIZATION	1	LUMP	\$ 100,000.00	\$ 100,000.00
TOTAL						\$ 325,000.00

STRUCTURES (Ref. Nos. 6 - 26)						
6	202	APPROACH SLAB REMOVED	106	SQ. YD.	\$ 60.00	\$ 6,360.00
7	SP 202	PORTIONS OF STRUCTURE REMOVED	1	LUMP	\$ 209,000.00	\$ 209,000.00
8	202	CATCH BASIN REMOVED	2	EACH	\$ 500.00	\$ 1,000.00
9	SP 509	EPOXY COATED REINFORCING STEEL, GRADE 60	71,450	POUND	\$ 3.00	\$ 214,350.00
10	SP 511(QC2)	CLASS QC2 CONCRETE, SUPERSTRUCTURE DECK SLAB	201	CU. YD.	\$ 1,300.00	\$ 261,300.00
11	SP 511(QC2)	CLASS QC2 CONCRETE, BARRIERS AND PARAPETS	78	CU. YD.	\$ 1,000.00	\$ 78,000.00
12	SP 511(QC2)	CLASS QC2 CONCRETE, ABUTMENT SLABS	37	CU. YD.	\$ 950.00	\$ 35,150.00
13	511	CLASS QC1 CONCRETE, PIER CAP	1	CU. YD.	\$ 1,250.00	\$ 1,250.00
14	511	CLASS QC1 CONCRETE, ABUTMENT NOT INCLUDING FOOTING	1	CU. YD.	\$ 1,250.00	\$ 1,250.00
15	512	CONCRETE REPAIR BY EPOXY INJECTION	67	FOOT	\$ 80.00	\$ 5,320.00
16	513	WELDED STUD SHEAR CONNECTORS	2,664	EACH	\$ 5.00	\$ 13,320.00
17	516	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE)	16	EACH	\$ 1,250.00	\$ 20,000.00
18	SP 519	PATCHING OF CONCRETE STRUCTURES	114	SQ. FT.	\$ 125.00	\$ 14,187.50
19	526	REINFORCED CONCRETE APPROACH SLABS	110	SQ. YD.	\$ 350.00	\$ 38,500.00
20	SP 527	FALSEWORK, TEMPORARY BRACING AND PROTECTIVE STRUCTURES	1	LUMP	\$ 75,000.00	\$ 75,000.00
21	SP 533	1 1/2" CONTINUOUS STRIP SEAL IN STRUCTURAL STEEL JOINT	66	FOOT	\$ 800.00	\$ 52,800.00
22	SP 536	CONCRETE WEATHERPROOFING, DECK, ABUTMENT SLABS, AND APPROACH SLABS	913	SQ. YD.	\$ 10.00	\$ 9,130.00
23	SP 536	CONCRETE WEATHERPROOFING, PARAPETS	436	SQ. YD.	\$ 10.00	\$ 4,360.00
24	SP 536	CONCRETE WEATHERPROOFING, SUBSTRUCTURE	289	SQ. YD.	\$ 15.00	\$ 4,335.00
25	601	CRUSHED AGGREGATE SLOPE PROTECTION	50	SQ. YD.	\$ 100.00	\$ 4,979.67
26	SP 607	TYPE II FENCE, ALL ALUMINUM (6'-0" CHAIN LINK WITH SPECIALS)	474	FOOT	\$ 150.00	\$ 71,100.00
27	611	CATCH BASIN, NO. 3	2	EACH	\$ 2,200.00	\$ 4,400.00
TOTAL - STRUCTURES						\$ 1,237,601.38

Ref. No.	Item No.	Item Description	Approx. Quantity	Unit	Unit Cost	Extended Bid Amount
ROADWAY (Ref. Nos. 29 - 43)						
28	201	CLEARING AND GRUBBING	1	LUMP	\$ 25,000.00	\$ 25,000.00
29	202	PAVEMENT REMOVED, ASPHALT	377	SQ. YD.	\$ 10.00	\$ 3,770.00
30	203	EXCAVATION	63	CU. YD.	\$ 20.00	\$ 1,260.00
31	203	EMBANKMENT	31	CU. YD.	\$ 25.00	\$ 775.00
32	204	SUBGRADE COMPACTION	377	SQ. YD.	\$ 5.00	\$ 1,885.00
33	254	PAVEMENT PLANING, ASPHALT CONCRETE, 1-1/4"	267	SQ. YD.	\$ 10.00	\$ 2,670.00
34	SP 302	ASPHALT CONCRETE BASE, PG64-22	43	CU. YD.	\$ 200.00	\$ 8,600.00
35	SP 304	AGGREGATE BASE	67	CU. YD.	\$ 70.00	\$ 4,690.00
36	SP 402	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, PG 64-22	18	CU. YD.	\$ 350.00	\$ 6,300.00
37	SP 404	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG 64-22	22	CU. YD.	\$ 200.00	\$ 4,400.00
38	407	NON-TRACKING TACK COAT	77	GALLON	\$ 5.00	\$ 385.00
39	606	GUARDRAIL, TYPE MGS	100	FOOT	\$ 25.00	\$ 2,500.00
40	606	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1	4	EACH	\$ 2,500.00	\$ 10,000.00
41	611	CATCH BASIN, NO. 3	2	EACH	\$ 2,750.00	\$ 5,500.00
42	642	EDGE LINE, 6", TYPE 1	0.19	MILE	\$ 5,000.00	\$ 946.97
43	642	CENTER LINE, 6", TYPE 1	0.09	MILE	\$ 6,000.00	\$ 568.18
TOTAL - ROADWAY						\$ 65,100.18

ENGINEER'S ESTIMATE

SUBTOTAL

\$1,627,701.57

Contingency - 20%

\$325,540.31

Inflation - 15%

\$292,986.28

TOTAL BASE BID (INCLUDES REF. NO. 1 THRU REF. NO. 43) ----->

\$2,246,228.16

PROJECT NO. 71-22-12 (PROSPECT ROAD BRIDGE OVER OTIC MAINLINE MP 182.1)
ENGINEER'S ESTIMATE - ADDITIONAL ALTERNATIVE 2 COSTS

Ref. No.	Item No.	Item Description	Approx. Quantity	Unit	Unit Cost	Extended Bid Amount
		GENERAL (Ref. Nos. 1-2)				
1		ADDITIONAL SURVEY	1	LUMP	\$ 20,000.00	\$ 20,000.00
2		GEOTECHNICAL INVESTIGATIONS	1	LUMP	\$ 50,000.00	\$ 50,000.00
3		ADDITIONAL ENGINEERING COSTS	1	LUMP	\$ 120,000.00	\$ 120,000.00
		TOTAL				\$ 190,000.00

		STRUCTURES (Ref. Nos. 4-25)				
4	203	SPECIAL - EARTHWORK (GRADING FOR TRAIL)	1	LUMP	\$ 100,000.00	\$ 100,000.00
5	503	UNCLASSIFIED EXCAVATION	1	LUMP	\$ 19,000.00	\$ 19,000.00
6	505	PILE DRIVING EQUIPMENT MOBILIZATION	1	LUMP	\$ 50,000.00	\$ 50,000.00
7	507	STEEL PILES HP12X53 FURNISHED	150	FOOT	\$ 50.00	\$ 7,500.00
8	507	STEEL PILES HP12X53, DRIVEN	90	FOOT	\$ 25.00	\$ 2,250.00
9	SP 509	EPOXY COATED REINFORCING STEEL, GRADE 60	16,120	POUND	\$ 3.00	\$ 48,360.00
10	SP 511 (QC2)	CLASS QC2 CONCRETE, SUPERSTRUCTURE DECK SLAB	41	CU. YD.	\$ 1,500.00	\$ 61,500.00
11	511	CLASS QC1 CONCRETE, PIER CAP	4	CU. YD.	\$ 1,500.00	\$ 6,000.00
12	511	CLASS QC1 CONCRETE, PIER ABOVE FOOTINGS	7	CU. YD.	\$ 1,500.00	\$ 10,500.00
13	511	CLASS QC1 CONCRETE, ABUTMENT NOT INCLUDING FOOTING	40	CU. YD.	\$ 1,500.00	\$ 60,000.00
14	511	CLASS QC1 CONCRETE, FOOTING	20	CU. YD.	\$ 1,500.00	\$ 30,000.00
15	513	STRUCTURAL STEEL MISC.: PREFABRICATED BRIDGE	1	LUMP	\$ 700,000.00	\$ 700,000.00
16	516	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE)	8	EACH	\$ 1,250.00	\$ 10,000.00
17	518	POROUS BACKFILL WITH GEOTEXTILE FABRIC	30	CU. YD.	\$ 125.00	\$ 3,750.00
18	518	PERFORATED CORRUGATED PLASTIC PIPE	30	FOOT	\$ 10.00	\$ 300.00
19	518	NON-PERFORATED CORRUGATED PLASTIC PIPE	20	FOOT	\$ 20.00	\$ 400.00
20	524	DRILLED SHAFTS, 36" DIAMETER, INTO BEDROCK	12	FOOT	\$ 2,000.00	\$ 24,000.00
21	524	DRILLED SHAFTS, 42" DIAMETER, ABOVE BEDROCK	12	FOOT	\$ 2,000.00	\$ 24,000.00
22	526	REINFORCED CONCRETE APPROACH SLABS	36	SQ. YD.	\$ 350.00	\$ 12,600.00
23	SP 536	CONCRETE WEATHERPROOFING, DECK, ABUTMENT SLABS, AND APPROACH SLABS	291	SQ. YD.	\$ 10.00	\$ 2,910.00
24	SP 536	CONCRETE WEATHERPROOFING, SUBSTRUCTURE	89	SQ. YD.	\$ 15.00	\$ 1,335.00
25	601	CRUSHED AGGREGATE SLOPE PROTECTION	28	SQ. YD.	\$ 100.00	\$ 2,783.78
26	607	FENCE, MISC.: BIKEWAY RAILING	80	FOOT	\$ 250.00	\$ 20,000.00
		TOTAL - STRUCTURES				\$ 1,316,907.66

Ref. No.	Item No.	Item Description	Approx. Quantity	Unit	Unit Cost	Extended Bid Amount
		ROADWAY (Ref. Nos. -)				
0	0		0	0	\$ -	\$ -
0	0		0	0	\$ -	\$ -
0	0		0	0	\$ -	\$ -
0	0		0	0	\$ -	\$ -
0	0		0	0	\$ -	\$ -
0	0		0	0	\$ -	\$ -
0	0		0	0	\$ -	\$ -
0	0		0	0	\$ -	\$ -
0	0		0	0	\$ -	\$ -
0	0		0	0	\$ -	\$ -
0	0		0	0	\$ -	\$ -
0	0		0	0	\$ -	\$ -
0	0		0	0	\$ -	\$ -
0	0		0	0	\$ -	\$ -
0	0		0	0	\$ -	\$ -
0	0		0	0	\$ -	\$ -
0	0		0	0	\$ -	\$ -
0	0		0	0.00	\$ -	\$ -
0	0		0	0.00	\$ -	\$ -
		TOTAL - ROADWAY				\$ -

ENGINEER'S ESTIMATE

SUBTOTAL	\$1,506,907.66
Contingency - 20%	\$301,381.53
Inflation - 15%	\$271,243.38
TOTAL BASE BID (INCLUDES REF. NO. 1 THRU REF. NO.) ----->	\$2,079,532.56

PROJECT NO. 71-22-12 (PROSPECT ROAD WIDENED BRIDGE OVER OTC MAINLINE MP 182.1)

ENGINEER'S ESTIMATE - ALTERNATIVE 3

Ref. No.	Item No.	Item Description	Approx. Quantity	Unit	Unit Cost	Extended Bid Amount
		GENERAL (Ref. Nos. 1-5)				
1	IB.ART.6	PREMIUM FOR CONTRACT PERFORMANCE BOND AND PAYMENT BOND	1	LUMP	\$ 50,000.00	\$ 50,000.00
2	SP 614	MAINTAINING TRAFFIC	1	LUMP	\$ 65,000.00	\$ 65,000.00
3	SP 619	FIELD OFFICE	1	LUMP	\$ 60,000.00	\$ 60,000.00
4	SP 623	CONSTRUCTION LAYOUT SURVEY	1	LUMP	\$ 50,000.00	\$ 50,000.00
5	624	MOBILIZATION	1	LUMP	\$ 100,000.00	\$ 100,000.00
6		ADDITIONAL SURVEY	1	LUMP	\$ 20,000.00	\$ 20,000.00
7		GEOTECHNICAL INVESTIGATIONS	1	LUMP	\$ 50,000.00	\$ 50,000.00
8		ADDITIONAL ENGINEERING COSTS	1	LUMP	\$ 147,000.00	\$ 147,000.00
		TOTAL				\$ 542,000.00

		STRUCTURES (Ref. Nos. 9 - 45)				
9	202	APPROACH SLAB REMOVED	106	SQ. YD.	\$ 60.00	\$ 6,360.00
10	SP 202	PORTIONS OF STRUCTURE REMOVED	1	LUMP	\$ 209,000.00	\$ 209,000.00
11	202	CATCH BASIN REMOVED	2	EACH	\$ 500.00	\$ 1,000.00
12	503	UNCLASSIFIED EXCAVATION	1	LUMP	\$ 11,500.00	\$ 11,500.00
13	505	PILE DRIVING EQUIPMENT MOBILIZATION	1	LUMP	\$ 50,000.00	\$ 50,000.00
14	507	STEEL PILES HP12X53, FURNISHED	170	FOOT	\$ 50.00	\$ 8,500.00
15	507	STEEL PILES HP12X53, DRIVEN	160	FOOT	\$ 25.00	\$ 4,000.00
16	SP 509	EPOXY COATED REINFORCING STEEL, GRADE 60	114,775	POUND	\$ 3.00	\$ 344,325.00
17	SP 511(QC2)	CLASS QC2 CONCRETE, SUPERSTRUCTURE DECK SLAB	262	CU. YD.	\$ 1,300.00	\$ 340,600.00
18	SP 511(QC2)	CLASS QC2 CONCRETE, BARRIERS AND PARAPETS	103	CU. YD.	\$ 1,000.00	\$ 103,000.00
19	SP 511(QC2)	CLASS QC2 CONCRETE, ABUTMENT SLABS	80	CU. YD.	\$ 950.00	\$ 76,000.00
20	511	CLASS QC1 CONCRETE, PIER CAP	11	CU. YD.	\$ 1,250.00	\$ 13,750.00
21	511	CLASS QC1 CONCRETE, PIER ABOVE FOOTINGS	18	CU. YD.	\$ 900.00	\$ 16,200.00
22	511	CLASS QC1 CONCRETE, ABUTMENT NOT INCLUDING FOOTING	59	CU. YD.	\$ 1,250.00	\$ 73,750.00
23	511	CLASS QC1 CONCRETE, FOOTING	10	CU. YD.	\$ 750.00	\$ 7,500.00
24	SP516A	CRACK REPAIR BY EPOXY INJECTION	67	FOOT	\$ 80.00	\$ 5,320.00
25	513	STRUCTURAL STEEL MEMBERS, LEVEL 2	65,932	POUND	\$ 5.00	\$ 329,659.31
26	513	WELDED STUD SHEAR CONNECTORS	3,996	EACH	\$ 5.00	\$ 19,980.00
27	SP 514A	FIELD PAINTING OF NEW AND EXISTING STEEL, INTERMEDIATE COAT, SYSTEM OZEU	3,404	SQ. FT.	\$ 3.00	\$ 10,211.83
28	SP 514A	FIELD PAINTING OF NEW AND EXISTING STEEL, FINISH COAT, SYSTEM OZEU	3,404	SQ. FT.	\$ 3.00	\$ 10,211.83
29	516	ELASTOMERIC BEARING WITH INTERNAL LAMINATES AND LOAD PLATE (NEOPRENE)	8	EACH	\$ 1,250.00	\$ 10,000.00
30	516G	ELASTOMERIC BEARINGS WITH INTERNAL LAMINATES, H-PILE AND LOAD PLATE (NEOPRENE)	16	EACH	\$ 1,250.00	\$ 20,000.00
31	518	POROUS BACKFILL WITH GEOTEXTILE FABRIC	26	CU. YD.	\$ 125.00	\$ 3,250.00
32	518	PERFORATED CORRUGATED PLASTIC PIPE	26	FOOT	\$ 10.00	\$ 260.00
33	518	NON-PERFORATED CORRUGATED PLASTIC PIPE	20	FOOT	\$ 20.00	\$ 400.00
34	SP 519	PATCHING OF CONCRETE STRUCTURES	114	SQ. FT.	\$ 125.00	\$ 14,187.50
35	524	DRILLED SHAFTS, 36" DIAMETER, INTO BEDROCK	36	FOOT	\$ 375.00	\$ 13,500.00
36	524	DRILLED SHAFTS, 42" DIAMETER, ABOVE BEDROCK	38	FOOT	\$ 450.00	\$ 17,100.00
37	526	REINFORCED CONCRETE APPROACH SLABS	149	SQ. YD.	\$ 350.00	\$ 52,150.00
38	SP 527	FALSEWORK, TEMPORARY BRACING AND PROTECTIVE STRUCTURES	1	LUMP	\$ 75,000.00	\$ 75,000.00
39	SP 533	1 1/2" CONTINUOUS STRIP SEAL IN STRUCTURAL STEEL JOINT	90	FOOT	\$ 800.00	\$ 72,000.00
40	SP 536	CONCRETE WEATHERPROOFING, DECK, ABUTMENT SLABS, AND APPROACH SLABS	1,291	SQ. YD.	\$ 10.00	\$ 12,910.00
41	SP 536	CONCRETE WEATHERPROOFING, PARAPETS	599	SQ. YD.	\$ 10.00	\$ 5,990.00
42	SP 536	CONCRETE WEATHERPROOFING, SUBSTRUCTURE	282	SQ. YD.	\$ 15.00	\$ 4,230.00
43	601	CRUSHED AGGREGATE SLOPE PROTECTION	66	SQ. YD.	\$ 100.00	\$ 6,571.89
44	SP 607	TYPE II FENCE, ALL ALUMINUM (6'-0" CHAIN LINK WITH SPECIALS)	661	FOOT	\$ 150.00	\$ 99,150.00
45	611	CATCH BASIN, NO. 3	2	EACH	\$ 2,200.00	\$ 4,400.00
		TOTAL - STRUCTURES				\$ 2,257,164.10

Ref. No.	Item No.	Item Description	Approx. Quantity	Unit	Unit Cost	Extended Bid Amount
		ROADWAY (Ref. Nos. 46 - 60)				
46	201	CLEARING AND GRUBBING	1	LUMP	\$ 25,000.00	\$ 25,000.00
47	202	PAVEMENT REMOVED, ASPHALT	533	SQ. YD.	\$ 10.00	\$ 5,330.00
48	203	EXCAVATION	89	CU. YD.	\$ 20.00	\$ 1,780.00
49	203	EMBANKMENT	44	CU. YD.	\$ 25.00	\$ 1,100.00
50	204	SUBGRADE COMPACTION	533	SQ. YD.	\$ 5.00	\$ 2,665.00
51	254	PAVEMENT PLANING, ASPHALT CONCRETE, 1-1/4"	267	SQ. YD.	\$ 10.00	\$ 2,670.00
52	SP 302	ASPHALT CONCRETE BASE, PG64-22	61	CU. YD.	\$ 200.00	\$ 12,200.00
53	SP 304	AGGREGATE BASE	94	CU. YD.	\$ 70.00	\$ 6,580.00
54	SP 402	ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE 2, PG 64-22	26	CU. YD.	\$ 350.00	\$ 9,100.00
55	SP 404	ASPHALT CONCRETE SURFACE COURSE, TYPE 1, PG 64-22	28	CU. YD.	\$ 200.00	\$ 5,600.00
56	407	NON-TRACKING TACK COAT	101	GALLON	\$ 5.00	\$ 505.00
57	606	GUARDRAIL, TYPE MGS	50	FOOT	\$ 25.00	\$ 1,250.00
58	606	MGS BRIDGE TERMINAL ASSEMBLY, TYPE 1	4	EACH	\$ 2,500.00	\$ 10,000.00
59	642	EDGE LINE, 6", TYPE 1	0.19	MILE	\$ 5,000.00	\$ 946.97
60	642	CENTER LINE, 6", TYPE 1	0.09	MILE	\$ 6,000.00	\$ 568.18
		TOTAL - ROADWAY				\$ 102,354.18

ENGINEER'S ESTIMATE

SUBTOTAL

Contingency - 20%

Inflation - 15%

TOTAL BASE BID (INCLUDES REF. NO. 1 THRU REF. NO. 60) ----->

\$2,901,518.28


\$580,303.66


\$522,273.29

\$4,004,095.23

APPENDIX C:
EXAGGERATED ROADWAY PROFILES EXHIBIT & VERTICAL CLEARANCE

MP 182.1 Overhead Road - Exaggerated Profile





APPROVED



Brian P. Bingham
Brian P. Bingham, PS

APPROVED

PROJECT 71-22-12	PROSPECT ROAD OVER THE OHIO TURNPIKE
	VERTICAL CLEARANCE
DATE: 08/22/23	M.P. 182.1
	SUMMIT COUNTY
OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION	

APPENDIX D:
ASBESTOS CONTAINING MATERIALS BRIDGE SURVEY REPORT

Asbestos Inspection Reporting Form

Date

June 7, 2023

County

Summit

Route

Prospect Road over Mainline I-80

Section

OTIC MP 182.10

PID

OTIC 71-22-12

Requesting ODOT District Office

Ohio Turnpike Infrastructure Commission

Regulating OEPA District Office and Address

Northeast District Office
2110 East Aurora Road
Twinsburg, Ohio 44087

Date of the Asbestos Inspection

April 20, 2023

Name and Address of the company conducting the asbestos inspection

EnviroScience Inc.
5070 Stow Road
Stow, Ohio 44224

Name, signature, and asbestos hazard evaluation number of the person writing the report



Amy Wakefield, AHES
Asbestos Hazard Evaluation Specialist #ES543881

Description sampling locations and how each location was determined (use additional pages if needed)

Project Background

EnviroScience, Inc. was contracted by American Structure Point to provide an asbestos survey of the MP 182.10 OTIC Prospect Rd. bridge over the I-80 Mainline in Summit County. The location coordinates of the structure are 41.255036°, - 81.461364°.

The deck will be replaced on the 223-foot-long four-span continuous steel girder bridge structure. The bridge inventory report information indicates the structure to have been originally built in 1954 with a major reconstruction done in 1993.

Asbestos Survey Summary

Bridge Plan Review – EnviroScience performed a limited review of available existing bridge construction plans that were provided by American Structure Point. The original construction plans from 1953 did not contain anything of note. The 1992 rehabilitation plans also did not have anything to note. There was no mention of expansion joint or caulking material to be used. No evidence of affixed utility conduits or duct work was found in any of the existing plans.

In summary, based on our review of portions of the MP182.10 original and rehabilitation plans, no conclusive evidence of suspect asbestos containing materials was noted. The plans reviewed are on file at EnviroScience and can be provided if requested.

Asbestos Survey - An asbestos survey of the subject bridge structure was conducted on 04/20/2023 by Amy Wakefield, Certified Asbestos Hazard Evaluation Specialist #ES543881.

All accessible portions of the MP 182.10 OTIC Prospect Road bridge over the I-80 Mainline were field investigated for the presence of suspected ACMs. A visual inspection of the top and bottom sides of the structure including the deck, outside parapet railing walls, steel beams, and abutments were conducted. No active or abandoned utilities were affixed to the structure. Saw cuts in the parapet railing walls contained caulking material that were sampled. The vandal fence base plates contained caulking material however, due to limited quantities only one sample was collected. Sample locations were determined by the ability to access the material safely, being suspect material and to amply characterize the entire structure.

The following table summarizes the samples that were collected:

Table 1 – Sample Summary – MP 182.10 Prospect Road Bridge SFN 7729820				
Sample	Homogeneous Area	Category	Location of Sample	Positive for Asbestos?
PC01	Parapet Wall Caulk	Misc.	Westside, eastbound	No
PC02	Parapet Wall Caulk	Misc.	Westside, eastbound	No
PC03	Parapet Wall Caulk	Misc.	Eastside, eastbound	No
VFC01	Vandal Fence Caulk	Misc.	Eastside, westbound	No

Appendix B includes sampling documentation including a Sample Location Map, sampling log, and laboratory analysis report and chain of custody. A photo log is provided in Appendix C.

Conclusion and Recommendations

Lab analysis of bulk samples taken from the MP 182.10 Prospect Road Bridge over the I-80 Mainline indicate that no asbestos containing material was identified.

If suspect ACMs are revealed during demolition or renovation activities that were not identified during this survey it is recommended that work activities cease until a Certified Asbestos Hazard Evaluation Specialist can evaluate the new material(s). Any removal and subsequent disposal of the asbestos containing material during demolition operations must comply with the Ohio Administrative code, the occupational Safety and Health Administration (OSHA) regulations and the National Emission Standard for Hazardous Air Pollutants (NESHAP). Reference the Ohio Environmental Protection Agency adopted chapters 3745-20-03 & 3745-20-04 of the Ohio Administrative Code. This implements the NESHAP standards for asbestos and its removal.

Notification


An OEPA Notification of Demolition and Renovation form must be submitted ten (10) working days prior to work activities. Appendix D contains the OEPA form of which Section 1 - General Information 1, 2, 3, 4, and 5; and Section 2 - Project Address Specific Information A, B, and C have been completed.

Once the Contractor has been selected for the project, the remaining sections of the form shall be completed (as applicable) and the notification form submitted with the proper remittance to the following address at least 10 working days prior to starting work:

Ohio EPA, DAPC Asbestos
P.O. Box 1049
Columbus, Ohio 43216-1049

The form may also be completed/submitted via on-line at <https://epa.ohio.gov/dapc/atu/asbestos>

Name, signature, and asbestos hazard evaluation number of each person who selected samples from the structure (use additional pages if needed)

Name	Signature	Asbestos Evaluation #
Amy Wakefield		ES543881

SUPPORTING INFORMATION

Laboratory Analytical Report

Blueprint, diagram or written description with the following:

- Type, location and amount of confirmed regulated asbestos containing material
- Location and collection date of each bulk sample
- Location and amounts of suspected asbestos containing material, both friable and non-friable

NOTE: The OEPA Notification of Demolition and Renovation Form with the appropriate Sections I, II, III, IV, VI and VII must be completed by the licensed asbestos hazard evaluation specialist and included with the report submission to ODOT prior to submission to OEPA or the local air authority with jurisdiction.

OEPA Notification of Demolition and Renovation Form

Work on projects cannot begin until 10 working days after a COMPLETE original notification form, including payment, is submitted to Ohio EPA. Instructions and a worksheet for fee calculation are available at epa.ohio.gov/asbestos. This form can be completed, and payment made, at ebiz.epa.ohio.gov. Questions? asbestos@epa.ohio.gov or (614) 466-0061.

Date: 4/29/2023 ES Project #17432 Path: C:\Users\AnnaPiazza\OneDrive - EnviroScience, Inc\Desktop\OTIC 71-22-12 Bridges, Hudson\17432_OTIC_Asbestos.aprx






Figure 1.
Location of Site on Highway
Map of Summit County, Ohio.
Prospect Road Bridge
(MP182.10).

 Project Area

0 200 400 800 1,200 Feet

0 100 200 400 Meters


EnviroScience™
Excellence In Any Environment

OTIC MP 182.10, Prospect Rd. over Mainline

41.255036°, -81.461364°



OTIC MP 182.10, Prospect Rd.
over Mainline



Chain of Custody

Contact Information

Client Company: EnviroScience Inc
Office Address: 5070 Stans Rd
City, State, Zip: Stam OH 44224
Fax Number: _____
Email Address: awakefield@enviroscienceinc.com

Project Number: 17431
Project Name: OTIC 3 Bridges Hudson
Primary Contact: Amy Wakefield
Office Phone: 330 688 4100
Cell Phone: 440 225 1909

Matrix:

Air ☐
Water ☐

Soil ☐
Paint ☐

Bulk ☒
Surface Dust / Wipe ☐

Other ☐ _____

Analysis Method:

☐ PCM: NIOSH 7400
☐ PCM: OSHA
☐ PCM: TWA

☐ Total Dust: NIOSH 0500
☐ Total Dust: NIOSH 0600

☐ AAS: Lead in Air
☐ AAS: Lead in Water
☐ AAS: Lead in Paint
☐ AAS: Lead Dust/Wipe₁
☐ AAS: Lead in Soil
☐ AAS: TCLP
☐ AAS: Metals [Cd, Zn, Cr-circle]

PLM Use Bulk Asbestos Sample Log

☒ PLM: Bulk Asbestos EPA 600
☐ PLM: Point Counting 198.1
☐ PLM: NOB via 198.6 (PLM only)
☐ If <1% by PLM, to TEM via 198.4₂

IAQ Use Mold Sample Log

☐ IAQ: I Bioaersol Fungal Spore Trap₃
☐ IAQ: II Bioaersol Fungal Spore
☐ IAQ: Tape, Bulk, Misc. Qualitative₃
☐ IAQ: Tape, Bulk, Misc. Quantitative₃
☐ IAQ: Other Culturable ID₂

☐ TEM: AHERA
☐ TEM: NIOSH 7402
☐ TEM: ISO 10312
☐ TEM: ISO 13794
☐ TEM: Wipe ASTM 6480
☐ TEM: Microvac ASTM D5755
☐ TEM: Microvac ASTM D5756
☐ TEM: NOB 198.4
☐ TEM: Bulk Analysis
☐ TEM: Potable Water
☐ TEM: Non-Potable Water
☐ TEM: Other _____
☐ Soil: Call for Available Methods

1- Requires ASTM acceptable material 2- Call to confirm TAT 3- Non-culturable 4- With Non-fungal Microscopic Exam

Special Instructions:

PLM: EPA 600 R-93/116, 1993

Turnaround Time

Preliminary Results Requested Date: May 1, 2023
Specific date / time

☐ Verbal ☒ Email ☐ Fax

☐ 10 Day ☒ 5 Day ☐ 3 Day ☐ 2 Day ☐ 1 Day* ☐ 12 Hour** ☐ 6 Hour** ☐ RUSH**

* End of next business day unless otherwise specified. ** Matrix Dependent. ***Please notify the lab before shipping***

Shipping Method

☒ FedEx

☐ UPS

☐ USPS

☐ Other _____

Chain of Custody

Relinquished (Name/Organization): Amy Wakefield EnviroScience
Received (Name / iATL): _____
Sample Login (Name / iATL): _____
Analyst (Name(s) / iATL): Chris [Signature]
QA/QC Review (Name / iATL): _____
Archived / Released: _____ QA/QC InterLAB Use: _____

Date: 4/20/23

Date: _____

Date: 5/11/23

Date: _____

Date: _____

Date: _____

Time: 1630

Time: _____

Time: 6

Time: _____

Time: APR 24 2023

Time: _____

CERTIFICATE OF ANALYSIS

Client: EnviroScience, Inc.
5070 Stow Road
Stow OH 44224

Client: ENV507

Report Date: 5/1/2023
Report No.: 682295 - PLM
Project: OTIC 3 Bridges Hudson; Prospect Rd Bridge
Project No.: 17431

PLM BULK SAMPLE ANALYSIS SUMMARY

Lab No.: 7606326
Client No.: VPC-01

Analyst Observation: Clear Caulk
Client Description: Composite Vandal Fence Caulk

Location:
Facility:

Percent Asbestos:
None Detected

Percent Non-Asbestos Fibrous Material:
None Detected

Percent Non-Fibrous Material:
100

Lab No.: 7606327
Client No.: PC-01

Analyst Observation: Grey Caulk
Client Description: Parapet Wall Caulk

Location: West Side
Facility:

Percent Asbestos:
None Detected

Percent Non-Asbestos Fibrous Material:
None Detected

Percent Non-Fibrous Material:
100

Lab No.: 7606328
Client No.: PC-02

Analyst Observation: Grey Caulk
Client Description: Parapet Wall Caulk

Location: West Side
Facility:

Percent Asbestos:
None Detected

Percent Non-Asbestos Fibrous Material:
None Detected

Percent Non-Fibrous Material:
100

Lab No.: 7606329
Client No.: PC-03

Analyst Observation: Grey Caulk
Client Description: Parapet Wall Caulk

Location: East Side
Facility:

Percent Asbestos:
None Detected

Percent Non-Asbestos Fibrous Material:
None Detected

Percent Non-Fibrous Material:
100

Please refer to the Appendix of this report for further information regarding your analysis.


Date Received: 4/24/2023

Date Analyzed: 05/01/2023

Signature:

Analyst: Christopher Riffe

Approved By:



Frank E. Ehrenfeld, III
Laboratory Director

CERTIFICATE OF ANALYSIS

Client: EnviroScience, Inc.
5070 Stow Road
Stow OH 44224

Report Date: 5/1/2023
Report No.: 682295 - PLM
Project: OTIC 3 Bridges Hudson; Prospect Rd
Bridge
Project No.: 17431

Client: ENV507

Appendix to Analytical Report

Customer Contact: Chuck Kessler

Method: 40 CFR Appendix E to Subpart E of Part 763, interim method for the Determination of Asbestos in Bulk Insulation Samples, USEPA 600, R93-116 and NYSDOH ELAP 198.1 as needed.

This appendix seeks to promote greater understanding of any observations, exceptions, special instructions, or circumstances that the laboratory needs to communicate to the client concerning the above samples. The information below is used to help promote your ability to make the most informed decisions for you and your customers. Please note the following points of contact for any questions you may have.

iATL Customer Service: customerservice@iatl.com

iATL Office Manager: wchampion@iatl.com

iATL Account Representative: House Account

Sample Login Notes: See Batch Sheet Attached

Sample Matrix: Bulk Building Materials

Exceptions Noted: See Following Pages

General Terms, Warrants, Limits, Qualifiers:

General information about iATL capabilities and client/laboratory relationships and responsibilities are spelled out in iATL policies that are listed at www.iATL.com and in our Quality Assurance Manual per ISO 17025 standard requirements. The information therein is a representation of iATL definitions and policies for turnaround times, sample submittal, collection media, blank definitions, quantification issues and limit of detection, analytical methods and procedures, sub-contracting policies, results reporting options, fees, terms, and discounts, confidentiality, sample archival and disposal, and data interpretation.

iATL warrants the test results to be of a precision normal for the type and methodology employed for each sample submitted. iATL disclaims any other warrants, expressed or implied, including warranty of fitness for a particular purpose and warranty of merchantability. iATL accepts no legal responsibility for the purpose for which the client uses test results. Any analytical work performed must be governed by our Standard Terms and Conditions. Prices, methods and detection limits may be changed without notification. Please contact your Customer Service Representative for the most current information.

This confidential report relates only to those item(s) tested and does not represent an endorsement by NIST-NVLAP, AIHA LAP LLC, or any agency of local, state or province governments nor of any agency of the U.S. government.

This report shall not be reproduced except in full, without written approval of the laboratory.

Information Pertinent to this Report:

Analysis by US EPA 600 93-116: Determination of Asbestos in Bulk Building Materials by Polarized Light Microscopy (PLM).

Certifications:

- NIST-NVLAP No. 101165-0
- NYSDOH-ELAP No. 11021
- AIHA-LAP, LLC No. 100188

Quantification at <0.25% by volume is possible with this method. (PC) Indicates Stratified Point Count Method performed. (PC-Trace) means that asbestos was detected but is not quantifiable under the Point Counting regimen. PC Trace represents a <0.25% amount. Analysis includes all distinct separable layers in accordance with EPA 600 Method. If not reported or otherwise noted, layer is either not present or the client has specifically requested that it not be analyzed (ex. analyze until positive instructions). Small asbestos fibers may be missed by PLM due to resolution limitations of the optical microscope. Therefore, PLM is not consistently reliable in detecting asbestos in non-friable organically bound (NOB) materials. Quantitative transmission electron microscopy (TEM) is currently the only method that can pronounce materials as non-asbestos containing.

Analytical Methodology Alternatives: Your initial request for analysis may not have accounted for recent advances in regulatory requirements or advances in technology that are routinely used in similar situations for other qualified projects. You may have the option to explore additional analysis for further information. Below are a few options, listed as the matrix followed by the appropriate methodology. Also included are links to more information on our website.

Bulk Building Materials that are Non-Friable Organically Bound (NOB) by Gravimetric Reduction techniques employing PLM and TEM: ELAP 198.6 (PLM-NOB), ELAP 198.4 (TEM-NOB) See additional information at the end of this appendix.

CERTIFICATE OF ANALYSIS

Client: EnviroScience, Inc.
5070 Stow Road
Stow OH 44224

Report Date: 5/1/2023
Report No.: 682295 - PLM
Project: OTIC 3 Bridges Hudson; Prospect Rd
Bridge
Project No.: 17431

Client: ENV507

Loose Fill Vermiculite Insulation, Attic Insulation, Zonolite (copyright), etc.: US EPA 600 R-4/004 (multi-tiered analytical process)
Sprayed On Insulation/Fireproofing with Vermiculite (SOF-V): ELAP 198.8 (PLM-SOF-V)

Soil, sludge, sediment, aggregate, and like materials analyzed for asbestos or other elongated mineral particles (ex. erionite, etc.): ASTM D7521, CARB 435, and other options available

Asbestos in Surface Dust according to one of ASTM's Methods (very dependent on sampling collection technique – by TEM): ASTM D 5755, D5756, or D6480

Various other asbestos matrices (air, water, etc.) and analytical methods are available.

Disclaimers / Qualifiers:

There may be some samples in this project that have a "NOTE:" associated with a sample result. We use added disclaimers or qualifiers to inform the client about something that requires further explanation. Here is a list with highlighted disclaimers that may be pertinent to this project. For a full explanation of these and other disclaimers, please inquire at **customerservice@iatl.com**.

- 1) Note: No mastic provided for analysis.
- 2) Note: Insufficient mastic provided for analysis.
- 3) Note: Insufficient material provided for analysis.
- 4) Note: Insufficient sample provided for QC reanalysis.
- 5) Note: Different material than indicated on Sample Log / Description.
- 6) Note: Sample not submitted.
- 7) Note: Attached to asbestos containing material.
- 8) Note: Received wet.
- 9) Note: Possible surface contamination.
- 10) Note: Not building material. 1% threshold may not apply.
- 11) Note: Recommend TEM-NOB analysis as per EPA recommendations.
- 12) Note: Asbestos detected but not quantifiable.
- 13) Note: Multiple identical samples submitted, only one analyzed.
- 14) Note: Analyzed by EPA 600/R-93/116. Point Counting detection limit at 0.080%.
- 15) Note: Analyzed by EPA 600/R-93/116. Point Counting detection limit at 0.125%.
- 16) Note: This sample contains >10% vermiculite mineral. See Appendix for Recommendations for Vermiculite Analysis.

Recommendations for Vermiculite Analysis:

Several analytical protocols exist for the analysis of asbestos in vermiculite. These analytical approaches vary depending upon the nature of the vermiculite mineral being tested (e.g. un-processed gänge, homogeneous exfoliated books of mica, or mixed mineral composites). Please contact your client representative for pricing and turnaround time options available.

iATL recommends initial testing using the EPA 600/R-93/116 method. This method is specifically designed for the analysis of asbestos in bulk building materials. It provides an acceptable starting point for primary screening of vermiculite for possible asbestos.

Results from this testing may be inconclusive. EPA suggests proceeding to a multi-tiered analysis involving wet separation techniques in conjunction with PLM and TEM gravimetric analysis (EPA 600/R-04/004).

For New York State customers, NYSDOH requires disclaimers and qualifiers for various vermiculite containing samples that direct analysis via ELAP198.6 and ELAP198.8 for samples that contain >10% vermiculite mineral where ELAP198.6 may be used to evaluate the asbestos content of the material. However, any test result using ELAP198.6 will be reported with the following disclaimer: "ELAP198.6 method does not remove vermiculite and may underestimate the level of asbestos present in a sample containing >10% vermiculite."

Further information on this method and other vermiculite and asbestos issues can be found at the following: Agency for Toxic Substances and Disease Registry (ATSDR) www.atsdr.cdc.gov, United States Geological Survey (USGS) www.minerals.usgs.gov/minerals/, US EPA www.epa.gov/asbestos. The USEPA also has an informative brochure "Current Best Practices for Vermiculite Attic Insulation" EPA 747F03001 May 2003, that may assist the health and remediation professional. NYS customers please follow current NYSDOH ELAP requirements per policy on subject of surfacing and vermiculite, May 6, 2016, Testing Requirements for Surfacing Material Containing Vermiculite (https://www.wadsworth.org/sites/default/files/WebDoc/I198_8_02_2.pdf)

The following is a summary of the analytical process outlines in the EPA 600/R-04/004 Method:

- 1) **Analytical Step/Method:** Initial Screening by PLM, EPA 600R-93/116
Requirements/Comments: Minimum of 0.1 g of sample. ~0.25% for most samples.

CERTIFICATE OF ANALYSIS

Client: EnviroScience, Inc.
5070 Stow Road
Stow OH 44224

Report Date: 5/1/2023
Report No.: 682295 - PLM
Project: OTIC 3 Bridges Hudson; Prospect Rd
Bridge
Project No.: 17431

Client: ENV507

2)**Analytical Step/Method:** Wet Separation by PLM Gravimetric Technique, EPA R-04/004

Requirements/Comments: Minimum 50g** of dry sample. Analysis of "Sinks" only.

3)**Analytical Step/Method:** Wet Separation by PLM Gravimetric Technique, EPA R-04/004

Requirements/Comments: Minimum 50g** of dry sample. Analysis of "Floats" only.

4)**Analytical Step/Method:** Wet Separation by TEM Gravimetric Technique, EPA R-04/004

Requirements/Comments: Minimum 50g** of dry sample. Analysis of "Sinks" only.

5)**Analytical Step/Method:** Wet Separation by TEM Gravimetric Technique, EPA R-04/004

Requirements/Comments: Minimum 50g** of dry sample. Analysis of "Suspension" only.

*With advance notice and confirmation by the laboratory.

**Approximately 1 Liter of sample in double-bagged container (~9x6 inch bag of sample).

New York State Department of Health requires that samples originating from NYS that they categorize as Non-friable Organically Bound materials can only be confirmed as None Detected for asbestos by method 198.4. See the table below for a list of those materials. (ENVIRONMENTAL LABORATORY APPROVAL PROGRAM CERTIFICATION MANUAL - ITEM No. 198.1, Revision Date 5/6/16)

*Asphalt Shingles, Caulking, Ceiling Tiles with Cellulose, Duct Wrap, Glazing, Mastic, Paint Chips, Resilient Floor Tiles, Rubberized Asbestos Gaskets, Siding Shingles, Vinyl Asbestos Tile, NOB materials (other than SM-V) with <10% vermiculite, Any material (Friable or NOB other than SM-V) with >10% vermiculite.

Statistically derived uncertainty with any measure should be taken into consideration when reviewing and interpreting all reported data and results. A more comprehensive listing of accuracy, precision, and uncertainty as it impacts this method is available upon request.



PHOTO 1
View of Prospect Road (MP
182.10).



PHOTO 2
View of structure underside. No
utilities were affixed.



PHOTO 3
View of steel bearing. No
gasketing material observed.



PHOTO 4
View of typical joint on parapet wall. Samples taken of caulk material.



PHOTO 5
View of outer beam. Paint in good condition.



PHOTO 6
View of the vandal fence base plate. Samples taken of caulk material.



Notification of Demolition and Renovation/Abatement

Section 1: General Information

Division of Air Pollution Control

Work on projects cannot begin until 10 working days after a COMPLETE original notification form, **including payment**, is submitted to Ohio EPA. Instructions and a worksheet for fee calculation are available at epa.ohio.gov/asbestos. This form can be completed, and payment made, at ebiz.epa.ohio.gov. Questions? asbestos@epa.ohio.gov or (614) 466-0061.

Ohio EPA Use Only	Notification #:	Postmarked: / /	Received: / /	<input type="checkbox"/> Hand-Delivered
-------------------	-----------------	-----------------	---------------	---

1) Notification Information (Check all that apply)

<input checked="" type="checkbox"/> Original	<input type="checkbox"/> Revision # (count):	<input type="checkbox"/> Installation	<input type="checkbox"/> Emergency	<input type="checkbox"/> Annual	<input type="checkbox"/> Cancellation	Project County: Summit
--	--	---------------------------------------	------------------------------------	---------------------------------	---------------------------------------	------------------------

2) Owner, Asbestos Abatement Contractor, Billing and Fire Department Information

Revised? ☐

Owner			
Name: Ohio Turnpike and Infrastructure Commission			Is this a company? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Address: 682 Prospect Street		Contact Person: Chris Matta, PE	
City: Berea	State: OH	Zip: 44017 -	
Email: Chris.Matta@ohioturnpike.org	Phone: (440) 234 - 2081	Fax: () -	
Asbestos Abatement Contractor (if applicable)			
Name:		License #: AC	Expiration Date: / /
Address:		Contact Person:	
City:	State:	Zip: -	
Email:	Phone: () -	Fax: () -	
Billing Contact			
Is this contact associated with the <input checked="" type="checkbox"/> Owner, <input type="checkbox"/> Asbestos Abatement Contractor, or <input type="checkbox"/> Demolition Contractor (if not installation)?			
Address: 682 Prospect Street		Contact Person: Chris Matta, PE	
City: Berea	State: OH	Zip: 44017 -	
Email: Chris.Matta@ohioturnpike.org	Phone: (330) 234 - 2081	Fax: () -	
Fire Department (if applicable)			
Name:			
Address:		Contact Person:	
City:	State:	Zip: -	
Email:	Phone: () -	Fax: () -	

3) Ohio Asbestos Hazard Evaluation Specialist and Evaluation Procedure

Revised? ☐

Evaluation Specialist: Amy Wakefield	Certification #: ES 543881	Expiration Date: 05 / 26 / 2024
Procedure, including analytical methods, employed to detect the presence of and to estimate the quantity of regulated asbestos-containing material (RACM) and Category I and Category II non-friable asbestos-containing material: <input checked="" type="checkbox"/> PLM <input type="checkbox"/> Point Count <input type="checkbox"/> TEM <input type="checkbox"/> Other Method (Explain Below):		
Bulk Sampling w/point count of samples that are less than 10% asbestos containing		

4) Procedures to be followed should unexpected RACM be discovered (check all that apply)

Revised? ☐

<input checked="" type="checkbox"/> Stop work and keep wet	<input type="checkbox"/> Evacuate area	<input type="checkbox"/> Demarcate area	<input type="checkbox"/> Contact licensed abatement contractor
<input type="checkbox"/> Contact district office/local air authority			
<input checked="" type="checkbox"/> Other (Explain): Notify Ohio Turnpike and Infrastructure Commission and the Project Superintendent			

5) Planned Demolition (check all that apply)

Revised? ☐

Describe demolition work to be performed and method(s) to be employed, including demolition techniques to be used:					
<input type="checkbox"/> Implosion	<input type="checkbox"/> Fire Training	<input type="checkbox"/> Wet Methods	<input checked="" type="checkbox"/> Manual Demolition	<input checked="" type="checkbox"/> Mechanical Demolition	<input type="checkbox"/> Other (Explain):
Existing structure will be removed by industry standard means and methods					

Mail completed form and payment to:
Ohio EPA, DAPC – Asbestos
P.O. Box 1049, Columbus, OH 43216-1049

Notification of Demolition and Renovation/Abatement

Section 1: General Information

Continued

Description of affected facility components (include attachment if necessary):

(Revised 02/18)

Page 1 of 3

6) Asbestos Description and Engineering Controls (if asbestos is being abated)

Revised? ☐

For the material listed in each project, describe the type(s) of ACM to be abated, engineering controls and work practices to be used to minimize emissions and ensure proper waste handling:

Type of ACM to be abated:	<input type="checkbox"/> Surfacing	<input type="checkbox"/> Mechanical	<input type="checkbox"/> Other		
Engineering Controls:	<input type="checkbox"/> Wet Methods	<input type="checkbox"/> Glove Bag	<input type="checkbox"/> NPE	<input type="checkbox"/> AFD	<input type="checkbox"/> Other:
Work Practices:	<input type="checkbox"/> Intact Removal	<input type="checkbox"/> Manual	<input type="checkbox"/> Mechanical	<input type="checkbox"/> Other:	

7) Asbestos Waste Transporter (if applicable)

Revised? ☐

Transporter #1 Name:		
Address:		Contact Person:
City:	State:	Zip: -
Email:	Phone: () -	Fax: () -
Transporter #2 Name (if applicable):		
Address:		Contact Person:
City:	State:	Zip: -
Email:	Phone: () -	Fax: () -

8) Asbestos Waste Disposal Site (if applicable)

Revised? ☐

Name:		
Address:		Contact Person:
City:	State:	Zip: -
Email:	Phone: () -	Fax: () -

9) Emergency Demolition (complete if you checked "Emergency" above and "Demolition" for any project)

Revised? ☐

A copy of the issued order, including the following information, **must be attached** to this notification.

Government Official Issuing Order:	Title:
Agency:	Authority of Order (Citation of Code):
Date of Order: / /	Demolition Date: / /

10) Emergency Renovation/Abatement (complete if you checked "Emergency" above and "Renovation/Abatement" for any project)

Revised? ☐

Date of Emergency: / /	Time of Emergency: : <input type="checkbox"/> a.m. <input type="checkbox"/> p.m.
Description of Sudden, Unexpected Event:	
Explanation of how the event caused unsafe conditions or equipment damage:	

11) Attestation

Revised? ☐

In accordance with Ohio Administrative Code rule 3745-20-03(A)(4)(p), I certify that at least one person trained as required by paragraph (B) of rule 3745-20-04 of the Administrative Code will supervise the stripping and removal described by this notification. I acknowledge that the submission of false or misleading statements is prohibited by law and I certify that facts contained in this notification are true, accurate, and complete.

Signature:	Date: / /
Name: Chris Matta, PE	Title: Chief Engineer
Organization: Ohio Turnpike and Infrastructure Commission	



Notification of Demolition and Renovation/Abatement

Section 2: Project Address Specific Information

Division of Air Pollution Control

Please complete Section 2 for the address included with this notification. If the project is an "Installation" per OAC 3745-20, complete a separate Section 2 page for each address associated with this notification.

Ohio EPA Use Only

Project ID #:

A. Facility Description

Revised? ☐

Building Name (if applicable): MP 182.10 Prospect Road Bridge		Site Location (specific): MP 182.10 Prospect Road Bridge over Mainline I-80 SFN 7729820	
Address: 1.8 miles east of Exit 12, Coordinates: 41.255036°, - 81.46136			
City: Hudson		State: OH	Zip: 44236 -
Building Size (square feet):		No. of Floors:	Age: 70
Present Use: Highway Bridge		Prior Use: Highway Bridge	

B. Type of Operation (check all that apply)

Revised? ☐

<input checked="" type="checkbox"/> Demolition	<input type="checkbox"/> Renovation/Abatement – Type: <input type="checkbox"/> Removal <input type="checkbox"/> Repair <input type="checkbox"/> Encapsulation <input type="checkbox"/> Enclosure
--	--

C. Asbestos Present (check one)

Revised? ☐

<input type="checkbox"/> Yes	<input checked="" type="checkbox"/> No	<input type="checkbox"/> No, previously abated	Year Abated:
------------------------------	--	--	--------------

D. Approximate Amount of Asbestos-Containing Materials (complete table below and Section 1 #6 if asbestos is present)

Revised? ☐

	Material to be Removed			Material NOT to be Removed	
	RACM	Non-friable Asbestos-Containing Material		Non-friable Asbestos-Containing Material	
		Category I	Category II	Category I	Category II
Pipes (linear feet)					
Surface area on other facility components (ft ²)					
Volume if length or area cannot be measured (ft ³)					

E. Asbestos Abatement Schedule and Abatement Specialist (original notification is required 10 working days prior to the start of work)

Revised? ☐

Setup Date: / /			Abatement Date: / /			Complete Date: / /	
(Shift 1) Time start/end on site	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday	Sunday
Abatement Specialist Name:			Certification #: AS			Expiration Date: / /	
(Shift 1) Time start/end on site	Monday	Tuesday	Wednesday	Thursday	Friday	Saturday	Sunday
Abatement Specialist Name:			Certification #: AS			Expiration Date: / /	

F. Demolition Contractor (if applicable)

Revised? ☐

Name:		
Address:		Contact Person:
City:	State:	Zip: -
Email:	Phone: () -	Fax: () -

G. Demolition Schedule (original notification is required 10 working days prior to the start of work)

Revised? ☐

Start Date: / /	Complete Date: / /
-----------------	--------------------

H. Project Hold

Revised? ☐

Hold Begin Date: / /	Work Resume Date: / /
----------------------	-----------------------

APPENDIX E:
EXISTING AND PROPOSED TRANSVERSE SECTIONS

DESIGNER _____ DATE: _____


DRAWN _____ DATE: _____

CHECKED: _____ DATE: _____


BACKCHECKED: _____ DATE: _____

APPROVED: _____ DATE: _____

7729820_ST001.dwg, 8/16/23 - 2:14pm



PROPOSED TRANSVERSE SECTION



EXISTING TRANSVERSE SECTION

PROJECT 71-22-12
DATE: 05/18/2023

TRANSVERSE SECTIONS
PROSPECT OVER THE OHIO TURNPIKE
SANDUSKY COUNTY
M.P. 182.1

DESIGNED
IMF
DRAWN
JFK

CHECKED
DEB
IN CHARGE
DEB

REVISIONS

BY
DATE

DESIGN AGENCY
COMPASS
INFRASTRUCTURE GROUP

OHIO
TURNPIKE

OHIO
TURNPIKE

OHIO
TURNPIKE AND INFRASTRUCTURE COMMISSION

DESIGNER _____ DATE: _____ CHECKED: _____ DATE: _____ CORRECTED: _____ DATE: _____
 DRAWN _____ DATE: _____ BACKCHECKED: _____ DATE: _____ APPROVED: _____ DATE: _____

O




dwg;


OHIO TURNPIKE COMMISSION

APPENDIX F:
BIKEWAY ALTERNATIVES SKETCHES


7729820_AR001.dwg; 8/17/23 - 6:32am



PLAN
REAR ABUTMENT




ELEVATION
REAR ABUTMENT



SECTION
REAR ABUTMENT



- DENOTES AREAS TO BE REPAIRED AS PER ITEM SP 519



- REMOVAL PER SP 202, SEE SHEET X OF X.

XX
XX

PROJECT 71-22-12

DATE: 8/17/23

ABUTMENT REMOVAL

PROSPECT OVER THE OHIO TURNPIKE

M.P. 182.1

SUMMIT COUNTY

REVISIONS

NO.

CHECKED

DESIGNED

JGM

DRAWN

JGM

IMF

IN CHARGE

DEB




BY

DATE

DESIGN AGENCY



OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION



PROJECT 71-22-12
DATE: 8/17/23

ABUTMENT WIDENING ALTERNATE
PROSPECT OVER THE OHIO TURNPIKE
M.P. 182.1

SUMMIT COUNTY

DESIGNED
JGM
DRAWN
JGM

CHECKED
IMF
IN CHARGE
DEB




NO.

REVISIONS

BY DATE



OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION



PROJECT 71-22-12
DATE: 8/17/23

PARALLEL BRIDGE ALTERNATE ABUTMENT
PROSPECT OVER THE OHIO TURNPIKE
SUMMIT COUNTY
M.P. 182.1

DESIGNED
JGM
DRAWN
JGM

CHECKED
IMF
IN CHARGE


NO.

REVISIONS

BY DATE



OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION



ELEVATION

PIER 1 SHOWN, PIER 2
AND PIER 3 SIMILAR





PROJECT 71-22-12
DATE: 8/17/23

PIER WIDENING DETAILS
PROSPECT OVER THE OHIO TURNPIKE
M.P. 182.1
SUMMIT COUNTY

DESIGNED	CHECKED	NO.	REVISIONS	BY	DATE
JGM	IMF	-	-	-	-
DRAWN	IN CHARGE	-	-	-	-
JGM	DEB	-	-	-	-





DESIGN AGENCY

COMPASS
INFRASTRUCTURE GROUP

BY DATE

REVISIONS

NO

CHECKED

DESIGNED

JGM

JGM

JGM

JGM

JGM

JGM

JGM

JGM

JGM

JGM

JGM

PARALLEL BRIDGE PIER
PROSPECT OVER THE OHIO TURNPIKE


SUMMIT COUNTY

M.P. 182.1


PROJECT 71-22-12
DATE: 8/17/23

OHIO TURNPIKE AND INFRASTRUCTURE COMMISSION

7729820_SV001.dwg; 8/18/23 - 3:22pm



PLAN
REAR ABUTMENT



ELEVATION
REAR ABUTMENT

SP 519 REPAIR AREAS		
MEASURED QUANTITY (SQ. FT.)	CONTINGENT QUANTITY (SQ. FT.)	TOTAL (SQ. FT.)
0	10	10
SP 516A AREAS		
MEASURED QUANTITY (FT.)	CONTINGENT QUANTITY (FT.)	TOTAL (FT.)
3.5	10	13.5


NOTES:

- THE AREAS OF REPAIR SHOWN ARE APPROXIMATE AND ARE BASED ON A FIELD INSPECTION. FINAL DETERMINATION OF THE AREAS TO BE REPAIRED WILL BE MADE BY THE ENGINEER AT THE TIME OF CONSTRUCTION.
- THE TOTAL CONCRETE PATCHING AND CRACK REPAIR AREAS INDICATED ON THE DETAILS HAVE BEEN INCREASED TO ACCOUNT FOR ANY FURTHER DETERIORATION THAT MAY HAVE OCCURRED SINCE THE FIELD INSPECTION.

LEGEND:



- DENOTES AREAS TO BE REPAIRED AS PER ITEM SP 519



- REMOVAL PER SP 202, SEE SHEET X OF X.

PROJECT 71-22-12
DATE: 8/17/23

XX
XX

PATCHING AND PARTIAL REMOVAL DETAILS (1 OF 5)
PROSPECT OVER THE OHIO TURNPIKE
M.P. 182.1

DESIGNED
JFK

CHECKED
IMF

NO.


REVISIONS

BY


DATE

DESIGN AGENCY
COMPASS
INFRASTRUCTURE GROUP

7729820_SV002.dwg; 8/18/23 - 3:37pm



PLAN
FORWARD ABUTMENT





ELEVATION
FORWARD ABUTMENT

SP 519 REPAIR AREAS		
MEASURED QUANTITY (SQ. FT.)	CONTINGENT QUANTITY (SQ. FT.)	TOTAL (SQ. FT.)
0	10	10
SP 516A AREAS		
MEASURED QUANTITY (FT.)	CONTINGENT QUANTITY (FT.)	TOTAL (FT.)
8	10	18

NOTES:

- THE AREAS OF REPAIR SHOWN ARE APPROXIMATE AND ARE BASED ON A FIELD INSPECTION. FINAL DETERMINATION OF THE AREAS TO BE REPAIRED WILL BE MADE BY THE ENGINEER AT THE TIME OF CONSTRUCTION.
- THE TOTAL CONCRETE PATCHING AND CRACK REPAIR AREAS INDICATED ON THE DETAILS HAVE BEEN INCREASED TO ACCOUNT FOR ANY FURTHER DETERIORATION THAT MAY HAVE OCCURRED SINCE THE FIELD INSPECTION.

LEGEND:

-  - DENOTES AREAS TO BE REPAIRED AS PER ITEM SP 519
-  - REMOVAL PER SP 202, SEE SHEET X OF X.

PROJECT 71-22-12
DATE: 8/17/23

COMPASS
INFRASTRUCTURE GROUP

DESIGN AGENCY

PATCHING AND PARTIAL REMOVAL DETAILS (2 OF 5)
PROSPECT OVER THE OHIO TURNPIKE
M.P. 182.1

REVISIONS

BY DATE

NO.

CHECKED

IMF

IN CHARGE

DEB

DESIGNED





JFK

DRAWN

JFK

SUMMIT COUNTY

7729820_SV003.dwg; 8/17/23 - 12:07pm



SP 519 REPAIR AREAS		
MEASURED QUANTITY (SQ. FT.)	CONTINGENT QUANTITY (SQ. FT.)	TOTAL (SQ. FT.)
20	3	23
SP 516A AREAS		
MEASURED QUANTITY (FT.)	CONTINGENT QUANTITY (FT.)	TOTAL (FT.)
6	0	6

NOTES:

- THE AREAS OF REPAIR SHOWN ARE APPROXIMATE AND ARE BASED ON A FIELD INSPECTION. FINAL DETERMINATION OF THE AREAS TO BE REPAIRED WILL BE MADE BY THE ENGINEER AT THE TIME OF CONSTRUCTION.
- THE TOTAL CONCRETE PATCHING AND CRACK REPAIR AREAS INDICATED ON THE DETAILS HAVE BEEN INCREASED TO ACCOUNT FOR ANY FURTHER DETERIORATION THAT MAY HAVE OCCURRED SINCE THE FIELD INSPECTION.

LEGEND:



- DENOTES AREAS TO BE REPAIRED AS PER ITEM SP 519






- REMOVAL PER SP 202, SEE SHEET X OF X.

PROJECT 71-22-12	DATE: 8/17/23	PATCHING AND PARTIAL REMOVAL DETAILS (3 OF 5)				SUMMIT COUNTY	M.P. 182.1
		DESIGNED	CHECKED	NO.	REVISIONS	BY	DATE
		JFK	IMF				
		DRAWN	IN CHARGE				
		JFK	DEB				

DESIGN AGENCY

COMPASS
INFRASTRUCTURE GROUP

7729820_SV004.dwg; 8/17/23 - 2:27pm





SP 519 REPAIR AREAS		
MEASURED QUANTITY (SQ. FT.)	CONTINGENT QUANTITY (SQ. FT.)	TOTAL (SQ. FT.)
9.5	0	9.5
SP 516A AREAS		
MEASURED QUANTITY (FT.)	CONTINGENT QUANTITY (FT.)	TOTAL (FT.)
6	0	6

NOTES:





- THE AREAS OF REPAIR SHOWN ARE APPROXIMATE AND ARE BASED ON A FIELD INSPECTION. FINAL DETERMINATION OF THE AREAS TO BE REPAIRED WILL BE MADE BY THE ENGINEER AT THE TIME OF CONSTRUCTION.
- THE TOTAL CONCRETE PATCHING AND CRACK REPAIR AREAS INDICATED ON THE DETAILS HAVE BEEN INCREASED TO ACCOUNT FOR ANY FURTHER DETERIORATION THAT MAY HAVE OCCURRED SINCE THE FIELD INSPECTION.

LEGEND:

-  - DENOTES AREAS TO BE REPAIRED AS PER ITEM SP 519
-  - REMOVAL PER SP 202, SEE SHEET X OF X.

<div><div><div>XX</div><div>XX</div></div></div>	<div>PROJECT 71-22-12</div> <div>DATE: 8/17/23</div>	<div>PATCHING AND PARTIAL REMOVAL DETAILS (3 OF 5)</div> <div>PROSPECT OVER THE OHIO TURNPIKE</div> <div>SUMMIT COUNTY</div> <div>M.P. 182.1</div>	DESIGN AGENCY			
			COMPASS			
			INFRASTRUCTURE GROUP			
						
			REVISIONS			
			BY DATE			
			NO			
			CHECKED			
			IMF			
			IN CHARGE			
			JFK			
			DESIGNED			
			JFK			
			DRAWN			
			JFK			
			DEB			

7729820_SV005.dwg; 8/18/23 - 3:47pm





SP 519 REPAIR AREAS		
MEASURED QUANTITY (SQ. FT.)	CONTINGENT QUANTITY (SQ. FT.)	TOTAL (SQ. FT.)
61	0	61
SP 516A AREAS		
MEASURED QUANTITY (FT.)	CONTINGENT QUANTITY (FT.)	TOTAL (FT.)
23	0	23

NOTES:

- THE AREAS OF REPAIR SHOWN ARE APPROXIMATE AND ARE BASED ON A FIELD INSPECTION. FINAL DETERMINATION OF THE AREAS TO BE REPAIRED WILL BE MADE BY THE ENGINEER AT THE TIME OF CONSTRUCTION.
- THE TOTAL CONCRETE PATCHING AND CRACK REPAIR AREAS INDICATED ON THE DETAILS HAVE BEEN INCREASED TO ACCOUNT FOR ANY FURTHER DETERIORATION THAT MAY HAVE OCCURRED SINCE THE FIELD INSPECTION.

LEGEND:

-  - DENOTES AREAS TO BE REPAIRED AS PER ITEM SP 519
-  - REMOVAL PER SP 202, SEE SHEET X OF X.